STATE OF: PENNSYLVANIA COUNTY OF: CENTRE

ON THIS THE\_\_\_\_\_DAY OF \_\_\_\_\_\_, 2019 THE UNDERSIGNED OWNER PERSONALLY APPEARED BEFORE ME AND CERTIFIED THAT THEY WERE THE OWNERS OF THE PROPERTIES SHOWN ON THIS PLAN AND ACKNOWLEDGE THE SAME TO BE THEIR ACT AND PLAN AND DESIGNS THE SAME TO BE RECORDED AS SUCH ACCORDING TO THE LAW.

WITNESS MY HAND AND SEAL, THIS DATE

## TOWNSHIP PLANNING COMMISSION

FERGUSON TOWNSHIP PLANNING COMMISSION APPROVED

TOWNSHIP SUPERVISORS

FERGUSON TOWNSHIP SUPERVISORS APPROVED

## STORMWATER FACILITIES ACKNOWLEDGMENT

MY/OUR HEIRS AND ASSIGNS, ACKNOWLEDGE THE STORMWATER MANAGMENT SYSTEM TO BE A PERMANENT FACILITY WHICH CAN BE ALTERED OR REMOVED ONLY AFTER APPROVAL OF A REVISED PLAN BY THE FERGUSON TOWNSHIP BOARD OF SUPERVISORS AND THAT THE STORMWATER MANAGE-MENT SYSTEM IS MAINTAINED IN ACCORDANCE WITH THE RECORDED STORMWATER MANAGEMENT OWNERSHIP AND MAINTENANCE AGREEMENT (RB \_\_\_\_\_ PG. \_\_\_\_)

## TOWNSHIP ENGINEER STORMWATER CERTIFICATION

THIS STORMWATER MANAGEMENT PLAN IN ACCORDANCE WITH THE DESIGN STANDARDS AND CRITERIA OF THE FERGUSON TOWNSHIP STORMWATER MANGEMENT ORDINANCE.

## STORMWATER CERTIFICATION

THAT THE STORMWATER MANAGEMENT PLAN MEETS ALL DESIGN STANDARDS AND CRITERIA OF THE FERGUSON TOWNSHIP STORMWATER MAGANGEMENT ORDINANCE.

## DESIGN ENGINEER CERTIFICATION

THAT THIS LAND DEVELOPMENT MEETS ALL DESIGN REQUIREMENTS OF THE SUBDIVISION AND LAND DEVELOPMENT ORDINANCE, ZONING ORDINANCE AND ALL OTHER APPLICABLE CHAPTERS OF THE FERGUSON TOWNSHIP CODE.

## FIRE MARSHALL CERTIFICATION

I HAVE REVIEWED AND HEREBY CERTIFY THAT THE LOCATION OF FIRE LANES AND FIRE HYDRANTS SHOWN ON THIS PLAN ARE ADEQUATE.

FIRE MARSHALL

RECORDER OF DEEDS

RECORDED IN THE OFFICE OF THE RECORDER OF DEEDS, CENTRE COUNTY, PENNSYLVANIA, IN PLAN BOOK\_\_\_\_\_\_, PAGE\_\_\_\_\_ THIS THE \_\_\_\_\_DAY OF \_\_\_\_\_\_\_, 20\_\_\_\_\_.

RECORDER OF DEEDS

## ZONING APPLICATION DATE

ZONING APPLICATION DATE FOR THIS LAND DEVELOPMENT PLAN:

DATE OF APPLICATION

## RECORD PLAN

THIIS RECORD PLAN CONFORMS WITH THE PLAN RECEIVING FINAL APPROVAL BY THE FERGUSON TOWNSHIP BOARD OF \_\_\_\_, ALL IMPROVEMENTS ARE SUPERVISORS ON \_\_\_\_\_ OR WILL BE INSTALLED IN ACCORDANCE WITH SUCH PLAN IN A MANNER AND TIME SO SPECIFIED THEREIN. (CHAPTER 22, SECTION 403.Q)

## PROJECT NARRATIVE:

WHITEHALL ROAD REGIONAL PARK PHASE 1 INCLUDES THE SITE LAYOUT. GRADING. UTILITY INSTALLATION. AND STORMWATER MANAGEMENT FOR APPROXIMATELY 54.20 ACRES OF THE 100 ACRE PROPERTY. THIS PROJECT WILL PROVIDE THE FOLLOWING AMENITIES: 4 RECTANGULAR GRASS PLAYING FIELDS (TWO OF THE FIELDS ARE DESIGNED WITH SYNTHETIC TURF AS AN ALTERNATE), TWO GRASS PRACTICE FIELDS, ALL SEASON PAVILION (CONCESSIONS, RESTROOMS, GATHERING AREA), PLAYGROUND, PARK STORAGE BUILDING, GRAVEL TRAIL NETWORK, PAVED ENTRANCE DRIVEWAY, CONCRETE SIDEWALKS, AND TWO PARKING LOTS AND LANDSCAPING. THERE IS AN EXISTING WOODED AREA THAT WILL BE RETAINED ON THE SITE. STORMWATER MANAGEMENT WILL CONSIST OF FOUR PRIMARY STORMWATER MANAGEMENT AREAS AND NUMEROUS VEGETATED SWALES, RAIN GARDENS, AND UNDERDRAINS THROUGHOUT THE PARK. THE GRAVEL WALKING TRAIL IS OVER 2 MILES IN LENGTH AND LOCATED AROUND THE PERIMETER AND THROUGHOUT THE PARK. AND WILL ALSO PROVIDE A FUTURE EXTENSION TO THE MUSSER GAP TRAIL NETWORK. FUTURE PHASES FOR WHITEHALL ROAD REGIONAL PARK WILL REQUIRE SUBSEQUENT LAND DEVELOPMENT REVIEW AND APPROVAL BY FERGUSON TOWNSHIP.

# FINAL LAND DEVELOPMENT PLAN

# WHITEHALL ROAD REGIONAL PARK PHASE 1 LOCATED IN

FERGUSON TOWNSHIP, CENTRE COUNTY, PENNSYLVANIA JUNE 6, 2019

# LOCATION **SCALE** LOCATION MAP

1. SITE INFORMATION:

SITE INFORMATION

A. OWNERS OF RECORD: THE CENTRE REGION COUNCIL OF GOVERNMENTS AND THE TOWNSHIP OF FERGUSON

B. DEVELOPER:

CENTRE REGION PARKS & RECREATION AUTHORITY

2463 GATEWAY DRIVE SUITE 1 STATE COLLEGE, PA 16801

2463 GATEWAY DRIVE SUITE 3

STATE COLLEGE, PA 16801

Serving the Borough of State College and the Townships of College, Ferguson, Harris, and Patton.

SCALE: 1"=2000'

2000

4000 FEET

1954 BLUE COURSE DRIVE EXTENSION C. SITE ADDRESS: STATE COLLEGE, PA 16801

24-004-,094G,0000-D. TAX PARCEL NO.:

E. DEED REFERENCE DB 2143 PG 30 F. ZONING: RA - RURAL AGRICULTURAL

G. SITE USE EXISTING: FOLLOW FARMLAND

H. SITE USE PROPOSED: REGIONAL PLACE OF ASSEMBLY - REGIONAL PARKLANDS PRIMARY USE: REGIONAL PARKLANDS

100.00 ACRES (4,356,009 SF) J. BUILDING SETBACKS: EXISTING: (FARMLAND):

> FRONT: 50° SIDE: 100'

**REAR: 75'** 

PROPOSED: (REGIONAL PLACE OF ASSEMBLY):

FRONT: 20° SIDE: 30'

**REAR: 50'** K. BUILDING HEIGHTS:

EXISTING: NONE

ALLOWABLE: 40'-0" (EXCEPTION-LIGHTING STRUCTURES FOR RECREATIONAL PLAY)

L. BUILDING COVERAGE: EXISTING: 0 SF (0.0%) PROPOSED: 5,390 SF (0.12%)

ALLOWABLE: 30% OF LOT COVERAGE FOR PRIMARY, ADJUNCT, AND ACCESSORY STRUCTURES

M. IMPERVIOUS COVERAGE: EXISTING: 0 SF (0.0%) PROPOSED: 11.77 AC (11.8%) ALLOWABLE: N/A

2. PARKING INFORMATION

D. SURFACE:

A. REQUIRED: 145 SPACES

B. CALCULATIONS: SEE TABLE BELOW C. PROPOSED: 473 SPACES (14 HC) TOTAL: 487 SPACES

ASPHALT PAVEMENT & DRIVEWAY SURFACE AGGREGATE

## PARKING ANALYSIS TABLE

ACTIVITY/STRUCTURE	PARKING REQUIREMENTS	PARKING SPACES REQUIRED
TRAILHEAD PARKING	NONE	15
4 RECTANGULAR FIELDS	25 SPACES/EVENT	100
1 PLAYGROUND	NONE	15
1 PAVILION	1 SPACE/PICNIC TABLE	15
PARK STORAGE BUILDING	NONE	0
TOTAL		145

3. SOILS INFORMATION

Hab - HAGERSTOWN SILT LOAM HcB - HAGERSTOWN SILTY CLAY LOAM

Hub - Hublersburg Silt Loam OhB - OPEQUON-HAGERSTOWN COMPLEX

## SHEET INDEX:

 COVER SHEET - PHASING PLAN \* C102 - EXISTING CONDITIONS \* C103 - OVERALL SITE PLAN C103.1 - SITE PLAN 1 C103.2 - SITE PLAN 2 C103.3 - SITE PLAN 3

C103.4 - SITE PLAN 4 \* C104 - OVERALL GRADING PLAN C104.1 - GRADING PLAN

C104.2 - GRADING PLAN 2 C104.3 - GRADING PLAN 3 C104.4 - GRADING PLAN 4 C104.5 - SITE SECTIONS

C104.6 - SITE SECTIONS \* C105 - OVERALL SITE UTILITY PLAN C105.1 - SITE UTILITY PLAN 1

C105.2 - SITE UTILITY PLAN 2 C105.3 - SITE UTILITY PLAN 3 C105.4 - SITE UTILITY PLAN 4

C105.5 - SITE UTILITY PROFILE \* C106 - OVERALL POST CONSTRUCTION STORMWATER MANAGEMENT C106.1 - POST CONSTRUCTION STORMWATER MANAGEMENT PLAN 1 C106.2 - POST CONSTRUCTION STORMWATER MANAGEMENT PLAN 2

C106.3 - POST CONSTRUCTION STORMWATER MANAGEMENT PLAN 3 C106.4 - POST CONSTRUCTION STORMWATER MANAGEMENT PLAN 4 - EROSION AND SEDIMENTATION CONTROL PLAN

C108.1 - SITE CONSTRUCTION DETAILS C108.2 - SITE CONSTRUCTION DETAILS C108.3 - SITE UTILITY DETAILS

C108.4 - SITE UTILITY DETAILS C108.5 - POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS C108.6 - POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS C108.7 - POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS

C108.8 - EROSION AND SEDIMENTATION CONTROL DETAILS C108.9 - EROSION AND SEDIMENTATION CONTROL DETAILS

- LANDSCAPING PLAN \* L100 L100.1 - SEEDING PLAN

- LANDSCAPING PLANTING LIST - LANDSCAPING DETAILS

- SITE PLAN ELECTRICAL - SITE PLAN LIGHTING CALCULATIONS

- SITE PLAN LIGHTING CALCULATIONS - DETAILS ELECTRICAL

\* DENOTES PLANS TO BE RECORDED.

4. ALL TREES AND SHRUBS SHALL BE PLANTED IN ACCORDANCE WITH THE "GUIDE TO PLANTING IN FERGUSON TOWNSHIP." 5. ALL INFRASTRUCTURE RELATED TO PUBLIC SEWER SHALL BE LOCATED ENTIRELY WITHIN THE CENTRE REGION REGIONAL GROWTH BOUNDARY AND SEWER SERVICE AREA.

6. SOIL INFILTRATION RATES WERE OBTAINED THROUGH FIELD TESTING AND ANALYSIS CONDUCTED BY CMT LABORATORIES AND SUMMARIZED IN A REPORT DATED SEPTEMBER 10, 2019.

7. FOR INFORMATION ON STORMWATER MANAGEMENT REFER TO REPORT TITLED WHITEHALL ROAD REGIONAL PARK

POST-CONSTRUCTION STORMWATER MANAGEMENT PREPARED BY STAHL SHEAFFER ENGINEERING, LLC DATED JUNE 6, 2019. 8. FOR INFORMATION ON EROSION AND SEDIMENT CONTROL PLAN REFER TO REPORT TITLED WHITEHALL ROAD REGIONAL PARK EROSION AND SEDIMENT CONTROL NARRATIVE PREPARED BY STAHL SHEAFFER ENGINEERING, LLC DATED JUNE 6, 2019.

9. AS-BUILT PLANS ARE TO BE SUBMITTED TO THE TOWNSHIP IN ACCORDANCE WITH REQUIREMENTS AND REQUIRED PHOTO DOCUMENTATION OF CRITICAL STAGES OF CONSTRUCTION TO INCLUDE DOCUMENTATION OF CONSTRUCTION MEANS, THE INFILTRATION SURFACE PRIOR TO PLACEMENT OF AMENDED SOIL. ALSO AS-BUILT INFILTRATION TESTING IS TO BE PERFORMED AND RESULTS INCLUDED WITH THE AS-BUILT SUBMISSION. AS-BUILT INFILTRATION TESTING IS TO BE PERFORMED IN ACCORDANCE WITH 26-304.F, AND ANY CLARIFICATIONS PROVIDED AT THE PRECONSTRUCTION MEETING.

10. ON APRIL 15, 2013, THE TOWNSHIP BOARD OF SUPERVISORS APPROVED A CONDITIONAL USE FOR THE WHITEHALL ROAD REGIONAL PARK PROJECT TO BE ZONED AS A REGIONAL PACE OF ASSEMBLY.

11. ON FEBRUARY 25, 2014, THE TOWNSHIP ZONING HEARING BOARD APPROVED A VARIANCE FOR THE WHITEHALL ROAD REGIONA PARK PROJECT TO ELIMINATE THE REQUIREMENT FOR RAISED PARKING ISLANDS WITHIN THE PARKING LOTS. THE CURRENT LAND DEVELOPMENT PLAN AS SUBMITTED ON JUNE 6, 2019 WILL NOT APPLY THIS VARIANCE TO THE PROJECT, THUS THE PARKING ISLANDS WILL BE CONSTRUCTED AS REQUIRED PER ORDINANCE.

12. THE PARKING LOT SURFACE MATERIALS INCLUDE A COMBINATION OF ASPHALT PAVED SURFACES (OUTER PERIMETER) AND COMPACTED AGGREGATE (INTERIOR). THE STORMWATER MANAGEMENT PLAN WAS DESIGNED FOR FUTURE PAVING OF THE ENTIRE PARKING LOT SURFACE.

13. PRIMARY ACCESS TO THE SITE IS PROVIDED BY THE 90' RIGHT-OF-WAY (FUTURE BLUE COURSE DRIVE EXTENSION). UNTIL SUCH TIME BLUE COURSE DRIVE EXRENSION IS CONSTRUCTED, THE EXISTING FARM LANES SHALL BE USED TO ACCESS THE PROPERTY SUBJECT TO AGREEMENT AMONGST THE OWNERS, AS RECORDED IN CENTRE COUNTY COURTHOUSE RB 2005 PG 643.

## ADDITIONAL SITE FEATURES & PLANNING NOTES:

1. THERE ARE NO WETLANDS ON THE PROPERTY ACCORDING TO THE NATIONAL WETLAND INVENTORY MAPPING (U.S. FISH AND WILDLIFE SERVICE), CURRENT AS OF JANUARY 2019.

2. NO PORTION OF THE SITE IS LOCATED WITHIN A FLOODPLAIN IN ACCORDANCE WITH FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) MAP # 42027C0638F, FERGUSON TOWNSHIP, DATED MAY 4, 2009. 3. PUBLIC WATER SUPPLY FOR THE SITE WILL BE PROVIDED BY THE STATE COLLEGE BOROUGH WATER AUTHORITY. WATER LINES

OUTSIDE OF THE EXTENDED BLUE COURSE DRIVE RIGHT-OF-WAY WILL BE OWNED AND MAINTAINED BY THE OWNER. 4. PUBLIC SANITARY SEWER SERVICE FOR THE SITE WILL BE PROVIDED BY THE UNIVERSITY AREA JOINT AUTHORITY. ALL SANITARY SEWER MAIN LINES ON THE SITE WILL BE OWNED AND MAINTAINED BY THE UNIVERSITY AREA JOINT AUTHORITY AND

LOCATED WITHIN A 20' DEDICATED SEWER EASEMENT 5. A SANITARY SEWER PUMP STATION WILL BE REQUIRED TO SERVICE THE PARK AND IS LOCATED ON THE EASTERN SIDE OF THE SITE. THE PUMP STATION CONSTRUCTION AND ALL ASSOCIATED PERMITTING HAS BEEN PROVIDED UNDER A PREVIOUSLY APPROVED LAND DEVELOPMENT PLAN (THE COTTAGES AT STATE COLLEGE) LOCATED ON THE ADJACENT PROPERTY LOCATED

6. NO STRUCTURES, GRADING, OR LANDSCAPING MAY BE PLACED WITHIN STORMWATER MANAGEMENT AREAS WHICH WOULD IMPEDE STORMWATER FLOW OR FUNCTION OF STORMWATER MANAGEMENT FACILITIES, OR ALTER THE FLOW'S COURSE.

7. PRIMARY ACCESS TO THE SITE IS PROVIDED BY THE 90' RIGHT-OF-WAY (FUTURE BLUE COURSE DRIVE EXTENSION). UNTIL SUCH TIME THAT BLUE COURSE DRIVE EXTENSION IS CONSTRUCTED (ANTICIPATED DATE: FALL 2019), THE EXISTING FARM LANES SHALL BE USED TO ACCESS THE SITE SUBJECT TO AGREEMENT AMONGST THE OWNERS, AS RECORDED IN CENTRE COUNTY COURTHOUSE DEED BOOK 2005, PAGE 643.

## SURVEY DATA:

NORTHEAST OF THE SITE.

1. SURVEY INFORMATION OBTAINED FROM DRAWING ENTITLED "EXISTING CONDITIONS AND TOPOGRAPHIC SURVEY" DATED 6/25/07, DRAWING # D-8725 PROVIDED BY SWEETLAND ENGINEERING & ASSOCIATES, INC. 24 HILL STREET SAYRE, PA 18840. PHONE: 570-882-9777. ADDITIONAL SURVEY INFORMATION PROVIDED BY STAHL SHEAFFER ENGINEERING, LLC, DATED 7/2/12. 301 SCIENCE PARK ROAD, SUITE 333, STATE COLLEGE, PA 16803. CONTOURS SHOWN ARE ONE FOOT INTERVALS.

2. HORIZONTAL DATUM IS PENNSYLVANIA NORTH ZONE STATE PLANE COORDINATES, NORTH AMERICAN DATUM OF 1983 (PA NAD83) U.S. FEET.

3. VERTICAL DATUM IS THE NATIONAL GEODETIC VERTICAL DATUM OF 1929 (NGVD 29). 4. THE BENCHMARK FOR THIS PROJECT IS A 3/4" REBAR SET AT THE NORTHEAST CORNER OF TAX PARCEL

PT# 103, 3/4" REBAR, NORTHING: 216838.3402, EASTING: 1935739.5284, ELEVATION: 1094.6098

APARTMENTS. LLC 24-004-,076A,0000-DB 2209 PG 719 15.18 ACRES STATE COLLEGE APARTMENTS, LLC 24-4-76B-0000 APARTMENTS. LLC DB 2209 PG 719 2.29 ACRES DB 2209 PG 719 BLUE COURSE DRIVE 28.37 ACRES RIGHT OF WAY STATE COLLEGE EXTENSION BOROUGH AUTHORITY 24-004-,093F,0000-58.89 ACRES CENTRE REGION COG & THE TOWNSHIP OF FERGUSON 24-004-.094G.0000-DB 2143 PG 30 100.00 ACRES PHASE 1 AND STORMWATER MAINTENANCE EASEMENT (HATCHED AREA) PENNSYLVANIA STATE UNIVERSITY 24-004-,094-,0000-DB 2210 PG 548 192.07 ACRES - MCWILLIAMS. GALEN G & KATHERINE M APPROXIMATE 24-004-,091-,0000-PROPERTY LINE (TYP.) DB 2180 PG 3 123.00 ACRES SCALE SITE KEY MAP

STATE COLLEGE -

# CALL BEFORE YOU DIG!

400

800 FEET

PENNSYLVANIA LAW REQUIRES 3 WORKING DAYS NOTICE FOR **CONSTRUCTION PHASE AND 10 WORKING** DAYS IN DESIGN STAGE - STOP CALL

PA1 SERIAL # DATE SERIAL # 20131482036 05/28/2013 1-800-242-1776

SCALE: 1"=400'

## ACT 172 UTILITY INFORMATION

- 1. PENNSYLVANIA LAW REQUIRES 3 WORKING DAYS NOTICE FOR CONSTRUCTION PHASE AND 10 WORKING DAYS IN DESIGN STAGE - BEFORE YOU DIG CALL THE PA ONE CALL SYSTEM TELEPHONE NUMBER 1-800-242-1776. PA ONE CALL SERIAL NO. 20131482036.
- 2. ALL UTILITY INFORMATION AND LOCATIONS SHOWN ON THIS PLAN SHOULD BE CONSIDERED APPROXIMATE. ALL UTILITY LOCATIONS SHOULD BE VERIFIED IN THE FIELD. CONTRACTOR SHALL NOTIFY PA ONE CALL (1-800-242-1776) AT LEAST 3 DAYS PRIOR TO ANY EXCAVATION.
- \* ELECTRIC WEST PENN POWER 2800 E. COLLEGE AVE., STATE COLLEGE, PA 16801 (814) 231-5338
- \* SANITARY SEWER UNIVERSITY AREA JOINT AUTHORITY 1576 SPRING VALLEY RD, STATE COLLEGE, PA 16801 (814) 238-5361
- \* TELEPHONE VERIZON 224 S. ALLEN STREET, STATE COLLEGE, PA 16801 (814) 231-6528
- (814) 238-6766 \* GAS - COLUMBIA GAS OF PA

2550 CAROLEAN DRIVE, STATE COLLEGE, PA 16801

(814) 278-5842

\* WATER - STATE COLLEGE BOROUGH WATER AUTHORITY

1201 WEST BRANCH ROAD, STATE COLLEGE, PA 16801

- \* TV/CABLE COMCAST 60 DECIBEL ROAD, SUITE 101, STATE COLLEGE, PA 16801 (814) 238-6766
- \* STORM SEWER FERGUSON TOWNSHIP 3147 RESEARCH DRIVE, STATE COLLEGE, PA 16801 (814) 238-4561

Parks & Recreation 2643 Gateway Drive, Suite #1 State College, PA 16801 Phone: (814) 231-3071 Fax: (814) 235-7832 www.crpr.org

**STAHL SHEAFFER** 

FAX: 814-689-1885 WWW.SSE-LLC.COM Fernsler

Hutchinson

301 SCIENCE PARK ROAD, SUITE 333 STATE COLLEGE, PA 16803

PH: 814-689-1562

**521 EAST BEAVER AVENUE** STATE COLLEGE, PA 16801 t: 814-234-6806 f: 814-234-0256 e: fjfaia@aol.com





182 FAIRMOUNT DRIV LEWISBURG, PA 17837 PH: 570-847-9519 brian@bsalandplan.com SSE PROJECT No:

CHECKED BY: REVISIONS SYM DATE DESCRIPTION

SUBMISSIONS


DESCRIPTION TWP. SUBMISSION 1 TWP. SUBMISSION 2

WHITEHALL ROAD REGIONAL PARK PHASE 1


**NOT FOR** CONSTRUCTION>


SHEET NAME **COVER SHEET** 


C100
















































































2643 Gateway Drive, Suite #1 State College, PA 16801 Phone: (814) 231-3071 Fax: (814) 235-7832 www.crpr.org

301 SCIENCE PARK ROAD, SUITE 333 STATE COLLEGE, PA 16803

> WWW.SSE-LLC.COM Fernsler Hutchinson

PH: 814-689-1562 FAX: 814-689-1885

ARCHITECTURE LLC 521 EAST BEAVER AVENUE STATE COLLEGE, PA 16801 t: 814-234-6806 f: 814-234-0256 e: fjfaia@aol.com

PENOENGINEERIN 2746 WEST COLLEGE AVENUE PROJECT NO.: E38095 STATE COLLEGE, PA 16801 © 2018 PENO ENGINEERING, LLI 814-234-7366



SSE PROJECT No:

DRAWN BY: CHECKED BY:

REVISIONS

SYM DATE DESCRIPTION


SUBMISSIONS

DESCRIPTION TWP. SUBMISSION 1 10/02/19 TWP. SUBMISSION 2

WHITEHALL ROAD REGIONAL PARK PHASE 1


<PRELIMINARY NOT FOR CONSTRUCTION>

SITE CONSTRUCTION **DETAILS** 



# SECTIONAL PLAN VIEW OF TYPICAL AND DROP MANHOLES

NOT TO SCALE




1. THE WORD "SANITARY" MUST BE ON THE MANHOLE COVER.

2. PRECAST CONCRETE RINGS ARE REQUIRED ONLY WHERE MANHOLE FRAME AND COVER MUST CONFORM TO GRADE OF STREET. THE TOPS OF ALL WATERTIGHT MANHOLE FRAMES AND COVERS SHALL BE NO LESS THAN (1) FOOT ABOVE GRADE AS DIRECTED BY AUTHORITY, MAX, HEIGHT ADJUSTMENT W/RINGS IS 12".


## MANHOLE FRAME AND COVER INSTALLATION FOR PRECAST CONCRETE MANHOLES

NOT TO SCALE



## TYPICAL MANHOLE SECTION A-A PRECAST BASE AND WALL SECTIONS

NOT TO SCALE



WHEN THE AMOUNT OF FLOW WARRANTS IT.

1. 4" DIAMETER IS THE MINIMUM SIZE, LARGER SIZES WILL BE SPECIFIED BY THE AUTHORITY

- . SLOPE SHALL BE 1/4" PER FOOT UNLESS APPROVED OTHERWISE BY THE AUTHORITY. CLEANOUTS MUST BE INSTALLED EVERY 50' ON 4" PIPE AND EVERY 100' ON 6" PIPE.
- LATERALS SHALL BE LAID IN AGGREGATE CUSHION AND BEDDING, REFER TO STANDARD PIPE TRENCH DETAIL 5. CLEANOUT TERMINAL(S) SHALL HAVE TREATMENT AT RESPECTIVE LOCATION, REFER TO
- DWG. NO.'S 10 & 10A. 6. ALL PIPING MATERIALS INCLUDING TRAPS FOR GRAVITY APPLICATIONS SHALL BE SCHEDULE
- 7. ALL SCHEDULÉ 40 PVC PIPE USED FOR PRESSURE APPLICATIONS MAY BE STAMPED ASTM D2665 BUT MUST ALSO INCLUDE A SECOND NUMBER, EITHER ASTM D1785 OR ASTM F480, WHICH ARE PRESSURE DESIGNATIONS.

40 PVC. ANSI/ASTM D2665.

- WORK MUST BE INSPECTED AND TESTED BEFORE BACKFILLING. THERE IS NO CHARGE FOR ONE-TIME INSPECTION UNLESS THE LATERAL IS
- LONGER THAN 150' AND/OR IF THE PIPE IS MORE THAN 4" IN DIAMETER.

  INSPECTIONS REQUIRING MORE THAN ONE VISIT TO THE SITE WILL BE BILLED AT THE RATE IN EFFECT AT THE TIME OF INSPECTION.


## TYPICAL SANITARY SEWER LATERAL

NOT TO SCALE


NOTE:
USE DOG HOUSE APPLICATION WHEN
CONNECTING INTO EXISTING SANITARY SEWER PRECAST WALL SECTION SET IN CONCRETE FOR INTEGRAL JOINT -- SEAL BETWEEN PIPE AND DOGHOUSE WITH CONCRETE/ HYDRAULIC CEMENT WATERSTOP INTEGRAL PIPE SEAL -4,000 P.S.I. CONCRETE FOR 5'-0" MIN. BASE, FLOW CHANNELS AND DOG HOUSE SEALING 5'-0" MIN. 1'-0" MIN. ALL MONOLITHIC CONCRETE -一ちある。あるののある。根準選手( /3.000 PSI CONC. CRADLE MIDPOINT OF PIPE NO.4 REBAR-12"c. TO c. BOTHWAYS USE ONE MAT IN 8" THICK, OVER - UNDISTURBED EARTH 8" USE TWO MATS TOP AND BOTTOM. 2 INCH MINIMUM COVER. ----6" AASHTO#57 - WATERSTOP BETWEEN BASE AND AGGREGATE PRECAST WALL SECTION BASE THICKNESS 2"-15"PIPE-8" 18"-27"PIPE-12"

30"-UP--DESIGN

## FIELD POURED BASE WITH PRECAST WALL SECTIONS




NOT TO SCALE




## CLEANOUT CONSTRUCTION DETAIL FOR PRIVATE COLLECTION SYSTEM

NOT TO SCALE



## TYPICAL DROP MANHOLE SECTION B-B PRECAST BASE AND WALL SECTIONS

NOT TO SCALE




. IN THE CONSTRUCTION OF LATERALS, THE CONTRACTOR MUST COORDINATE HIS EFFORTS WITH THE AUTHORITY SO AS TO PROVIDE THE PROPER SERVICE TO THE PROPERTY OWNERS. IF IN THE JUDGEMENT OF THE AUTHORITY THE LATERAL CONSTRUCTED BY THE CONTRACTOR DOES NOT PROVIDE ADEQUATE SERVICE TO THE PROPERTY OWNER, THE CONTRACTOR SHALL RECONSTRUCT THE LATERAL TO THE PROPER GRADE AT HIS (CONTRACTOR) EXPENSE. IT IS THE POLICY OF THE AUTHORITY TO PROVIDE BASEMENT SERVICE (LOWEST ELEVATION) TO ALL LOTS.

CONCRETE ENCASE LATERAL FOR A DISTANCE OF 5' ON EITHER SIDE OF A WATER OR STORM SEWER CROSSING. ENCASEMENT SHALL BE 6" MIN AROUND PIPE WITH 3,000 PSI CONCRETE.

## LATERAL AND MARKER DETAIL

NOT TO SCALE



CLEANOUT CONSTRUCTION DETAIL FOR PAVED **AREAS** 

> DETAILS SHOWN ARE UNIVERSITY AREA JOINT AUTHORITY (UAJA) STANDARDS DETAILS. REFER TO UAJA STANDARD SPECIFICATIONS APPENDIX B FOR ADDITIONAL INFORMATION.



Stahl Sheaffer

301 SCIENCE PARK ROAD, SUITE 333 STATE COLLEGE, PA 16803 PH: 814-689-1562 FAX: 814-689-1885 WWW.SSE-LLC.COM

Fernsler

Hutchinson ARCHITECTURE LLC **521 EAST BEAVER AVENUE** STATE COLLEGE, PA 16801 t: 814-234-6806 f: 814-234-0256

e: fjfaia@aol.com







SSE PROJECT No: CHECKED BY: DRAWN BY: REVISIONS

DESCRIPTION

SUBMISSIONS DESCRIPTION

06/07/19 TWP. SUBMISSION 1

10/02/19 TWP. SUBMISSION 2


SYM DATE

WHITEHALL ROAD REGIONAL PARK PHASE 1

<PRELIMINARY NOT FOR CONSTRUCTION>


SHEET NAME

UAJA STANDARD SANITARY SEWER DETAILS



PIPE		TOTAL		AREA OF B	LOCK IN S	QUARE FEE <sup>-</sup>	Γ
SIZE (IN.)	AREA SQ."	FORCE (LBS)	TEE & PLUGS	90° BENDS	45° BENDS	22½° BENDS	11¼° BENDS
4	13	2,900	1.0	1.0	1.0	1.0	1.0
6	29	6,500	1.7	2.3	1.3	1.0	1.0
8	53	12,000	3.0	4.1	2.2	1.2	1.0


CONCRETE THRUST BLOCKS



1. LOCATOR TRACER WIRE AND WARNING TAPE INSTALLED BY CONTRACTOR. 2. 6" OF SCREENINGS AT BOTTOM OF DITCH MUST BE INSTALLED BY CONTRACTOR PRIOR TO INSTALLATION OF THE 3. CONTRACTOR MUST INSTALL MINIMUM OF 12" OF SCREENINGS OVER TOP OF GAS SERVICE AT TIME OF INSTALLATION. 4. WARNING TAPE MUST BE INSTALLED BY CONTRACTOR 12" BELOW GRADE. 5. AT LEAST 3 WORKING DAYS BEFORE YOU DIG CALL 1-800-242-1776 FOR LOCATION OF UTILITIES. 6. IF YOU HIT A GAS LINE, IMMEDIATELY CALL COLUMBIA GAS.

GAS SERVICE TRENCH

## 4", 6" or 8" DOMESTIC & FIRE LINE COMBINATION METER PIT- Using Omni Meter




\*4", 6" or 8" SENSUS OMNI F2 Meter to be purchased by owner with delivery to the job site and installation by owner. Authority personnel will inspect the installation.


## NOTES:

1. Mega-lug glands must be used on all fittings and valves. 2. Concrete Thrust Blocks must be used on all underground bends & tee's.


WATER METER PIT




<u>IRRIGATION HOSE BIB</u>




TYPICAL GATE VALVE AND VALVE BOX DETAIL




WATERLINE TRENCH IN NON-PAVED AREAS



WATERLINE TRENCH IN PAVED AREAS



FIRE HYDRANT



Parks & Recreation 2643 Gateway Drive, Suite #1 State College, PA 16801 Phone: (814) 231-3071 Fax: (814) 235-7832 www.ćrpr.org

STAHL SHEAFFER 301 SCIENCE PARK ROAD, SUITE 333

STATE COLLEGE, PA 16803 PH: 814-689-1562 FAX: 814-689-1885 WWW.SSE-LLC.COM 1 Fernsler

Hutchinson ARCHITECTURE LLC 521 EAST BEAVER AVENUE STATE COLLEGE, PA 16801 t: 814-234-6806 f: 814-234-0256 e: fjfaia@aol.com





LEWISBURG, PA 17837	
PH: 570-847-9519	
brian@bsalandplan.com	
SE PROJECT No:	16-248


DRAWN BY:		CHECKED BY:		
REVIS	IONS ATE	DESCRIPTION		


**SUBMISSIONS** 06/07/19 TWP. SUBMISSION 1 10/02/19 TWP. SUBMISSION 2


# WHITEHALL ROAD REGIONAL PARK PHASE 1

<PRELIMINARY **NOT FOR** CONSTRUCTION>

SITE UTILITY DETAILS








N.T.S.

RAIN GARDEN TYPICAL DETAIL N.T.S.



STORMWATER BASIN 2 DETAIL N.T.S.

√ 1180.70

STORMWATER BASIN 4 DETAIL

15"Ø HDPE @ 4% ——— INV:1179.00

16' APART

15" YARD DRAIN ——

TOP OF BANK = 1184.50 FT.

4" PERFORATED PVC UNDERDRAIN @ 0.00% ———


INV. 1179.00. CONNECT TO OUTLET STRUCTURE.


N.T.S.

BASIN BOTTOM 1180.50

EMERGENCY SPILLWAY = 1183.50 FT.

CLEANOUTS -





SEEDING AS DIRECTED ON —

LANDSCAPING PLAN

STORMWATER BASIN 2 OUTLET STRUCTURE N.T.S.

BY 12" (MIN.) IN ALL DIRECTIONS

\_\_\_ REMOVE EXISTING TOPSOIL AND/OR SUBGRADE

— SCARIFY EXISTING SUBSOIL PRIOR TO

PLACING MODIFIED TOPSOIL MIXTURE

1. SEE SUMMARY TABLE FOR BASIN DETAILS

SPECIFIED ON DETAILS.

1. MODIFIED TOPSOIL MIX SHALL BE FREE OF CLAY AND NATIVE SOIL CLUMPS LARGER THAN 2" IN SIZE, AND SHALL BE THOROUGHLY MIXED TO CREATE A HOMOGENEOUS STATE OF SOIL AND

2. THE USE OF STRIPPED TOPSOIL FROM THE SITE IS ACCEPTABLE, PROVIDED THE TOPSOIL IS NOT COMPACTED WHEN PLACING IN A STOCKPILE FOR TEMPORARY STORAGE. THE CONDITION


OF THE TOPSOIL MATERIALS SHALL BE INSPECTED PRIOR TO MIXING AND FOLLOWING MIXING BUT PRIOR TO INFILTRATION TESTING.

3. MODIFIED SOIL MUST BE TESTED BY A QUALIFIED PROFESSIONAL FOR INFILTRATION CAPABILITIES PRIOR TO PLACEMENT. THE INFILTRATION RATES OF THE MODIFIED SOILS SHALL


MEET A MINIMUM OF 1.0 IN/HR, WITH A MAXIMUM RATE OF 3.0 IN/HR.

AND REPLACE WITH MODIFIED SOIL/PLANTING MIX

(70% TOPSOIL, 30% SHREDDED MULCH) IN DEPTH



1. SEE BASIN CHART FOR DIMENSIONS FOR EMERGENCY SPILLWAYS. 2. FOR SPILLWAYS THAT CROSS OR ARE LOCATED WITHIN AREAS OF WALKWAYS AND/OR DRIVING SURFACES, THE SPILLWAY BANKS SHALL NOT EXCEED 5%. STORMWATER BASIN TYPICAL SPILLWAY CHART & DETAIL



STORMWATER BASIN 3 OUTLET STRUCTURE N.T.S.

		Stormwater Basin / Rain Garden Details															
	Basin Floor Elevation (sf)	Top of Outlet Structure Elev.	Underdrain Elevation	Basin Discharge Pipe - Size	Basin Discharge Pipe - Upstream Inv.	Outlet Structure Type/Size	Basin Bottom Area (sf)	Basin Top Area (sf)	Total Basin Storage (cf)	Basin Storage (Below Outlet Structure) (cf)	Top of Storage Elev. (ft)	Total BMP Depth (ft)		Spillway Width (ft)	Spillway Length (ft)	Modified Top Soil Depth	Infiltration
Basin 1	1207.00	1207.50	1205.00	6"	1205.00	Domed Yard Drain - 6"	3,000	4,550	8,494	1,586	1209.25	2.25	1208.40	10	35	12"	Yes
Basin 2	1201.00	1201.50	1199.00	12"	1198.50	2'x2'	86,000	97,700	89,513	21,670	1203.00	2.00	1202.50	10	40	N/A	
Basin 3	1172.50	1174.00	1171.00	18"	1171.00	2'x4'	5,270	21,600	36,618	12,693	1175.50	3.00	1174.45	10	70	12"	Yes
Basin 4	1180.50	1180.70	1179.00	15"	1179.00	Domed Yard Drain - 15"	1,050	22,200	51,583	811	1184.50	4.00	1183.50	10	45	12"	
Rain Garden 1	1181.50	N/A	N/A	N/A	N/A	N/A	2,342	4,420	5,010	2,275	1183.00	1.50	1182.30	10	30	24"	Yes
Rain Garden 2	1216.50	1216.50	1215.00	24"	1213.00	2'x2'	3,110	7,900	5,868	0	1217.60	1.10	1217.30	5	10	12"	
Rain Garden 3	1222.00	1222.00	1220.25	12"	1220.25	Domed Yard Drain - 12"	607	2,800	2,726	0	1223.60	1.60	1222.90	5	20	12"	
Rain Garden 4	1221.50	1221.50	1220.25	6"	1220.25	Domed Yard Drain - 6"	10	7,450	5,390	N/A	1223.55	2.05	1222.65	5	10	12"	
Rain Garden 5	1221.00	N/A	1220.25	N/A	N/A	N/A	931	4,200	5,066	N/A	1223.00	2.00	1222.00	5	15	12"	

Recreation 2643 Gateway Drive, Suite #1 State College, PA 16801 Phone: (814) 231-3071 Fax: (814) 235-7832 www.ćrpr.org

STAHLSHEAFFER 301 SCIENCE PARK ROAD, SUITE 333 STATE COLLEGE, PA 16803


> Fernsler Hutchinson ARCHITECTURE LLC 521 EAST BEAVER AVENUE STATE COLLEGE, PA 16801 t: 814-234-6806

PH: 814-689-1562

FAX: 814-689-1885

WWW.SSE-LLC.COM





182 FAIRMOUNT DRIVE LEWISBURG, PA 17837 PH: 570-847-9519 brian@bsalandplan.com

SSE PROJECT No: DRAWN BY: CHECKED BY: REVISIONS SYM DATE DESCRIPTION

SUBMISSIONS

DATE DESCRIPTION


06/07/19 TWP. SUBMISSION 1

10/02/19 TWP. SUBMISSION 2


WHITEHALL ROAD REGIONAL PARK PHASE 1

<PRELIMINARY NOT FOR CONSTRUCTION>


POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS








PARKING LOT SWALE & UNDERDRAIN DETAIL AT LIGHT POLE




NOTES: 1. PROVIDE OPEN GRATE TOP WHERE NOTED ON PLANS. 2. PROVIDE FLAT SCREW TOP IN PLAYING FIELD AREAS. 3. IN PAVED AREAS, PROVIDE TRAFFIC RATED CLEANOUT TOP ENCASED IN 4" CONCRETE ALL SIDES.

CLEANOUT DETAIL
N.T.S.



CONCRETE ANTI-SEEP COLLAR DETAIL
N.T.S.



		SECTION A-A
3Do	N.T.S.	
PIPE		
PIPE END SECTION		
GEO	OTEXTILE	
SECTION B-B		
N.T.S.		

NOTES:	
1. ROCK WILL BE PLACED TO FULL COURSE THICKNESS IN ONE CONTINUOUS OPERATION TO PREVENT SEGREGATION OF MATERIALS. INDIVIDUAL ROCKS MAY BE REARRANGED, AND VOIDS FILLED WITH HAND PLACED SMALLER ROCK, TO ACHEIVE A UNIFORM ROCK BLANKET.	
2. NO ROCK PIECES SHALL HAVE A LENGTH EXCEEDING THREE TIMES ITS WIDTH OR DEPTH.	
3. ROCK SHALL BE ANGULAR, CRUSHED AND HAVE A UNIT WEIGHT OF 165 LBS./C.F.	

RIPRAP APRON	W	L	SIZE OF	MIN ROCK	FLOW
NO.	(FT)	(FT)	ROCK	DEPTH (D)	(CFS)
1	12.5	10	R-3	18"	6
1.1	8.5	6	R-3	18"	3
1.2	8.5	6	R-3	18"	3
2	32.5	28	R-6	36"	52
3	32.5	28	R-6	36"	52
4	30	24	R-6	36"	47
5	11	8	R-3	18"	5
6	11	8	R-3	18"	5
7	15	10	R-3	18"	7
8	15	10	R-3	18"	7
9	20	16	R-4	18"	15
10	11.75	8	R-3	18"	3
11	11.75	8	R-3	18"	3
12	24	18	R-4	18"	30
13	10.5	8	R-3	18"	5
14	9	6	R-3	18"	4
14.1	9	6	R-3	18"	4
15	9	6	R-3	18"	3
16	9	6	R-3	18"	3
17	7.5	6	R-3	18"	3
18	14	12	R-4	18"	7

RIP-RAP APRON DETAIL
N.T.S.

2643 Gateway Drive, Suite #1 State College, PA 16801 Phone: (814) 231-3071 Fax: (814) 235-7832 www.ćrpr.org

301 SCIENCE PARK ROAD, SUITE 333 STATE COLLEGE, PA 16803 PH: 814-689-1562

> Fernsler Hutchinson ARCHITECTURE LLC 521 EAST BEAVER AVENUE STATE COLLEGE, PA 16801 t: 814-234-6806 f: 814-234-0256 e: fjfaia@aol.com

FAX: 814-689-1885 WWW.SSE-LLC.COM





SSE PROJECT No: CHECKED BY: DRAWN BY:

REVISIONS SYM DATE DESCRIPTION


SUBMISSIONS

06/07/19 TWP. SUBMISSION 1 10/02/19 TWP. SUBMISSION 2

WHITEHALL ROAD REGIONAL PARK PHASE 1


<PRELIMINARY NOT FOR CONSTRUCTION>


POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS





LANDSCAPED FINISHED SURFACE (SEE DETAILS) PAVED FINISHED SURFACE (SEE DETAILS) TOPSOIL (DEPTH AS REQ'D) PENNDOT 2A STONE BACKFILL SUITABLE FILL MATERIAL MATERIAL COMPACTED IN 12" LIFTS TO 95% MODIFIED PROCTOR COMPACTED IN 12" LIFTS TO STANDARDS 95% MODIFIED PROCTOR STANDARDS -HDPE STORM SEWER, CORRUGATED, SMOOTH-LINED INTERIOR PIPE BEDDING & BACKFILL (2A MODIFIED OR 2RC STONE COMPACTED IN LIFTS)

STORM SEWER (HDPF) INSTALLATION DETAIL









YARD DRAIN AND GRATE

## STORMWATER FACILITIES CONSTRUCTION NOTES

1. Special protection measures should be taken to identify the bottoms of stormwater basins and rain garden areas to avoid tracking of heavy equipment and soil compaction during the stripping process.

Protecting these areas with temporary orange construction fence during earthwork activities is required to avoid compaction of soils and negatively impacting the infiltration capabilities of the stormwater facilities. Where possible, excavators or backhoes should work from the sides to remove the topsoil within these areas.

2. Sediment accumulation shall be removed from all stormwater facilities and BMPs prior to fine grading and placement of amended topsoil mix, gravel, and/or underdrain system. Alternatively, silt sock may be used to protect the BMP areas, and any silt accumulation shall be removed if present prior to fine grading and/or seeding.

3. Compaction of the soil structure in the bottom of any stormwater infiltration areas shall be avoided. For micro—scale and small—scale applications, excavating equipment should have arms with adequate extension so they do not have to work inside the footprint of the infiltration area to avoid compaction. Contractors can utilize a cell construction approach, whereby the proposed infiltration area is split into 500 to 1000 sq. ft. temporary cells with a 10 to 15 foot earth bridge in between, so that cells can be excavated from the side. Excavated material should be placed away from the open excavation so as to not jeopardize the stability of the side walls. The Contractor may request alternate methods of excavation, which shall be approved by the Owner prior to implementation.

4. All field and unpaved area subgrades (excluding stormwater infiltration areas) should be compacted to a maximum of 90% Proctor. If a higher compaction exists, the surface should be scarified to bring the surface to below 90% Proctor. The subgrade should be graded to match the final grade. The contractor may not achieve proposed grades by increasing or decreasing topsoil depths. The Landscape Architect should review the subgrade before beginning placement of topsoil.

5. Topsoil depth should be at least 6 inches (12 inches for amended soil locations as indicated on plan) and compacted to 85% Proctor. If the surface is greater than 85% Proctor, it should be scarified to

bring the Proctor values down below 85%. Any bumps or depressions that occur shall be graded and re—tamped until a satisfactory grade is established.

6. Final seeding: Seeding shall be completed as soon as possible after final grade & soil placed to avoid exposure to sun, rainfall, sediment and silt accumulations, all of which can inhibit the infiltration

6. Final seeding: Seeding shall be completed as soon as possible after final grade & soil placed to avoid exposure to sun, rainfall, sediment and silt accumulations, all of which can inhibit the infiltration capabilities of the soil. Prior to seeding, the surface must be free of surface water, saturated conditions, and silt and sediment accumulation.

7. The site is located in a State College Borough Water Authority Well Head Sensitive Area, as defined in the Spring Creek Watershed Stormwater Ordinance. Additional care and precaution should be taken to

ensure that all temporary and permanent erosion & sediment control and stormwater management facilities are installed correctly to provide adequate protection to the adjacent well field site.

8. Compaction test reports shall be kept on file at the site and be subject to review at all times with copies being forwarded to the Township Engineer.

9. Whenever embankment fill material in excess of three feet is to be used, each layer of compacted fill shall be tested to determine its density per ASTM 2922 or ASTM 3017. The density of each layer shall be 98% of a Standard Proctor Density analysis per ASTM 698. All embankment soils shall have a K factor of 0.32 or less to minimize erosion.

10. When rock is encountered during the excavation of an infiltration area, it shall be removed to an elevation of at least 30 inches below proposed basin floors. All exposed cracks and fissures are to be structurally filled.

11. Temporary and permanent grasses or stabilization measures shall be established on the sides and base of all earthen basins within 15 days of construction.

## STORMWATER FACILITIES CONSTRUCTION INSPECTION PROGRAM

Prior to the installation or implementation of the following stormwater management facilities and best management practices (BMPs), the Owner or Township shall be notified and given the opportunity to provide a licensed engineer or soil scientist for inspection of the soil conditions and stormwater management facilities to ensure proper installation during the following critical stages:

1. Creation of the amended topsoil: The amended soil mixture shall be free of clay and native soil clumps larger than 2" in size, and shall be thoroughly mixed to create a homogeneous state of soil, sand, and mulch. Condition of the topsoil materials shall be inspected 1) prior to mixing, and 2) following mixing but prior to infiltration testing. Amended soil must be tested to meet infiltration rate requirement of minimum 10 in/hr, maximum 6 in/hr.

2. Placement of underdrain systems, gravel, and/or amended topsoil mixture: Stormwater facility subsoils shall be inspected to ensure that compaction or accumulation of silt and sediment did not occur within the infiltration facilities. If compaction is apparent in the soil surface due to presence of standing water or visual inspection of the soil material, infiltration testing may be required to determine that

the design infiltration rates determined during pre—development soil testing are still achievable within the stormwater facilities or BMP.

3. Final seeding: Prior to seeding to ensure no compaction or silt accumulation has occurred within the stormwater facilities after the amended soil was placed and while awaiting final seeding. If compaction

occurred or an impermeable layer has been created due to silt and/or exposure to weather, remediation of the surface may be required, which may include scarification of the subsoil and/or amended soil layer, or removal and replacement of the impermable layer.

## STORMWATER FACILITIES POST-CONSTRUCTION MAINTENANCE PROGRAM

4. Installation of outlet structures for Basins 1, 2, 3, and 4, and rain gardens as applicable.

A. The owner shall be responsible for ensuring the proper operation and function of the stormwater facilities located on the property, and the program shall include the following:

1. Following construction, any damaged or incidentally compacted areas shall be restored to their design condition prior to final topsoil and seeding placement.

2. The owner shall complete a visual inspection at least once every six (6) months, and immediately after major storm events (i.e. 2.5 inches or more in a 48—hour period), and one of the inspections shall be after leaves have fallen from trees in autumn. Such a visual inspection shall at least involve an examination for debris deposition (such debris may include, but shall not be limited to aggregate material, leaves, grass clippings, and soil material), settlement, sinkholes, seeps, structural cracking, animal burrows, excessive vegetation, foundation movement, dead plantings, erosion, depressions, and water retention times that exceed seventy—two (72) hours. A visual inspection of the trees and shrubs in the beginning and middle of the growing season to evaluate health of plantings and to complete any necessary pruning. Any perennial plantings shall be cut down and clippings removed at the end of each growing season. During periods of extended drought (i.e. July and August), additional watering of plantings may be required. All inlet pipes, outlet pipes, outlet inlet, storm piping, and drainage structures shall be kept free of any obstructions and foreign material that would cause disruption of water flow in a manner not anticipated for the facility. A written report documenting each inspection shall be retained by the designee, including the date of inspection, list of items inspected, name and organization of the person conducting the inspection, and a list of maintenance correction tasks performed.

3. The owner shall remove any accumulation of debris from stormwater management areas); maintain groundcover vegetation within any above—ground stormwater management system(s) and on berms to a height that does not exceed six (6) inches; and immediately repair any erosion damage by replacing topsoil on all areas that experience erosion, and seeding, mulching and matting such areas immediately in accordance with the specifications contained in the applicable erosion and sediment pollution control plan and/or approved post construction stormwater management plan. Vehicular access is prohibited within basins; and care should be taken to avoid excessive compaction by mowers. Dislodged rock in any riprap apron should be reset in place. Removal of sediment/debris shall take place when the area has dried, if possible. Rain garden(s) that do not drain within seventy—two (72) hours shall be evaluated by a qualified engineer, geologist, and/or hydrogeologist prior to initiating any

when the area has dried, if possible. Rain garden(s) that do not drain within seventy—two (72) hours shall be evaluated by a qualified engineer, geologist, and/or hydrogeologist prior to initiating any repair and/or reconstruction activities.

4. The owner shall remove trash bags and/or litter from such outlets during periods between storm events. Man—made trash removed from any facility shall be disposed of properly in containers collected

by a licensed commercial trash hauler.

5. A written report documenting each inspection shall be retained by the designee, including the date of inspection, list of items inspected, name and organization of the person conducting the inspection, and a list of maintenance correction tasks performed.

6. For any structural facility (pipe, inlet, manhole), it must be repaired or replaced in a timely manner if damaged more than superficially, in a way that is a safety hazard, if structurally unsound, or if not substantially performing as it is intended per the original design. The owner shall keep a record of any repaired or replaced facility, including costs, dates, materials removed, materials placed, and the contractor(s) information.

7. The designee shall immediately notify the Township and Centre County Conservation District prior to initiating any "major" repair activities (such repairs that may be required as a result of settlement, sinkholes, seeps, structural cracking, foundation movement, and water retention times that exceed seventy—two hours). All "major" repairs shall be conducted under the direction and supervision of a qualified engineer, geologist, and/or hydrogeologist.

8. All impervious surfaces shall be maintained clean of oil, fuel or other toxic spills, in accordance with state, federal or local regulations.

9. The stormwater management facilities shall be maintained in the following manner:

a. Stormwater Basins and Rain Gardens: Keep free of debris and leaves. Minimize compaction of the bottom of the bed by promoting natural, native vegetation and eliminating the need for riding mowers within the bottom of the bed area by maintaining the growth with non—compacting equipment (trimmers, etc) that will promote vegetated growth within infiltration and detention areas. The only exception will be an annual mowing at the end of the growing season. The basin bottom, banks, outlet structure and downstream outfall shall be inspected for erosion issues and repaired as needed with topsoil, seed, or rip rap as required.

b. <u>Vegetated Swales and Steep Slopes:</u> Keep free of debris and leaves to ensure free movement of runoff. During initial establishment period, inspect erosion control matting and vegetation to ensure all swales and banks become fully stabilized, reseed or repair matting as required. Provide long—term inspection of swales and steep slopes to identify rills or channels that have formed from erosion and channelized runoff, regrade and revegetate if erosion occurs.

c. Storm Inlets and Storm Sewers: Keep free of debris and leaves both within the storm inlet and externally above the grate and stormwater collection area. Inspect storm inlets and storm sewers for missing or broken materials, and replace or repair as required. Inspect inlets for accumulated sediment and properly dispose of waste material.

B. The Owner is responsible for maintaining the stormwater management in accordance with the approved design. If the Township, Conservation District, or DEP determines at any time that any permanent stormwater facility has been eliminated, altered or improperly maintained, the Owner of the property shall be advised of corrective measures required and given 7 days to initiate appropriate action in accordance with a time schedule dictated by the Township. If such action is not taken by the property Owner, the Township may cause the work to be done and charge all costs to the property owner.

STORMWATER BMP INSPECTION AND MAINTENANCE SUMMARY						
ВМР	INSPECTION FREQUENCY	INSPECTION ACTIVITY	ROUTINE MAINTENANCE & REPAIRS			
STORMWATER BASIN & RAIN GARDENS	EVERY 6 MONTHS OR AFTER LARGE STORM EVENT (>2.5" in 48 HR)	<ul> <li>Inspect for trash or large debris</li> <li>Observe outlet structure, and pipe outfall for clogs or damage.</li> <li>Observe rip rap areas for erosion or displaced rock</li> <li>Observe banks for erosion or sags</li> <li>Observe basin/rain garden bottoms for standing water</li> </ul>	<ul> <li>Keep free of debris.</li> <li>Mow annually, otherwise maintain by hand trimming.</li> <li>Repair &amp; seed eroded areas</li> <li>Scarify surface or otherwise remove any layers on the basin/rain garden bottom that inhibits drainage</li> <li>Repair or replace broken grates, outlet structures, or end sections</li> <li>Install additional rip rap as necessary</li> </ul>			
VEGETATED SWALES & STEEP SLOPES	ANNUALLY	<ul> <li>Inspect for trash or large debris</li> <li>Observe rip rap areas for erosion or displaced rock</li> <li>Observe banks for erosion, rills or channels</li> <li>Ensure swales are following intended flow path</li> <li>Observe end sections and culverts</li> </ul>	<ul> <li>Keep free of debris to maintain flow path.</li> <li>Mowing can occur regularly, or minimally in "no mow" seeded areas.</li> <li>Repair &amp; seed eroded areas</li> <li>Install additional rip rap as necessary</li> <li>Repair or replace broken culverts or end sections</li> </ul>			
STORM INLETS & STORM SEWERS	ANNUALLY	<ul> <li>Inspect for trash or large debris above the grate or within the structure/pipe</li> <li>Oberve for cracks or deficiencies in the grates or concrete structure</li> </ul>	· Keep free of debris and grass clippings. · Repair or replace broken pipes or inlets as required.			

2643 Gateway Drive, Suite #1
State College, PA 16801
Phone: (814) 231-3071
Fax: (814) 235-7832
www.crpr.org

STAHL SHEAFFER ENGINEER INC

301 SCIENCE PARK ROAD, SUITE 333 STATE COLLEGE, PA 16803 PH: 814-689-1562 FAX: 814-689-1885 WWW.SSE-LLC.COM

Fernsler Hutchinson

521 EAST BEAVER AVENUE STATE COLLEGE, PA 16801 t: 814-234-6806 f: 814-234-0256 e: fjfaia@aol.com



PENOENGINEERING

MECHANICAL & ELECTRICAL CONSULTANTS

2746 WEST COLLEGE AVENUE
STATE COLLEGE, PA 16801
814-234-7366

PROJECT NO.: E38095
© 2018 PENO ENGINEERING, LLC



LEWISBURG, PA 17837
PH: 570-847-9519
brian@bsalandplan.com

SSE PROJECT No:

REVISIONS

SYM DATE DESCRIPTION

SUBMISSIONS
DATE DESCRIPTION

10/02/19

TWP. SUBMISSION 1

TWP. SUBMISSION 2

WHITEHALL ROAD REGIONAL PARK PHASE 1

<PRELIMINARY
NOT FOR
CONSTRUCTION>

POST C

POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS

## GENERAL EROSION AND SEDIMENTATION CONTROL METHODS/PROCEDURES

In all cases the smallest practical area of land surfaces shall be disturbed.

Erosion and sedimentation controls must be constructed, stabilized, and functional before site disturbance within the tributary areas of

All sediment shall be prevented from entering any existing storm drain or ditch through use of filter fabric fence, sediment traps,

straw blankets, and rock filters.

All construction traffic shall enter and exit the site via the proposed rock construction entrance.

## EROSION & SEDIMENT CONTROL CONSTRUCTION NOTES

1. Special protection measures should be taken to identify infiltration bed, basin, and swale areas to avoid tracking of heavy equipment and soil compaction during the stripping process. Flagging and protecting these areas during earthwork activities is highly recommended to avoid compaction of soils and negatively impacting the infiltration capabilities of the stormwater facilities. Where possible, excavators or backhoes should work from the sides to remove the topsoil within these areas.

2. Sediment accumulation shall be removed from all stormwater facilities and BMPs prior to fine grading and placement of amended topsoil mix, gravel, and/or underdrain system. Alternatively, silt sock may be used to protect the BMP areas, and any silt accumulation shall be removed if present prior to fine grading and/or seeding.

3. Compaction of the soil structure in the bottom of any stormwater infiltration beds, basins, or swales shall be avoided. For micro—scale and small—scale applications, excavating equipment should have arms with adequate extension so they do not have to work inside the footprint of the infiltration area to avoid compaction. Contractors can utilize a cell construction approach, whereby the proposed infiltration area is split into 500 to 1000 sq. ft. temporary cells with a 10 to 15 foot earth bridge in between, so that cells can be excavated from the side. Excavated material should be placed away from the open excavation so as to not jeopardize the stability of the side walls. The Contractor may request alternate methods of excavation, which shall be approved by the Owner prior

4. All field and unpaved area subgrades (excluding stormwater infiltration areas) should be compacted to a maximum of 90% Proctor. If a higher compaction exists, the surface should be scarified to bring the surface to below 90% Proctor. The subgrade should be graded to match the final grade. The contractor may not achieve proposed grades by increasing or decreasing topsoil depths. The Landscape Architect should review the subgrade before beginning placement of topsoil.

Topsoil depth should be at least 6 inches and compacted to 85% Proctor. If the surface is greater than 85% Proctor, it should be scarified to bring the Proctor values down below 85%. Any bumps or depressions that occur shall be graded and re-tamped until a satisfactory grade is established.

5. Seeding shall be applied to all disturbed areas as soon as practical following completion of fine grading. Disturbed areas that will not be topsoiled and fine graded within 2 weeks of being excavated shall be temporarily seeded and mulched. Prior to seeding, the surface must be free of surface water, saturated conditions, and silt and sediment accumulation.

## MAINTENANCE OF EROSION AND SEDIMENTATION CONTROL FACILITIES

All erosion and sedimentation control facilities must be maintained in operating condition including replacement of plugged sediment sock, until upstream areas are stabilized with a minimum of 70% perennial uniform vegetated ground cover.

Erosion and sedimentation control devices shall be inspected after each runoff event and on a weekly basis.

Sediment at sediment sock must be removed when accumulations reach 1/2 the above ground height of the sock.

Sediment removed from sediment sock shall be placed in a designated topsoil stockpile area.

Seeding shall be applied to all disturbed areas as soon as practical following completion of fine grading. Disturbed areas that will not be topsoiled and fine graded within 2 weeks of being excavated shall be temporarily seeded and mulched.

## <u>Temporary seed mixture shall be as follows:</u>

Formula and Species	% Ву	Min	imum %	Weed	Seeding Rate
	Mass	Purity	Germination	Seed	lb/1000 s.y.
Formula E					20.0 Total
Annual Ryegrass (Lolium multiflorum)	100	98	90	0.15	20.0

## Permanent seed mixtures shall be as follows:

## Turf Grass Seed Mix Specifications

Mix Composition 30.0% Festuca arundinacea, 'Fawn' (Tall Fescue, 'Fawn') 30.0% Lolium perenne. 'Shining Star' (Perennial Ryegrass, 'Shining Star' (turf type)) 'Volt' (Kentucky Bluegrass, 'Volt') 15.0% Poa pratensis, 'Shamrock' (Kentucky Bluegrass, 'Shamrock') 15.0% Poa pratensis, 10.0% Lolium multiflorum (Annual Ryegrass)

General Product Information: This mix is good for high-traffic areas. Item Number: Ernst Seed, ERNMX-106, or approved equal Product Categories: <u>Lawn & Turfgrass Sites</u> Height: 1.0 – 4.0 Ft

Seeding Rate: 75-150 lb per acre, or 3-5 lb per 1,000 sq ft

## Partially Shaded Seed Mix Specifications

Mix C	omposition	
39.8%	Schizachyrium scoparium,	'Camper' (Little Bluestem, 'Camper')
19.0%	Elymus virginicus,	PA Ecotype (Virginia Wildrye, PA Ecotype)
17.7%	Panicum sphaeroncarpon	(Round Seed Panicgrass)
4.0%	Chamaecrista fasciculata	PA Ecotype (Partridge Pea, PA Ecotype)
3.5%	Echinacea purpurea	(Purple Coneflower)
3.0%	Rudbeckia hirta,	(Blackeyed Susan, Coastal Plain NC Ecotype)
2.0%	Heliopsis helianthoide,	(Oxeye Sunflower, PA Ecotype)
2.0%	Penstemon digitalis	(Tall White Beardtongue, PA Ecotype)
1.0%	Elymus hystrix	(Bottlebrush Grass, PA Ecotype)
1.0%	Liatris spicata	(Marsh Blazing Star, PA Ecotype)
0.5%	Agrostis perennans	(Autumn Bentgrass, Albany Pine Bush-NY Ecoty)
0.5%	Asclepias tuberosa	(Butterfly Milkweed)
0.5%	Aster macrophyllus	(Bigleaf Aster, PA Ecotype)
0.5%	Aster prenanthoides	(Zigzag Aster, PA Ecotype)
0.5%	Baptisia australis	(Blue False Indigo, Southern WV Ecotype)
0.5%	Geum canadense	(White Avens, PA Ecotype)
0.5%	Pycnanthemum tenuifolium	(Narrowleaf Mountainmint)
0.5%	Solidago bicolor	(White Goldenrod, PA Ecotype)
0.5%	Tradescantia ohiensis	(Ohio Spiderwort, PA Ecotype)
0.5%	Zizia aurea	(Golden Alexanders, PA Ecotype)
0.4%	Anemone virginiana	(Thimbleweed, PA Ecotype)
0.4%	Aster laevis	(Smooth Blue Aster, NY Ecotype)
0.4%	Monarda fistulosa	(Wild Bergamot, Fort Indiantown Gap-PA Ecotype
0.2%	Solidago juncea	(Early Goldenrod, PA Ecotype)
0.1%	Baptisia tinctoria	(Yellow False Indigo, PA Ecotype)
0.1%	Penstemon hirsutus	(Hairy Beardtongue)
0.1%	Veronicastrum virginicum	(Culver's Root, PA Ecotype)

General Product Information: The native grasses and forbs are ideal for roadside areas and woodland margins.

Item Number: Ernst Seed mix, ERNMX-140, or approved equal Product Categories: Pollinator Favorites, Woodland Openings Height: 0.3 – 5.0 Ft Seeding Rate: 20 lb per acre, or 1/2 lb per 1,000 sq ft

## No Mow Seed Mix Specifications

```
Mix Composition
          Festuca ovina
                                     Hard Fescue
           Festuca rubra 'commutata' Chewings Fescure
General Product Information: Low Maintenance Law Areas
Item Number: Lesco No Mow Fine Fescure Seed Mix, or approved equal
Product Categories: <u>Lawn & Turfgrass Sites</u>
Seeding Rate: 2-3 lb per 1,000 sq ft
No Mow Fine Fescue Mix
Mix Composition
                                            Silhouette Chewings Fescue
24.50% Festuca commutata
           Festuca ovina
           Hard Fescue
12.38%
                                            Festuca brevipila (F. longifolia)
            Festuca rubra
                                            Shoreline Slender Creeping Red Fescue
            Festuca brevipila (F. longifolia) Eureka 2 Hard Fescue
11.76%
           Festuca rubra
                                            Maxima 1 Creeping Red Fescue-
Item Number: Prairie Nursery #50091 No Mow Formula
```

Seeding Rate: 2.5 lbs / 1000 SF, or 110 pounds per acre

## Steep Slope Seed Mix Specifications

No Mow Fine Fescue mix with Annual Rye and Clover cover crop added for short-term

Mix Composition 24.0 % Festuca ovina Blue Mesa Sheep Fescue 22.0 % Festuca commutata Shadow II Chewings Fescue 12.0 % Festuca brevipila (F. longifolia) Gladiator Hard Fescue Sea Fire Slender Creeping Red Fescue 12.0 % Festuca rubra 12.0 % F. rubra, subsp. rubra Kent Creeping Red Fescue 12.0 % Festuca brevipila (F. longifolia) Sword Hard Fescue 3.0 % Lolium multiflorum Annual Ryegrass Trifolium repens Item Number: Prairie Nursery #50092 No Mow Formula Lot Number: PNA17

## **Pollinator Seed Mix Specifications**

Seeding Rate: 5 lb / 1000 SF, or 220 pounds per acre

Mix Com	position	
12.0%	Coreopsis lanceolata	Lanceleaf Coreopsis
12.0%	Echinacea purpurea	Purple Coneflower
12.0%	Penstemon digitalis	Tall White Beardtongue, PA Ecotype
12.0%	Rudbeckia hirta,	Blackeyed Susan, Coastal Plain NC Ecotype
9.5%	Chamaecrista fasciculata	Partridge Pea, PA Ecotype
3.0%	Heliopsis helianthoides	Oxeye Sunflower, PA Ecotype
6.0%	Verbena hastata	Blue Vervain, PA Ecotype
5.0%	Aster laevis	Smooth Blue Aster, NY Ecotype
5.0%	Liatris spicata	Marsh Blazing Star
3.0%	Asclepias incarnata	Swamp Milkweed, PA Ecotype
3.0%	Aster novae-angliae	New England Aster, PA Ecotype
2.0%	Senna hebecarpa	Wild Senna, VA & WV Ecotype
2.0%	Tradescantia ohiensis	Ohio Spiderwort, PA Ecotype
2.0%	Zizia aurea	Golden Alexanders, PA Ecotype
1.6%	Monarda fistulosa	Wild Bergamot, Fort Indiantown Gap-PA Eco
1.5%	Geum canadense	White Avens, PA Ecotype
1.5%	Pycnanthemum tenuifolium	Narrowleaf Mountainmint
1.0%	Baptisia australis	Blue False Indigo, Southern WV Ecotype
1.0%	Lespedeza capitata	Roundhead Lespedeza, RI Ecotype
0.5%	Solidago juncea	Early Goldenrod, PA Ecotype
0.3%	Eupatorium perfoliatum	Boneset, PA Ecotype
0.2%	Solidago rugosa	Wrinkleleaf Goldenrod, PA Ecotype
0.2%	Solidago speciosa	Showy Goldenrod, Southern WV Ecotype
0.1%	Eupatorium fistulosum	Joe Pye Weed, PA Ecotype
0.1%	Eupatorium rugosum	White Snakeroot, PA Ecotype

## \*Plant with Oats or Annual Rye Cover Crop

General Product Information: Contains native forbs common in the Northeast. Excellent for wildlife food and shelter, including pollinators.

Item Number: Ernst Seed ERNMX-125 Product Categories: Pollinator Favorites, Uplands & Meadows Height: 1.0 – 5.0 Ft Seeding Rate: 5-10 lb per acre with 30 lb per acre of a cover crop

### Pollinator Mix Option -Grass and Wildflower Meadow

Mix Composition 73.2% Festuca ovina. Variety Not Stated (Sheep Fescue, Variety Not Stated)

17.0% Lolium multiflorum (Annual Ryegrass) 3.0% Chrysanthemum maximum (Shasta Daisy) 2.0% Coreopsis lanceolata (Lanceleaf Coreopsis) 2.0% Rudbeckia hirta, Coastal Plain NC Ecotype (Blackeyed Susan, Coastal Plain NC Ecotype) 0.5% Achillea millefolium (Common Yarrow)

0.5% Asclepias tuberosa (Butterfly Milkweed) 0.3% Chamaecrista fasciculata, PA Ecotype (Partridge Pea, PA Ecotype) 0.3% Eupatorium coelestinum, VA Ecotype (Mistflower, VA Ecotype) 0.3% Rudbeckia fulgida var. fulgida, Northern VA Ecotype (Orange Coneflower, Northern VA Ecotype)

0.2% Penstemon hirsutus (Hairy Beardtongue) 0.2% Pycnanthemum tenuifolium (Narrowleaf Mountainmint) 0.1% Aster oblongifolius, PA Ecotype (Aromatic Aster, PA Ecotype) 0.1% Aster prenanthoides, PA Ecotype (Zigzag Aster, PA Ecotype)

0.1% Tradescantia virginiana, Southeastern PA/Northern VA blend (Virginia Spiderwort, Southeastern PA/Northern VA blend)

General Product Information: Specifically designed to provide erosion and sediment control and color on low-fertility sites. May be mowed occasionally. Low Growing Wildflower & Grass Mix

Item Number: Ernst Seed, ERNMX-156, or approved equal Product Categories: <u>Uplands & Meadows</u> Height: 0.5 – 5.0 Ft Seeding Rate: 20-40 lb per acre

0.1% Baptisia tinctoria, PA Ecotype (Yellow False Indigo, PA Ecotype)

Pollinator Mix Option -**Grass Clover Pasture Mix** 

Mix Composition 40.0% Trifolium pratense, Medium, Variety Not Stated (Red Clover, Medium, Variety Not Stated) 30.0% Festuca arundinacea, 'Bronson' (Tall Fescue, 'Bronson' (pasture type)) 20.0% Medicago sativa, VNS (Alfalfa, VNS) 10.0% Phleum pratense, 'Climax' (Timothy, 'Climax') Item Number: ERNMX-108 Product Categories: Forage & Pasture Sites Height: 1.3 – 4.0 Ft

## Wet Basin Seed Mix Specifications

Item Number: Ernst Seed ERNMX-126

Product Categories: Stormwater Management

Seeding Rate: 20-40 lb per acre, or 0.5 - 1.0 lb per 1,000 sq ft

Seeding Rate: 20-25 lb per acre

20.0% 19.0%	Puccinellia distans, 'Fults' Panicum clandestinum. 'Tioga'	Alkaligrass, 'Fults' Deertonque, 'Tioga'
18.0%	Agrostis stolonifera	Creeping Bentgrass
18.0%	Elymus virginicus, PA Ecotype	Virginia Wildrye, PA Ecotype
15.0%	Poa palustris	Fowl Bluegrass
5.0%	Carex vulpinoidea, PA Ecotype	Fox Sedge, PA Ecotype
3.0%	Juncus effusus	Soft Rush
2.0%	Carex scoparia, PA Ecotype	Blunt Broom Sedge, PA Ecotype
species		nexpensive grass and grass-like hat may have high salt inflows and

Height: 0.3 – 5.0 Ft

The contractor shall balance all cuts and fill with the amount of rock and soil that is available on site.

In the case that fill material is required for the site, the contractor is responsible to perform environmental due dilligence and determine that all fill imported to the site meets DEP's definition of

Clean fill is defined as uncontaminated, nonwater—loluble, nondecomposable inert solid material. The term includes soil, rock, stone, dredged material, used asphalt, and brick, block or concrete from construction and deomolition activities that is separate from other waste and recognizable as such. (25 Pa. Code 271.101 and 287.101) The term does not include materials placed in or on the waters of the Commonwealth unless otherwise authorized.

Environmental due diligence is defined as investigative techniques, inluding, but not limited to, visual property inspections, electronic data base searches, review of ownership and use of history of property, Sanborn maps, environmental questionnaires, transaction screens, analytical testing, environmental assessments or audits.

## SEQUENCE OF CONSTRUCTION FOR EROSION AND SEDIMENTATION CONTROL

1. Submit a detailed construction schedule to the Owner for evaluation and approval. The sequence below provides a general guidance installation of site features to minimize off—site erosion and sediment transport, however it is the Contractor's responsibility to review and determine the final process for installation and project completion, as it is recognized that external factors, including weather, material availability, and subcontractor coordination may impact the desired sequence of construction.

2. Install the rock construction entrance and compost filter sock in accordance with the contract drawings. Any adjustment to the location or layout of the entrance must be coordinated and approved by the County Conservation District. Store topsoil stockpiles in designated area on site. Other areas used for topsoil storage shall be protected with compost filter sock on the downstream side of the stockpile. 3. Construct and stabilize southern swales at the bottom of the site, as well as the diversion compost filter sock on the southern end of the site that will direct runoff to the rock filter and eventually through the lower compost filter sock before leaving the site.

4. Place temporary orange construction fence around the bottom of each stormwater management area to preserve stormwater infiltration capabilities of the soil. 5. Establish areas to be graded, preserving as much natural vegetation as practical. Cut and clear necessary vegetation to install compost filter sock where indicated throughout the site.

6. Strip topsoil in only areas necessary for project completion and store in designated topsoil stockpile location. Do not strip entire site, specifically the southern area below the developed that is designated to be transition from agricultural/farming cover to No—Mow Fescue (see Landscaping Plan). This area is proposed to be transitioned through the process of undercutting and tilling, and the existing topsoil will remain in 7. Rough grade and excavate for the proposed stormwater management areas, to include the installation of underdrain systems as applicable. Avoid compaction of soil in the bottom of any stormwater infiltration beds, basins, or swales. Where possible, excavators or backhoes should work from the sides to excavate the reservoir layer to its appropriate design depth and dimensions. For micro-scale and small-scale

applications, excavating equipment should have arms with adequate extension so they do not have to work inside the footprint of the infiltration area (to avoid compaction). Contractors can utilize a cell

construction approach, whereby the proposed infiltration area is split into 500 to 1000 sq. ft. temporary cells with a 10 to 15 foot earth bridge in between, so that cells can be excavated from the side. Excavated material should be placed away from the open excavation so as to not jeopardize the stability of the side walls. 8. In all cases, within 7 days after earth disturbance activities cease in any area of the project, the operator shall stabilize all disturbed areas. During non—germinating months, mulch or protective blanketing shall be applied as described in the plan. Areas not at finished grade may be stabilized in accordance with the temporary stabilization specifications.

9. Install gravel, amended soils, outlet pipes, culverts and rip rap apron within the stormwater management basins and rain gardens as shown on the construction plans. Where possible, excavators or backhoes should work from the sides to place materials within the bottoms of the beds and basins. 10. Rough grade remainder of the site, including excavation for the vegetated swales. Place swale lining within the trenches as soon as possible following backfill of trenches to provide protection of sediment within

the swale. If a rain event that causes erosive damage or sediment transport to the trenches occurs before site stabilization, the sediment shall be removed before final seeding is completed. 11. Final grade new playing fields and excavate for vegetated swales in parking lot area. 12. Complete fine grading by placing topsoil in the location and depths specified on the construction plans and specifications.

13. Seed basin area and all other parkland grass/meadow areas upon completion of fine grading. Seeding should meet all specifications detailed in the erosion & sediment control narrative and construction 14. Begin construction of new buildings and install proposed utility connections, main lines, laterals and site lighting.

15. Install concrete sidewalk, aggregate paths, and parking lot driving surface once site stabilization is complete. Do not construct aggregate paths until the upstream tributary areas are vegetated and stormwater management controls, swales, etc are installed. 16. Fertilize, mulch and seed all disturbed areas as specified.

17. Remove any accumulated sediment from the bottom of the sediment basin. Excavate additional material from bottom of basin as necessary for placement of amended topsoil. Scarify bottom of basin prior to topsoil placement. Place topsoil using low impact equipment to avoid compacting basin bottom. Install permanent seeding and soil supplements in basin bottom. 18. Upon 70% vegetative cover of erosion resistant perennial species, remove all erosion and sedimentation control devices. 19. Request final site inspection by the Township and Centre County Conservation District.

## EROSION AND SEDIMENT CONTROL PLAN STANDARD NOTES:

1. Topsoil stockpile heights shall not exceed 45 feet. Stockpile sides must be 3:1 or

2. A copy of the approved erosion and sediment control plan must be available at the project site at all times. The operator shall assure that the approved erosion and sediment control plan is properly and completely 3. Before initiating any revisions to the approved erosion and sediment control plan or revisions to other plans which may affect the effectiveness of the approved E&S control plan, the operator must receive approval

of the revisions from the Centre County Conservation District. 4. At least 7 days before starting any earth disturbance activities, the owner and/or operator shall invite all contractors involved in those activities, the landowner, all appropriate municipal officials, the erosion and sediment control plan preparer, and a representative of the Centre County Conservation District to an on-site pre construction meeting. 5. At least 3 days before starting any earth disturbance activities, all contractors involved in those activities shall notify the Pennsylvania One Call System Incorporated at 1—800—242—1776 for the location of existing

6. All earth disturbance activities shall proceed in accordance with the following sequence. Each stage shall be completed and immediately stabilized before any following stage is initiated. Clearing, grubbing, and topsoil stripping shall be limited only to those areas described in each stage. 7. Immediately upon discovering unforseen circumstances posing the potential for accelerated erosion and/or sediment pollution, the operator shall implement appropriate best management practices to eliminate the

potential for accelerated erosion and/or sediment pollution. 8. All pumping of sediment laden water shall be through a sediment control BMP, such as a pumped water filter bag or equivalent sediment removal facility, over undisturbed vegetated areas.

9. Upon completion of all earth disturbance activities and permanent stabilization of all

disturbed areas, the owner and/or operators shall contact the Centre County Conservation District for an inspection prior to removal of the BMP's. 10. Upon completion of all earth disturbance activities, removal of all temporary BMP's and permanent stabilization of all disturbed areas, the owner and/or operators shall contact the Centre County Conservation

District for a final inspection. 11. All channels must be kept free of obstructions such as fill, fallen leaves, & woody debris, accumulated sediment, and construction materials/wastes. Channels should be kept mowed and/or free of all weedy, brushy, or woody growth. Any underground utilities running across/through the channel(s) shall

be covered immediately—and the channel(s) repaired and stabilized per the channel cross —section detail. 12. Vegetated channels shall be constructed free of rocks, tree roots, stumps, or other projections that will impede normal channel flow and/or prevent good lining to soil contact. The channel shall be initially over excavated to allow for the placement of topsoil.

13. Sediment basins/traps shall be kept free of all trash, concrete wash water and other debris that pose the potential for clogging the basin/trap outlet structures and/or pose the potential for pollution to waters of the Commonwealth.

14. When sediment has accumulated to the clean out elevation on any stake, all accumulated sediment shall be removed from the entire trap/basin bottom. 15. Sediment basins must be protected from unauthorized acts of third parties. 16. Fill material for the embankments shall be free of roots, or other woody vegetation, organic material, large stones, and other objectionable materials. The embankment shall be compacted in maximum 12" layered

17. Permanent stabilization is defined as a minimum uniform 70% perennial vegetative cover or other permanent cover with a density sufficient to resist accelerated surface erosion and subsurface characteristics sufficient to resist sliding and other movements.

18. Immediately after earth disturbance activities cease,the operator shall stabilize the disturbed areas. During stabilization periods, mulch must be applied at the specific rates.

Disturbed areas which are not at finished grade and which will be within 1 year must be stabilized in accordance with the temporary vegetative stabilization specifications. Disturbed areas which are at final grade or which will not be within 1 year must be stabilized in accordance with the permanent

vegetative stabilization specifications. 19. An erosion control blanket will be installed on all disturbed slopes steeper than 3:1, all areas of concentrated flows, and disturbed areas within 50' of Waters of the Commonwealth.

20. Until the site is stabilized, all erosion and sediment control BMP's must be maintained properly. Maintenance must include inspections of all erosion and sediment control BMP's after each runoff event and on a weekly basis. All preventative and remedial maintenance work, including, repair, replacement, re— grading, reseeding, re—mulching and re—netting must be performed immediately. If erosion and sediment control BMP's fail to perform as expected, replacement BMP's or modifications of those installed will be required. 21. Sediment must be removed from storm water inlet protection after each runoff event.

22. Sediment removed from BMP's shall be disposed of in landscaped areas outside of steep slopes, wetlands, floodplains, or drainage swales and immediately stabilized, or placed in topsoil stockpiles. 23. The permittee and co-permittee must ensure that visual site inspectors are conducted

weekly, and after each measurable precipitation event by qualified personnel, trained and experienced in erosion and sediment control, to ascertain that the Erosion and

Sediment Control (E&S) BMP's are operational and effective in preventing pollution to the waters of the Commonwealth. A written report of each inspection shall be kept, and

include: a) a summary of the site conditions, E&S BMP's, and compliances; and

b) the date, time, and the name of the person conducting the inspection. 24. All building materials and wastes must be removed from the site and recycled or disposed of in accordance with the Department's Solid Waste Management Regulations at 25 Pa. Code 260.1 et seg., 271.1., and 287.1 et seq. No building materials or wastes or unused building materials shall be burned, buried, dumped, or discharged at the site. 25. The contractor will be responsible for the removal of any excess material and make sure the site(s) receiving the excess has an approved erosion and sediment control plan that meets the conditions of Chapter

## **BLASTING NOTES:**

IF DRILLING OR BLASTING IS REQUIRED DURING CONSTRUCTION, ALL ACTIVITIES MUST BE PLANNED WITH BOTH FERGUSON TOWNSHIP AND THE STATE COLLEGE BOROUGH WATER AUTHORITY.

IN THE CASE THAT DRILLING OR BLASTING ACTIVITIES WILL OCCUR THE FOLLOWING GUIDELINES MUST BE FOLLOWED: 1. BLASTING ACTIVITIES MUST BE MONITORED BY EITHER A PENNSYLVANIA LICENSED PROFESSIONAL GEOLOGIST OR ENGINEER.

2. THE AFOREMENTIONED LICENSED PROFESSIONAL MUST SUBMIT A REPORT WITH SPECIFIC BLASTING RECOMMENDATIONS WITH REGARDS TO AMOUNT OF CHARGE, FIRING TIMES, GROUND VELOCITY, ACCELERATION AND DISPLACEMENT AS WELL AS ANY POTENTIAL EFFECTS TO THE GROUND WATER AQUIFER SYSTEM.

3. BLASTING SHALL BE MONITORED BY THE LICENSED GEOLOGIST OR ENGINEER WITH SEISMOGRAPHIC EQUIPMENT AND ACCURATE RECORDS SHALL BE TAKEN FOR EACH BLAST. 4. BLASTING RECORDS MUST CONTAIN GENERAL LOCATION, DEPTH AND QUANTITY OF HOLES DRILLED AS WELL AS TYPE AND QUANTITY OF EXPLOSIVE USED, GROUND DATA, ETCETERA.

5. ALL BLASTING OPERATIONS SHALL BE CONDUCTED BY EXPERIENCED PERSONNEL WITH A VALID PENNSYLVANIA BLASTER'S LICENSE. IN THE EVENT THAT EXCESSIVE SUBSURFACE FRACTURING OCCURS, REMEDIATION MEASURES MUST BE APPROVED BY SCBWA. 6. THE DEVELOPER WILL REIMBURSE ASSOCIATED COSTS & EXPENSES FOR ALL CONSTRUCTION PHASES TO SCBWA & FERGUSON TOWNSHIP.

7. THE ABOVE STANDARDS MAY BE MODIFIED AS DEEMED NECESSARY BY SCBWA UPON AGREEMENT BETWEEN DEVELOPER, FERGUSON TOWNSHIP, SCBWA.

## PROCEDURES FOR SINKHOLE REMEDIATION

102 and/or other State or Federal regulations.

DURING DAILY SITE INSPECTIONS IF ANY SUBSIDENCE OR OPEN VOIDS ARE DISCOVERED IMMEDIATELY CALL THE EMERGENCY CONTACTS BELOW:

• STATE COLLEGE BOROUGH WATER AUTHORITY (814)—238—6766, FERGUSON TOWNSHIP ENGINEER (814)—238—4651, THE CONSTRUCTION PROJECT MANAGER, PROJECT GEOTECHNICAL ENGINEER, AND STAHL SHEAFFER ENGINEERING (814)-689-1562

IN THE CASE THAT NO CONTACT CAN BE MADE, CONTINUE THE FOLLOWING PROCEDURES:

IMMEDIATELY ROPE OFF THE AREA.

DIVERT ANY RUNOFF THAT IS ENTERING THE CAVITY.

• STOP ALL EXCAVATION UPSLOPE OF THE AREA UNTIL FURTHER DIRECTION FROM GEOTECHNICAL ENGINEER IS RECEIVED.

• IN THE CASE THAT A SINKHOLE DOES DEVELOP, A TEMPORARY FIX MUST BE PROVIDED BY THE CONTRACTOR WITHIN 24 HOURS. WITHIN 5 DAYS A PERMANENT SOLUTION MUST BE CREATED WITH THE GEOTECHNICAL ENGINEER AND APPROVED BY STATE COLLEGE BOROUGH WATER AUTHORITY BEFORE COMPLETING ANY WORK. UNLESS OTHERWISE AGREED UPON, WORK MUST START WITHIN 10 CALENDAR DAYS.

• STATE COLLEGE BOROUGH AND FERGUSON TOWNSHIP RESERVE THE RIGHT TO ENTER THE PROPERTY TO COMPLETE REPAIRS IF THE AFOREMENTIONED TIME FRAME IS NOT MET.

State College, PA 16801 Phone: (814) 231-3071 Fax: (814) 235-7832

www.crpr.org

301 SCIENCE PARK ROAD, SUITE 333 STATE COLLEGE, PA 16803 PH: 814-689-1562 FAX: 814-689-1885 WWW.SSE-LLC.COM

Fernsler Hutchinson ARCHITECTURE LLC

**521 EAST BEAVER AVENUE** STATE COLLEGE, PA 16801 t: 814-234-6806 f: 814-234-0256 e: fjfaia@aol.com





brian@bsalandplan.com SSE PROJECT No: RAWN BY: CHECKED BY:

REVISIONS SYM DATE DESCRIPTION

SUBMISSIONS DESCRIPTION

TWP. SUBMISSION 2

06/07/19 TWP, SUBMISSION 1

10/02/19

<PRELIMINARY CONSTRUCTION>


> **EROSION AND** SEDIMENTATION CONTROL DETAILS

(LOOKING DOWNSTREAM) SWALE CROSS-SECTION \* SEE MANUFACTURER'S LINING INSTALLATION DETAIL FOR STAPLE PATTERNS, VEGETATIVE STABILIZATION FOR SOIL AMENDMENTS, SEED MIXTURES AND MULCHING INFORMATION

SWALE NO.	DEPTH D (FT)	TOP WIDTH W (FT)	LINING *
1	1.0	8.0	NAG S75; PERM. SEED
2	1.0	11.0	NAG SC150; PERM. SEED
3	0.75	6.0	NAG S75; PERM. SEED
4	1.0	9.5	NONE
5	1.0	7.8	NAG SC150; PERM. SEED
6	1.0	7.8	NAG S75; PERM. SEED
7	1.0	12.50	NAG SC150; PERM. SEED
8&9	0.50	7.50	NAG S75; PERM. SEED
10&12	1.0	12.50	NAG S75; PERM. SEED
11	0.50	17.0	NONE

NOTES: 1. SWALES SHALL BE LINED WITH S75BN NORTH AMERICAN GREEN EROSION CONTROL LINING. 2. ALL SWALES DESIGNATED ON THE EROSION AND SEDIMENT CONTROL PLANS SHALL BE LINED. 3. ANCHOR TRENCHES SHALL BE INSTALLED AT BEGINNING AND END OF CHANNEL IN THE SAME MANNER AS LONGITUDINAL ANCHOR TRENCHES. 4. CHANNEL DIMENSIONS SHALL BE CONSTANTLY MAINTAINED. CHANNEL SHALL BE CLEANED WHENEVER TOTAL CHANNEL DEPTH IS REDUCED BY 25% AT ANY LOCATION. 5. SEDIMENT DEPOSITS SHALL BE REMOVED WITHIN 24 HOURS OF DISCOVERY OR AS SOON AS SOIL CONDITIONS PERMIT ACCESS TO CHANNEL WITHOUT FURTHER DAMAGE. DAMAGED LINING SHALL BE REPAIRED OR REPLACED WITHIN 48 HOURS OF DISCOVERY. 6. NO MORE THAN ONE THIRD OF THE SHOOT (GRASS LEAF) SHALL BE REMOVED IN ANY MOWING. GRASS HEIGHT SHALL BE MAINTAINED BETWEEN 2 AND 3 INCHES UNLESS OTHERWISE SPECIFIED. EXCESS VEGETATION SHALL BE REMOVED FROM PERMANENT CHANNELS TO ENSURE SUFFICIENT CHANNEL CAPACITY.

VEGETATED SWALE INSTALLATION




NOTES: SEED AND SOIL AMENDMENTS SHALL BE APPLIED ACCORDING TO THE RATES IN THE PLAN DRAWINGS PRIOR TO INSTALLING THE BLANKET.

PROVIDE ANCHOR TRENCH AT TOE OF SLOPE IN SIMILAR FASHION AS AT TOP OF SLOPE.

SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS, AND GRASS. BLANKET SHALL HAVE GOOD CONTINUOUS CONTACT WITH UNDERLYING SOIL THROUGHOUT ENTIRE LENGTH. LAY BLANKET LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH SOIL. DO NOT STRETCH


THE BLANKET SHALL BE STAPLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. BLANKETED AREAS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT UNTIL PERENNIAL VEGETATION IS ESTABLISHED TO A MINIMUM UNIFORM 70% COVERAGE THROUGHOUT THE BLANKETED AREA. DAMAGED OR DISPLACED BLANKETS SHALL BE RESTORED OR REPLACED WITHIN 4 CALENDAR DAYS.

EROSION CONTROL BLANKET INSTALLATION




NOTES: SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH 1/2 THE HEIGHT OF THE FILTERS. IMMEDIATELY UPON STABILIZATION OF EACH CHANNEL, REMOVE ACCUMULATED SEDIMENT,

REMOVE ROCK FILTER, AND STABILIZE DISTURBED AREAS.



SOCK FABRIC SHALL MEET STANDARDS OF TABLE 4.1 OF THE PA DEP EROSION CONTROL MANUAL. COMPOST SHALL MEET THE STANDARDS OF TABLE 4.2 OF THE PA DEP EROSION CONTROL MANUAL. COMPOST FILTER SOCK SHALL BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE BARRIER SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN BARRIER ALIGNMENT. MAXIMUM SLOPE LENGTH ABOVE ANY BARRIER SHALL NOT EXCEED THAT SPECIFIED FOR THE SIZE OF THE SOCK AND THE SLOPE OF ITS TRIBUTARY AREA. TRAFFIC SHALL NOT BE PERMITTED TO CROSS COMPOST FILTER SOCKS. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES 1/2 THE ABOVE GROUND HEIGHT OF THE BARRIER AND DISPOSED IN THE MANNER DESCRIBÉD ELSEWHERE IN THE PLAN. COMPOST FILTER SOCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24 HOURS OF INSPECTION. BIODEGRADABLE COMPOST FILTER SOCKS SHALL BE REPLACED AFTER 6 MONTHS; PHOTODEGRADABLE SOCKS AFTER 1 YEAR. POLYPROPYLENE SOCKS SHALL BE REPLACED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS. UPON STABILIZATION OF THE AREA TRIBUTARY TO THE SOCK, STAKES SHALL BE REMOVED. THE SOCK MAY BE LEFT IN PLACE AND VEGETATED OR REMOVED. IN THE LATTER CASE, THE MESH


SHALL BE CUT OPEN AND THE MULCH SPREAD AS A SOIL SUPPLEMENT.



REMOVE TOPSOIL PRIOR TO INSTALLATION OF ROCK CONSTRUCTION ENTRANCE. EXTEND ROCK OVER FULL WIDTH OF ENTRANCE. RUNOFF SHALL BE DIVERTED FROM ROADWAY TO A SUITABLE SEDIMENT REMOVAL BMP PRIOR TO ENTERING ROCK CONSTRUCTION ENTRANCE. MOUNTABLE BERM SHALL BE INSTALLED WHEREVER OPTIONAL CULVERT PIPE IS USED AND PROPER PIPE COVER AS SPECIFIED BY MANUFACTURER IS NOT OTHERWISE PROVIDED. PIPE SHALL BE SIZED APPROPRIATELY FOR SIZE OF DITCH BEING CROSSED. MAINTENANCE: ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE. ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE IMMEDIATELY. IF EXCESSIVE AMOUNTS OF SEDIMENT ARE BEING DEPOSITED ON ROADWAY, EXTEND LENGTH OF ROCK CONSTRUCTION ENTRANCE BY 50 FOOT INCREMENTS UNTIL CONDITION IS ALLEVIATED OR INSTALL WASH RACK. WASHING THE ROADWAY OR SWEEPING THE DEPOSITS INTO ROADWAY DITCHES, SEWERS, CULVERTS, OR OTHER DRAINAGE COURSES IS NOT ACCEPTABLE.

\* MOUNTABLE BERM USED TO PROVIDE PROPER COVER FOR PIPE

ROCK CONSTRUCTION ENTRANCE



LOW VOLUME FILTER BAGS SHALL BE MADE FROM NON-WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STITCHED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS. HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE FOLLOWING STANDARDS:

ASTM D-4884 AVG. WIDE WIDTH STRENGTH PUNCTURE ASTM D-4833 MULLEN BURST ASTM D-3786 UV RESISTANCE ASTM D-4355

ASTM D-4751

AOS % RETAINED


AND NOT RESUME UNTIL THE PROBLEM IS CORRECTED.

A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME 1/2 FULL OF SEDIMENT. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED. BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA, AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS. WHERE THIS IS NOT POSSIBLE, A GEÓTEXTILE UNDERLAYMENT AND FLOW PATH SHALL BE PROVIDED. BAGS MAY BE PLACED ON FILTER STONE TO INCREASE DISCHARGE CAPACITY. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5%. FOR SLOPES EXCEEDING 5%, CLEAN ROCK OR OTHER NON-ERODIBLE AND NON-POLLUTING MATERIAL MAY BE PLACED UNDER THE BAG TO REDUCE SLOPE STEEPNESS. NO DOWNSLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. COMPOST BERM OR COMPOST FILTER SOCK SHALL BE INSTALLED BELOW BAGS LOCATED IN HQ OR EV WATERSHEDS, WITHIN 50 FEET OF ANY

RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAILABLE. THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS PURPOSE. THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR 1/2 THE MAXIMUM SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHALL BE FLOATING AND SCREENED.

FILTER BAGS SHALL BE INSPECTED DAILY. IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE IMMEDIATELY

PUMPED WATER FILTER BAG



STACKED FILTER SOCK

Recreation 2643 Gateway Drive, Suite #1 State College, PA 16801 Phone: (814) 231-3071 Fax: (814) 235-7832 www.ćrpr.org

301 SCIENCE PARK ROAD, SUITE 333 STATE COLLEGE, PA 16803


> Fernsler Hutchinson ARCHITECTURE LLC 521 EAST BEAVER AVENUE STATE COLLEGE, PA 16801 t: 814-234-6806 f: 814-234-0256

> > e: fjfaia@aol.com

PH: 814-689-1562

FAX: 814-689-1885

WWW.SSE-LLC.COM





SSE PROJECT No:

CHECKED BY: DRAWN BY:

REVISIONS SYM DATE DESCRIPTION


SUBMISSIONS


DESCRIPTION TWP. SUBMISSION 1 10/02/19 TWP. SUBMISSION 2

WHITEHALL REGIONAL PARK PHASE 1

<PRELIMINARY CONSTRUCTION>

SHEET NAME **EROSION AND CONTROL DETAILS** 





## 2 SOCCER FIELD ELECTRICAL SERVICE - ENLARGED PLAN

		YAINS TYPE: 300A MCB		L				NEMA	4/				LOCATION: SOCO	
	В	JS RATING: 400 A			FEE	D-THRU	LUGS:	NO					FED FROM: UTILTIY	XFMR
CKT	FEEDER	LOAD DESCRIPTION		3KR				(KVA)	_		BK	_	LOAD DESCRIPTION	FEEDER
NO.			Р	AMP		A		В	(	<u> </u>	AMP	Р		
1		SOCCER FIELD #WH2 LIGHTING -			5.76	5.76							SOCCER FIELD #WH1 LIGHTING -	
3	40.4G	POLE \$1	3	30			5.76	5.76			30	3	POLE S3	40.4G
5	7	MMIRSCHERMINT 4 COUNTY							5.76	5.76			0.25 (1993) (3944) (3956)	
7	10.10	SOCCER FIELD #WH2 LIGHTING -	3	200	5.76	5.76	E 7.4	5.74			00	_	SOCCER FIELD #WH1 LIGHTING -	10.10
9	40.4G	POLE S2	3	30		-	5.76	5.76	F 71	F 74	30	3	POLE S4	40.4G
11	i.					F 71			5.76	5.76				
13	40.4G	SOCCER FIELD #WH2 LIGHTING -	3	30	6.46	5.76		F 71			30	3	SOCCER FIELD #WH1 LIGHTING -	40.4G
15	40.46	POLE \$3	3	30			6.46	5.76		F 7/	30	3	POLE \$5	40.46
17	3		$\vdash$		6,46	5.76			6.46	5.76				
21	40.4G	SOCCER FIELD #WH2 LIGHTING -	3	30	0.40	5./6	6.46	5.76			30	3	SOCCER FIELD #WH1 LIGHTING -	40,4G
23	40.40	POLE S4	3	30	-	-	0.40	3.76	6,46	5.76	30	3	POLE S6	40.40
25				_	0.00	0.00			0.40	3.70	_	-		
27	30.3G	PANELBOARD SF2	3	25	0.00	0.00	0.00	0.00		-	20	2	WEST PARKING LOT	40.2G
29	00.00	TARLEDOTING STZ	0	20		1	0.00	0.00	0.00	0.00				
31		PROVISIONS	-	-	0.00	0.00			0.00	0.00	20	2	EAST PARKING LOT	40.2G
33	_	PROVISIONS	-	-	0.00	0.00	0.00	0.00			-	-	PROVISIONS	-
35	-	PROVISIONS	-	-			0.00	0.00	0.00	0.00	-	-	PROVISIONS	-
37	-	PROVISIONS	-	-	0.00	0.00					-	-	PROVISIONS	-
39	-	PROVISIONS	-	-			0.00	0.00			-	-	PROVISIONS	-
41	-	PROVISIONS	(-)						0.00	0.00	-	-	PROVISIONS	-
	PANFIRO	ARD NOTES:	_		47	.50	47	.50	47	.50	$\vdash$			

	M	AINS TYPE: 50A MCB		E	NCLOS	URE RA	ATING:	NEMA	4X				LOCATION: SOCO	CER FIELDS	5
	BU	S RATING: 100 A			FEED	D-THRU	LUGS:	NO					FED FROM: PANE	L SF1	
CKT	FEEDER	LOAD DESCRIPTION	-	3KR			LOAD	(KVA)			BKI	3	LOAD DESCRIPTION	FEEDER	CK
١٥.	ILLDLK	LOAD DESCRIPTION	P	AMP	-	4		3	(	2	AMP	Р	EOAD DESCRIPTION	TLLDLK	NC
1	20.2G	SPORTS LTG CONTROL PANEL	1	20	1.00	0.36					20	1	RECEPTACLE PEDESTAL	40.2G	2
3	20.2G	REC AT PANELBOARD	1	20			0.18	0.36			20	1	RECEPTACLE PEDESTAL	40.2G	4
5	2	SPARE	1	20					0.00	0.36	20	1	RECEPTACLE PEDESTAL	40.2G	6
7	-	SPARE	1	20	0.00	0.36					20	1	RECEPTACLE PEDESTAL	40.2G	8
9	-	SPARE	1	20			0.00	0.36			20	1	RECEPTACLE PEDESTAL	40.2G	10
11	÷	SPARE	1	20					0.00	0.00	20	1	SPARE	-	12
13	-	SPARE	1	20	0.00	0.00					20	1	SPARE	-	14
15	-	SPARE	1	20			0.00	0.00			20	1	SPARE	-	16
17	-	SPARE	1	20					0.00	0.00	20	1	SPARE	7.5	18
19	-	SPARE	1	20	0.00	0.00					20	1	SPARE		20
21	-	PROVISIONS	-				0.00	0.00			-	-	PROVISIONS	- 8	22
23	-	PROVISIONS	-	-					0.00	0.00	-	-	PROVISIONS	-	24
25	-	PROVISIONS	-	-	0.00	0.00					-	-	PROVISIONS	170	26
27	-	PROVISIONS	-	-			0.00	0.00			-	-	PROVISIONS	(#)	28
29	-	PROVISIONS		-					0.00	0.00	-	-	PROVISIONS	100	30
	PANELBOA	ARD NOTES:			1.	72	0.	90	0.	36					

## **GENERAL NOTES:**

- ALL UNDERGROUND BRANCH CIRCUITING SHALL BE INSTALLED IN 1-1/4" MINIMUM PVC SCHEDULE 80 CONDUIT.
- 2. CONDUIT ROUTINGS SHOWN ON PLAN ARE DIAGRAMMATIC. DETERMINE EXACT ROUTING IN FIELD.

## KEY NOTES:

- 1. ELECTRICAL UTILITY SWITCH AND COMMUNICATIONS SERVICE PEDESTAL.
- 2. ILLUMINATED FACILITY SIGN. FURNISH AND INSTALL ELECTRICAL UTILITY METER AND FUSED DISCONNECT.
- 3. UNDERGROUND ELECTRICAL UTILITY PRIMARY AND COMMUNICATIONS SERVICE DUCTBANK.
- 4. RECEPTACLE PEDESTAL/BOLLARD.
- 5. CIRCUIT SHALL ORIGINATE IN PAVILLION BUILDING.
- 6. POLE AND LIGHTING FIXTURES INSTALLED BY SPORTS LIGHTING MANUFACTURER. BASIS OF DESIGN IS BY MUSCO, UTILIZING THEIR ADJUSTABLE TLC-LED-1150 HEADS.

SHEET NAME SITE PLAN -

2643 Gateway Drive, Suite #1 State College, PA 16801 Phone: (814) 231-3071

Fax: (814) 235-7832 www.crpr.org

301 SCIENCE PARK ROAD, SUITE 333 STATE COLLEGE, PA 16803 PH: 814-689-1562

FAX: 814-689-1885

WWW.SSE-LLC.COM

Hutchinson ARCHITECTURE LLC

521 EAST BEAVER AVENUE STATE COLLEGE, PA 16801 t: 814-234-6806

f: 814-234-0256 e: fjfaia@aol.com

PENOENGINEERING

182 FAIRMOUNT DRIVE LEWISBURG, PA 17837 PH: 570-847-9519 brian@bsalandplan.com

CHECKED BY:

DESCRIPTION

SSE PROJECT No:

REVISIONS SYM DATE

SUBMISSIONS

ROAD

PARK

PHASE 1

<PRELIMINARY

CONSTRUCTION>

NOT FOR

10/02/19

06/07/19 TWP. SUBMISSION 1

DESCRIPTION

TWP. SUBMISSION 2

WHITEHALL

REGIONAL

DRAWN BY:

Fernsler

			LIC	SHTING	FIXTUR	E SCHE	DULE						
						PERFOR	MANCE				MOUNT	ING	
TAG	MANUFACTURER & SERIES	DESCRIPTION	LIGHT SOURCE		LUMINAIRE WATTS (W)	DELIVERED LUMENS (LM)	COLOR TEMP (K)	DIMMING STYLE	CRI (MINIMUM)	LUMEN MAINT.	TYPE	HEIGHT (AFF)	COMMENTS
PL1	LITHONIA - D-SERIES SIZE 0 AREA OR APPROVED EQUAL BY HUBBELL OR LSI	26"L x 13"W x 7"D POLE MOUNTED LED AREA LUMINAIRE. DIE-CAST ALUMINUM HOUSING WITH INTEGRAL HEAT SINK. DARK BRONZE FINISH. TYPE III MEDIUM DISTRIBUTION OPTICS. IP66 RATING. 22'-0" SQUARE POLE WITH DARK BRONZE FINISH.	LED	UNV/ MVOLT	38.0	4700	4000	0-10	70	L85 @ 100,000 HRS	POLE	25'-0"	MOUNT FIXTURE TO 4" SQUARE ALUMINUM POLE (SAME MANUFACTURER AND FINISH. REFER TOTAL
PL2	LITHONIA - D-SERIES SIZE 0 AREA OR APPROVED EQUAL BY HUBBELL OR LSI	26"L x 13"W x 7"D POLE MOUNTED LED AREA LUMINAIRE. DIE-CAST ALUMINUM HOUSING WITH INTEGRAL HEAT SINK. DARK BRONZE FINISH. TYPE IV MEDIUM DISTRIBUTION OPTICS. IP66 RATING. 22'-0" SQUARE POLE WITH DARK BRONZE FINISH. HOUSE SIDE SHIELD.	LED	UNV/ MVOLT	38.0	4700	4000	0-10	70	L85 @ 100,000 HRS	POLE	25'-0"	MOUNT FIXTURE TO 4" SQUARE ALUMINUM POLE (SAME MANUFACTURER AND FINISH. REFER DETAIL 3/E500 FOR POLE AND BASI INSTALLATION DETAILS.

	CIRCUIT SUMMARY BY ZONE												
POLE	CIRCUIT DESCRIPTION	# OF LUMINAIRE HEADS	# OF DRIVERS	VOLTAGE	PHASE	FULL LOAD AMPS *	CONTACTOR SIZE (A)	CONTACTOR ID	ZO				
<b>S</b> 1	SOCCER FIELD #1	13	13	480	3	20.8	30	C1	1				
S2	SOCCER FIELD #1	13	13	480	3	20.8	30	C2	1				
\$3	SOCCER FIELD #1	14	14	480	3	23.3	30	C3	1				
S4	SOCCER FIELD #1	14	14	480	3	23.3	30	C4	1				
\$3	SOCCER FIELD #2	13	13	480	3	20.8	30	C5	2				
S4	SOCCER FIELD #2	13	13	480	3	20.8	30	C6	2				
S5	SOCCER FIELD #2	13	13	480	3	20.8	30	C7	2				
\$6	SOCCER FIELD #2	13	13	480	3	20.8	30	C8	2				

\* = BASED ON AMPS PER DRIVER.

Г			TD	1 1050 51	4ED 0011		
			IR <i>F</i>	<b>ANSFORM</b>	<i>N</i> ER SCHE	DULE	
	TAG	KVA	PRIMARY VOLTAGE	SECONDARY VOLTAGE	MOUNTING	ENCLOSURE	NOTES
	T1	15	480V Δ	120/208V Y	PAD	4X	-

					BRANC	CH C	IRCUIT & FE	EEDER S	SCHEDULE					
KEY	NO. SETS	CONDUCTORS (AWG - KCMIL) (PER SET)	PATHWAY (PER SET)	CONDUCTOR TEMP. RATING	KEY	NO. SETS	CONDUCTORS (AWG - KCMIL) (PER SET)	PATHWAY (PER SET)	CONDUCTOR TEMP. RATING	KEY	NO. SETS	CONDUCTORS (AWG - KCMIL) (PER SET)	PATHWAY (PER SET)	CONDUCTOR TEMP. RATING
20.2G	1	2#12 & 1#12G	3/4" C	60° C	20.3G	1	3#12 & 1#12G	3/4" C	60° C	20.4G	1	4#12 & 1#12G	3/4" C	60° C
30.2G	1	2#10 & 1#10G	3/4" C	60° C	30.3G	1	3#10 & 1#10G	3/4" C	60° C	30.4G	1	4#10 & 1#10G	3/4" C	60° C
40.2G	1	2#8 & 1#10G	3/4" C	60° C	40.3G	1	3#8 & 1#10G	3/4" C	60° C	40.4G	1	4#8 & 1#10G	3/4" C	60° C
55.2G	1	2#6 & 1#10G	3/4" C	60° C	55.3G	1	3#6 & 1#10G	3/4" C	60° C	55.4G	1	4#6 & 1#10G	1" C	60° C
70.2G	1	2#4 & 1#8G	3/4" C	60° C	70.3G	1	3#4 & 1#8G	1" C	60° C	70.4G	1	4#4 & 1#8G	1-1/4" C	60° C
85.2G	1	2#3 & 1#8G	1" C	60° C	85.3G	1	3#3 & 1#8G	1" C	60° C	85.4G	1	4#3 & 1#8G	1-1/4" C	60° C
95.2G	1	2#2 & 1#8G	1" C	60° C	95.3G	1	3#2 & 1#8G	1" C	60° C	95.4G	1	4#2 & 1#8G	1-1/4" C	60° C
100.2G	1	2#3 & 1#8G	1" C	75° C	100.3G	1	3#3 & 1#8G	1-1/4" C	75° C	100.4G	1	4#3 & 1#8G	1-1/4" C	75° C
400.2G	1	2#600 & 1#3G	2-1/2" C	75° C	400.3G	1	3#600 & 1#3G	3" C	75° C	400.4G	1	4#600 & 1#3G	3-1/2"C	75° C

) TERMINATION PROVISIONS OF EQUIPMENT FOR CIRCUITS RATED 100 AMPERES OR LESS, OR MARKED FOR 14AWG THROUGH 1 AWG CONDUCTORS SHALL BE USED FOR THE FOLLOWING:

(3) CONDUCTORS WITH HIGHER TEMPERATURE RATINGS IF THE EQUIPMENT IS LISTED AND IDENTIFIED FOR USE WITH SUCH CONDUCTORS.

(4) FOR MOTORS MARKED WITH DESIGN LETTERS B, C OR D, CONDUCTORS HAVING AN INSULATION RATING OF 75°C (167°F) IR HIGHER SHALL BE PERMITTED TO BE USED, PROVIDED THE AMPACITY OF SUCH CONDUCTORS DOES NOT EXCEED THE 75°C (167°F) AMPACITY.


TERMINATION PROVISIONS OF EQUIPMENT FOR CIRCUITS RATED OVER 100 AMPERES, OR MARKED FOR CONDUCTORS LARGER THAN 1 AWG, SHALL BE USED ONLY FOR ONE OF THE FOLLOWING: (1) CONDUCTORS RATED 75°C (167°F). (2) CONDUCTORS WITH HIGHER TEMPERATURE RATINGS, PROVIDED THE AMPACITY OF SUCH CONDUCTORS DOES NOT EXCEED THE 75°C (167°F) AMPACITY OF THE CONDUCTOR SIZE USED, OR UP TO THEIR AMPACITY IF THE EQUIPMENT IS LISTED

.) TABLE BASED ON THE ALLOWABLE AMPACITIES OF COPPER CONDUCTORS IN TABLE 310.15 (B) (16) IN THE 2017 EDITION OF NFPA 70: NATIONAL ELECTRICAL CODE.

(1) CONDUCTORS RATED 60°C (140°F). (2) CONDUCTORS WITH HIGHER TEMPERATURE RATINGS, PROVIDED THE AMPACITY OF SUCH CONDUCTORS IS DETERMINED BASED ON THE 60°C (140°F) AMPACITY OF THE CONDUCTOR SIZE USED.

AND IDENTIFIED FOR USE WITH SUCH CONDUCTORS. 4.) MINIMUM CONDUIT SIZED BASED ON 90°C RATED CONDUCTORS WITH THHN INSULATION IN EMT. PROVIDE CONDUIT SIZE BASED ON NEC REQUIREMENTS IF OTHER PATHWAY TYPE IS USED.

5.) PROVIDE AN INDIVIDUAL CONDUIT FOR EACH FEEDER SET OF CONDUCTORS.



LIGHTING CALCULATION SUMMARY - OVERALL SITE

SITE LI	GHTING	CALCULA	ATION SU	MMARY	
CALCULATION AREA	AVERAGE (FC)	MAXIMUM (FC)	MINIMUM (FC)	AVG : MIN	MAX : MIN
ENTIRE SITE	-	76.1	0.0	-	-
PARKING LOT EAST	0.80	2.20	0.10	8.00	22.0
PARKING LOT WEST	0.80	1.70	0.10	8.00	17.0
SOCCER FIELD EAST	51.1	65.1	34.3	1.49	1.90
SOCCER FIELD WEST	51.1	66.6	37.5	1.36	1.78
NOTES:	LAROVE ODADE				



STAHL SHEAFFER ENGINEERING 301 SCIENCE PARK ROAD, SUITE 333 STATE COLLEGE, PA 16803

PH: 814-689-1562 FAX: 814-689-1885 WWW.SSE-LLC.COM

Fernsler Hutchinson

521 EAST BEAVER AVENUE STATE COLLEGE, PA 16801 t: 814-234-6806 f: 814-234-0256 e: fjfaia@aol.com





SSE PROJECT No:

CHECKED BY: DRAWN BY:

REVISIONS

SYM DATE DESCRIPTION

SUBMISSIONS


06/07/19 TWP. SUBMISSION 1 10/02/19 TWP. SUBMISSION 2

WHITEHALL ROAD REGIONAL PARK PHASE 1

<PRELIMINARY NOT FOR CONSTRUCTION>

SHEET NAME SITE PLAN -LIGHTING CALCULATIONS

E101



LIGHITNG CALCULATION SUMMARY - PROPERTY LINE

SCALE: 1" = 70'-0"

SITE LIGHTING CALCULATION SUMMARY											
CALCULATION AREA	AVERAGE (FC)	MAXIMUM (FC)	MINIMUM (FC)	AVG : MIN	MAX : MIN						
PROPERTY LINE (HORIZONTAL)	0.18	2.34	0.00	-	-						



STAHL SHEAFFER
ENGINEERING

301 SCIENCE PARK ROAD, SUITE 333
STATE COLLEGE, PA 16803
PH: 814-689-1562
FAX: 814-689-1885
WWW.SSE-LLC.COM

Fernsler Hutchinson ARCHITECTURE LLC 521 EAST BEAVER AVENUE STATE COLLEGE, PA 16801 t: 814-234-6806 f: 814-234-0256 e: fjfaia@aol.com





SSE PROJECT No: 16-248

DRAWN BY: CHECKED BY:

REVISIONS

REVISIONS
SYM DATE DESCRIPTION

SUBMISSIONS

DATE DESCRIPTION
06/07/19 TWP. SUBMISSION 1
10/02/19 TWP. SUBMISSION 2

WHITEHALL
ROAD
REGIONAL
PARK
PHASE 1

<PRELIMINARY
NOT FOR
CONSTRUCTION>

SHEET NAME

SITE PLAN 
LIGHTING

CALCULATIONS

E102

## **ABBREVIATIONS**

- & AND
- DEGREES
- Ø PHASE (E) EXISTING
- (R) RELOCATED
- A AMPS AC ABOVE COUNTER
- AFF ABOVE FINISHED FLOOR
- AFG ABOVE FINISHED GRADE
- AFI ARC FAULT CIRCUIT INTERRUPTOR
- AHU AIR HANDLING UNIT
- AIC AMPS INTERRUPTING CAPACITY
- AL ALUMINUM
- BLDG BUILDING
- C CONDUIT

CB CIRCUIT BREAKER

- CKT CIRCUIT
- CU COPPER DISC DISCONNECT
- DIST DISTRIBUTION
- DN DOWN EC ELECTRICAL CONTRACTOR
- EF EXHAUST FAN
- ELEC ELECTRIC OR ELECTRICAL
- E.O. ELECTRONICALLY OPERATED
- EMG EMERGENCY
- EXH EXHAUST
- F D FIRE DAMPER F/S D FIRE/SMOKE DAMPER
- FAAP FIRE ALARM ANNUNCIATOR PANE
- FACP FIRE ALARM CONTROL PANEL
- FAEP FIRE ALARM EXTENDER PANEL
- FCU FAN COIL UNIT
- FLA FULL LOAD AMPS G GROUND
- GND GROUND
- GFI GROUND FAULT CIRCUIT INTERRUPTER
- GEN GENERATOR
- HP HORSEPOWER KIT KITCHEN
- kW KILO WATTS
- kVA KILO VOLT-AMPERES
- LED LIGHT EMITTING DIODE
- LTG LIGHTING
- LSI LONG, SHORT AND INSTANTANEOUS TRIP CB
- LSIG LSI CB WITH GROUND FAULT PROTECTION

LFMC LIQUID-TIGHT FLEXIBLE METAL CONDUIT

- MAX MAXIMUM
- MC MECHANICAL CONTRACTOR
- MCA MINIMUM CIRCUIT AMPS MCB MAIN CIRCUIT BREAKER
- MECH MECHANICAL
- MIN MINIMUM
- MLO MAIN LUGS ONLY
- MOCP MAXIMUM OVERCURRENT PROTECTION DEVICE
- MTD MOUTED
- MTR MOTOR
- N NEUTRAL
- N/E NORMAL/EMERGENCY
- OE OVERHEAD ELECTRIC
- OE/T OVERHEAD ELECTRIC & TELECOM. OL OVERLOAD
- PB PUSH-BUTTON
- PC PLUMBING CONTRACTOR
- PH PHASE PL PILOT LIGHT
- PNL PANEL
- REC RECEPTACLE RM ROOM
- S D SMOKE DAMPER SD SMOKE DETECTOR
- UC UNDERCABINET
- UE UNDERGROUND ELECTRIC UL UNDERWRITERS LABORATORY
- UT UNDERGROUND TELECOMMUNICATIONS
- W WIRE WAP WIRELESS ACCESS POINT
- WP WEATHERPROOF

XFMR TRANSFORMER

## GENERAL REQUIREMENTS

- A. GENERAL: 1. THESE DRAWINGS ARE DIAGRAMMATIC IN NATURE AND DO NOT NECESSARILY SHOW ALL OFFSETS AND FITTINGS THAT WILL BE REQUIRED. COORDINATE CAREFULLY WITH EXISTING UTILITIES, EQUIPMENT AND
- 2. IT IS THE GENERAL INTENT OF THESE DRAWINGS AND SPECIFICATIONS THAT THE CONTRACTOR FURNISH AND INSTALL A COMPLETE AND WORKABLE ELECTRICAL SYSTEM IN COMPLIANCE WITH ALL APPLICABLE CODES AND REGULATIONS AND TO THE SATISFACTION OF THE ARCHITECT, ENGINEER
- AND OWNER. 3. CONTRACTOR IS RESPONSIBLE FOR VERIFICATION OF ALL FIELD CONDITIONS PRIOR TO PLACING BID, PURCHASING EQUIPMENT OR MATERIALS AND COMMENCEMENT OF ANY WORK, NOTIFY ENGINEER OF ANY DISCREPANCIES FOR RESOLUTION.
- 4. REPORT ANY OBSERVED CODE VIOLATIONS OF EXISTING SYSTEMS TO ENGINEER.
- 5. THE CONTRACTOR SHALL FURNISH, TO THE JOBSITE, AND INSTALL ALL EQUIPMENT AND MATERIALS SPECIFIED IN THE TECHNICAL SECTIONS OF THIS SPECIFICATION. THE INSTALLATION SHALL INCLUDE ALL ACCESSORIES REQUIRED TO ASSURE A COMPLETE AND WORKABLE INSTALLATION. 6. THE WORK SHALL INCLUDE THE FURNISHING OF ALL LABOR, MATERIALS,
- TOOLS, EQUIPMENT, TRANSPORTATION, PERMITS, INSPECTION FEES, SERVICES AND ALL NECESSARY RELATED ITEMS REQUIRED FOR A COMPLETE AND OPERATIONAL SYSTEM. 7. BEFORE SUBMITTAL OF BID, THOROUGHLY EXAMINE THE SITE. NO CLAIM
- FOR EXTRA COMPENSATION WILL BE RECOGNIZED IF DIFFICULTIES ARE ENCOUNTERED WHICH AN EXAMINATION OF SITE CONDITIONS, PRIOR TO EXECUTING CONTRACT WOULD HAVE REVEALED. B. CODE AND REGULATIONS: THE ENTIRE INSTALLATION SHALL CONFORM WITH
- ALL PERTINENT ORDINANCES, CODES AND REGULATIONS OF THE NATIONAL FIRE PROTECTION ASSOCIATION, THE 2008 VERSION OF THE NATIONAL ELECTRICAL CODE (NEC) AND OTHER REGULATORY BODIES HAVING JURISDICTION OVER THIS CLASS OF WORK.
- C. COORDINATION: ELECTRICAL CONTRACTOR SHALL SCHEDULE AND COORDINATE ALL ELECTRICAL OUTAGES WITH THE OWNER, A MINIMUM OF TWO WEEK (14-DAYS) PRIOR TO SHUTDOWN.
- D. SHOP DRAWINGS AND PRODUCT DATA 1. ALL EQUIPMENT MATERIALS SHALL BE AS SPECIFIED HEREIN.

—— TRENCH WIDTH ——

**UNDER VEHICLE PATHWAYS** 

TRENCH WIDTH ----

UNDER GRASS/NATURAL COVER

E500 SCALE: NOT TO SCALE

*NUTILITY DUCTBANK* 

GRADE

**FINISHED** 

PAD MOUNTED XFMR 'T1' ——

2. THE FOLLOWING MATERIALS AND EQUIPMENT SHALL BE SUBMITTED:

ROADWAY STRUCTURE, BY OTHERS

GRADE

ON CENTER

- DETECTABLE WARNING TAPE, (6" MIN.

PROCTOR) FROM ABOVE LIMESTONE

COVERAGE, ALL SIDES OF CONDUITS

SCREENING UP TO LOAD SUBBASE

WIDTH) AT 12" BELOW FINISHED

COMPACTED 2A AGGREGATE (100%)

12" MIN.FINE LIMESTONE SCREENING

- REINFORCEMENT SHALL BE #4

DETECTABLE WARNING TAPE,

FINISHED GRADE

COMPACTED BACKFILL

BLOCKS, ETC

(6" MIN. WIDTH) AT 12" BELOW

EXCAVATION MATERIAL, TO BE

(1) 4" CONDUIT FOR COMMUNICATIONS

ELECTRICAL PRIMARY (1 ACTIVE, I SPARE)

SERVICE AND (2) 5" CONDUITS FOR

FREE OF LARGE STONES,

SAND FILL (3" MIN COVERAGE,

ALL SIDES OF CONDUITS)

STIRRUPS SPACED 12" ON CENTER

AND #6 LONGITUDINALS SPACED 6"

SERVICE AND (2) 5" CONDUITS FOR

(1) 4" CONDUIT FOR COMMUNICATIONS

ELECTRICAL PRIMARY (1 ACTIVE, I SPARE)

- a. FIRESTOPPING MATERIALS.
- b. TRANSFORMERS.
- c. SERVICE SWITCHES AND GANG METERS.
- d. PANELBOARDS & CIRCUIT BREAKERS.
- e. DISCONNECT SWITCHES. f. LIGHTING FIXTURES AND LAMPS.
- g. DEVICES, FACEPLATES AND BOXES.
- h. RECEPTACLES. i. LIGHTING SWITCHES AND CONTROLS
- j. TELECOMMUNICATIONS OUTLETS & CABLING k. BUILDING POWER WIRING AND CONDUIT. I. FIRE ALARM SYSTEM AND COMPONENTS (DETECTION AND
- NOTIFICATION APPLIANCES, ETC.). E. GUARANTEE: THE ENTIRE INSTALLATION SHALL BE GUARANTEED FOR A PERIOD OF ONE (1) YEAR FROM DATE OF ACCEPTANCE, BY THE OWNER, UNLESS OTHERWISE SPECIFIED, AGAINST DEFECTS IN MATERIAL AND WORKMANSHIP, IN ACCORDANCE WITH THE TERMS OF THE CONTRACT. GUARANTEE SHALL COVER THE REPLACEMENT, WITHOUT COST TO THE OWNER OF ANY AND ALL
- ITEMS THAT SHALL BECOME DEFECTIVE WITHIN THE STATED TIME. F. REMOVAL OF RUBBISH: PERIODICALLY AND AT THE COMPLETION OF THE WORK CONTEMPLATED UNDER THESE SPECIFICATIONS, THE CONTRACTOR SHALL REMOVE FROM THE BUILDING AND SITE ALL RUBBISH AND ACCUMULATED MATERIALS OF WHATEVER NATURE NOT CAUSED BY OTHER TRADES, AND SHALL LEAVE THE WORK IN A CLEAN, ORDERLY AND ACCEPTABLE CONDITION.
- G. MATERIALS AND EQUIPMENT: ALL EQUIPMENT OR APPARATUS OF ANY ONE SYSTEM MUST BE THE PRODUCT OF ONE MANUFACTURER, OR EQUIVALENT PRODUCTS OF A NUMBER OF MANUFACTURERS WHICH ARE SUITABLE FOR USE IN A UNIFIED OR ASSEMBLED SYSTEM. ALL MATERIALS AND EQUIPMENT TO BE FURNISHED UNDER THIS CONTRACT SHALL BE NEW.
- H. EQUIPMENT SUPPORTS AND ACCESS: FURNISH AND INSTALL ALL STRUCTURAL STEEL MEMBERS, HANGERS AND SUPPORTS AS REQUIRED FOR SUPPORT OF EQUIPMENT AND MATERIALS (CONDUIT, EQUIPMENT, DEVICES, ETC.) IN ACCORDANCE WITH INDUSTRY STANDARDS. EXTERIOR SUPPORTS SHALL BE

SHOE-BOX STYLE HEAD,

FIXTURE SCHEDULE AND

DIRECT MOUNTING

SQUARE ARM EXTENSION -

REMOVABLE HANDHOLE COVER —

24" DIA. CONCRETE BASE -

FINISHED GRADE

E500 SCALE: NOT TO SCALE

PLANS FOR TYPE ———

REFER TO LIGHTING

- GALVANIZED STAINLESS STEEL. I. FINISH AND ACCESSORIES: THE CONTRACTOR SHALL CAREFULLY INVESTIGATE
  - THE STRUCTURAL WORK AND ALL FINISH CONDITIONS AFFECTING HIS WORK. HE SHALL ARRANGE HIS WORK IN ACCORDANCE WITH SUCH CONDITIONS, FURNISHING ALL ACCESSORIES TO MEET SUCH CONDITIONS.
  - J. CUTTING, PATCHING AND PAINTING: 1. PROVIDE ALL CUTTING AND PATCHING FOR LINTELS, RECESSES, CHASES, AND MAJOR OPENINGS IN ROOFS, WALLS, FLOORS, CEILINGS, AND
  - PARTITIONS TO RECEIVE CONDUITS, BUS DUCTS, AND EQUIPMENT. 2. PROVIDE ALL CUTTING AND PATCHING FOR MINOR OPENINGS, AND REPAIR ALL DAMAGED AREAS. PAINT SHALL MATCH EXISTING
  - 3. ALL CUTTING AND PATCHING SHALL BE DONE IN A NEAT AND WORKMANLIKE MANNER BY WORKMEN SKILLED IN THE APPLICABLE TRADE INVOLVED, AND SHALL BE SUBJECT TO THE APPROVAL OF THE ENGINEER/ARCHITECT.
  - 4. THE CONTRACTOR SHALL FURNISH AND PLACE ALL SLEEVES REQUIRED FOR CONDUITS, BUS DUCTS, ETC., PASSING THROUGH ROOFS, FLOORS, WALLS, AND CEILINGS ALL ANCHORS AND INSERTS REQUIRED FOR CONDUITS AND EQUIPMENT FURNISHED UNDER THIS CONTRACT. J. FIELD QUALITY CONTROL:
  - 1. INSPECTION AND TESTING OF ALL APPLICABLE ELECTRICAL EQUIPMENT SHALL BE DONE IN ACCORDANCE WITH THE LATEST VERSION OF NETA TESTING SPECIFICATIONS.
  - 2. PERFORM SYSTEM FUNCTION TESTS UPON COMPLETION OF THE EQUIPMENT TESTS AS OUTLINED. IT IS THE PURPOSE OF THE SYSTEM FUNCTION TESTS TO PROVE THE CORRECT INTERACTION OF ALL SENSING, PROCESS AND ACTION DEVICES.
  - K. INSPECTION AND TESTING: ELECTRICAL WORK SHALL BE INSPECTED BY THE CODE OFFICIAL AS PRESCRIBED BY THE MUNICIPALITY THE WORK IS BEING PERFORMED IN.
  - L. PROJECT CLOSE-OUT: 1. CLEAN ALL WORK AT PROJECT COMPLETION, SUBJECT TO ACCEPTANCE OF OWNER.
  - 2. MAINTAIN A RECORD SET OF DRAWINGS SHOWING ALL CHANGES DURING CONSTRUCTION PROCESS. DELIVER THESE RECORD DRAWINGS TO ARCHITECT AT COMPLETION OF PROJECT.

- CAPPED TOP FOR

- DRILL HOLES IN SIDE OF

ARM MOUNT IN FIELD

4" SQUARE, NON-TAPERED

ALUMINUM POLE; REFER TO

ANCHOR NUTS & BOLTS, GALVANIZED

STEEL; SEE MANUFACTURERS SPEC FOR

SCHEDULE FOR DETAILS

(COLOR, HEIGHT, ETC.)

**BOLT ARRANGEMENT** 

POLE TO ACCEPT DIRECT

SIDE DRILLING

## **ELECTRICAL SYMBOLS**

120V 20A DUPLEX RECEPTACLE PANELBOARD: 120/208V, 3Ø, 4W; SURFACE MOUNTED

PANELBOARD: 277/480V, 3Ø, 4W; SURFACE MOUNTED DISCONNECT SWITCH; SIZE AND VOLTAGE AS SCHEDULED COMBINATION MOTOR STARTER/DISCONNECT SWITCH;

SIZE AND VOLTAGE AS SCHEDULED T DRY-TYPE XFMR; SIZE AND VOLTAGE AS SCHEDULED M MOTORIZED DAMPER

SITEWORK: UTILITY POLE (MH) SITEWORK: MANHOLE


## LIGHTING SYMBOLS


POLE MOUNTED SITE LIGHTING FIXTURE, QUANTITY AND DIRECTION OF HEADS AS INDICATED


## MISC. SYMBOLS

- ----- NEW WORK
- ----- EXISTING WORK
- ---- DEMOLITION WORK
- – UNDERGROUND ELECTRICAL PATHWAY — -T- — UNDERGROUND COMMUNICATIONS PATHWAY
- ··· OVERHEAD ELECTRICAL UTILITY LINES
- HOMERUN TO PANELBOARD
- CONDUCTOR; (2) WIRE + GND UNLESS NOTED; REFER TO PANEL SCHEDULES FOR WIRE AND PATHWAY SIZE SHORT TICK MARKS INDICATE NUMBER OF PHASE CONDUCTORS,
- LONG TICK MARKS INDICATE NUMBER OF NEUTRAL CONDUCTORS. REFER TO PANEL SCHEDULES FOR SIZE OF CONDUCTORS, GROUND WIRES, AND CONDUITS.









5 POLE MOUNTED LUMINAIRE BASE DETAIL (PL1 & PL2) - ELEVATION E500 SCALE: NOT TO SCALE

## 1-1/4" SCHEDULE 80 PVC CONDUIT FOR METERING TELEPHONE LINE, NOTE 5 - COMMUNICATIONS GROUND GROUND ROD -4" <del>--| |--</del> 54" TRANSFORMER COMPARTMENT 1" CHAMFER ON BARRIER —— **OUTSIDE EDGES** – 6"x6" 6/6 MESH, TYP. 30" MIN.

- NOTE 1 / STOP REINFORCING 3" FROM

ALL SIDES AND OPENINGS

FOUNDATION PAD

## **DETAIL NOTES**

TYPE II PVC, SCHEDULE 80 ELBOW

6" MIN. CRUSHED STONE OR

GRAVEL (WELL COMPACTED) -

5/8" DIA. x 8'L GROUND ROD, AND

#6 AWG COPPER GROUND WIRING -

1. ELECTRICAL CONTRACTOR SHALL CONTACT THE UTILITY COMPANY ON BEHALF OF THE OWNER PRIOR TO BEGINNING WORK TO DISCUSS THE DETAILS OF TRANSFORMER FOUNDATION POSITION AND ORIENTATION, WORKING CLEARANCES, BARRIER PROTECTION, CONSTRUCTION SPECIFICATIONS, AND INSPECTION PROCEDURES. THE ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR INSTALLING THE TRANSFORMER FOUNDATION. THE CONTRACTOR SHALL PROVIDE A CLEAR AND FIRM APPROACH TO THE TRANSFORMER FOUNDATION AND KEEP THE AREA ABOVE THE TRANSFORMER CLEAR OF OBSTRUCTIONS THAT MAY BLOCK THE USE OF COMPANY VEHICLES (E.G., CRANE ACCESS TO THE TRANSFORMER).

- COMMUNICATIONS

→ 1-1/4" SCHEDULE 80 PVC CONDUIT FOR

METERING TELEPHONE LINE, NOTE 5

GROUND

TYPE II PVC, SCHEDULE


80 ELBOWS, TYP.

- SECONDARY CONDUITS SHALL NOT EXTEND EXTEND MORE THAN 2 INCHES ABOVE THE TOP OF FOUNDATION. PRIMARY CONDUITS SHOULD BE CUT OFF 2 INCHES BELOW THE TOP OF FOUNDATION TO ALLOW FOR TERMINATING THE CABLES. 3. INSTALL ALL CONDUITS BEFORE PLACING PAD. CONDUITS SHOULD NOT BE PLACED UNDER SECTIONS OF PAD SUPPORTING TRANSFORMER SO THAT ORIGINAL
- GROUND WILL NOT BE DISTURBED. 4. BACKFILL SHALL BE CLEAN GRANULAR SOIL, FREE OF LARGE STONES AND PERISHABLE MATERIAL. ALL BACKFILL SHALL BE SPREAD AND COMPACTED IN MAXIMUM
- LAYERS OF 8 INCHES. THOROUGHLY COMPACT BASE CRUSHED STONE OR GRAVEL.
- CONCRETE PAD MAY BE POURED-IN-PLACE OR MAY BE PRECAST (4000 MIN. PSI CONCRETE). TO PREVENT WATER MIGRATION FROM CONCRETE WHEN POURING, PLACE WATERPROOF MEMBRANE ON CRUSHED STONE OR GRAVEL BEFORE POURING
- 8. REINFORCING WIRE MESH SHALL CONFORM TO ASTM DESIGNATION A185. 9. CEMENT TO BE 1 OR 1-A AND MEETING ASTM DESIGNATIONS C-150 AND C-175 RESPECTIVELY. 10. POURED PAD CONCRETE TO DEVELOP MINIMUM 4000 PSI AT 28 DAYS AGE, CONTAIN MINIMUM OF 5.5 BAGS OF CEMENT PER CUBIC YARD AND MAXIMUM OF 6
- GALLONS OF WATER PER 94-POUND BAG OF CEMENT, AND CONFORM TO ASTM DESIGNATION C-94. FOURTEEN (14) DAYS MINIMUM DRYING TIME BEFORE TRANSFORMER IS SET. 11. SEAL ALL OPENINGS AROUND CONDUITS WITH GROUT; CAP ALL SPARE CONDUITS TO PREVENT ENTRY OF RODENTS AND ANIMALS INTO TRANSFORMER COMPARTMENT.
- 12. IF CONDUIT EXTENDS INTO BUILDING, IT SHALL BE SEALED (PER NEC) AT BUILDING END TO PREVENT GAS FROM ENTERING BUILDING THROUGH THE CONDUIT. 13. COMMUNICATION GROUND – THE NESC REQUIRES BONDING OF ALL COMMUNICATIONS EQUIPMENT (TELEPHONE, CATV, ETC.) THAT ARE WITHIN SIX (6) FEET OF THE PAD-MOUNTED TRANSFORMER. THE WIRE FOR BONDING COMMUNICATIONS EQUIPMENT SHALL BE MINIMUM #6 AWG SOLID COPPER WIRE THAT IS ATTACHED DIRECTLY TO GROUND ROD, RUNS UNDERNEATH THE CONCRETE PAD, EXTENDS 12 INCHES BEYOND THE EDGE OF THE PAD, AND FINALLY RUNS ALONGSIDE THE PAD FOUNDATION. THE REQUIRED MINIMUM LENGTH OF WIRE IS 8-1/2 FEET.

UNDER FOUNDATION. ELECTRICAL CONTRACTOR SHALL CONTACT THE COMPANY FOR DETAILS.

14. IN AREAS WHERE SETTLING MAY OCCUR, INSTALL THREE (3) CONCRETE PIERS, 8-INCH MINIMUM DIAMETER, 36 INCHES DEEP, IN A TRIANGULAR CONFIGURATION

3-PHASE PAD-MOUNTED UTILITY TRANSFORMER FOUNTATION



6 ONE-LINE DIAGRAM

E500 SCALE: NOT TO SCALE

PENOENGINEERING MECHANICAL & ELECTRICAL CONSULTANTS 2746 WEST COLLEGE AVENUE PROJECT NO.: E38095 STATE COLLEGE, PA 16801 © 2018 PENO ENGINEERI 814-234-7366

2643 Gateway Drive, Suite #1

State College, PA 16801

Phone: (814) 231-3071

Fax: (814) 235-7832

www.crpr.org

301 SCIENCE PARK ROAD, SUITE 333

STATE COLLEGE, PA 16803

PH: 814-689-1562

FAX: 814-689-1885

WWW.SSE-LLC.COM

Hutchinson

521 EAST BEAVER AVENUE

STATE COLLEGE, PA 16801

t: 814-234-6806

f: 814-234-0256

e: fjfaia@aol.com

Fernsler

ARCHITECTURE LLC

182 FAIRMOUNT DRIVE LEWISBURG, PA 17837 PH: 570-847-9519 brian@bsalandplan.com

SSE PROJECT No: CHECKED BY: DRAWN BY:

**REVISIONS** SYM DATE DESCRIPTION

SUBMISSIONS

DATE DESCRIPTION

10/02/19 TWP. SUBMISSION 2

TWP. SUBMISSION 1

WHITEHALL ROAD REGIONAL PARK PHASE 1

<PRELIMINARY NOT FOR CONSTRUCTION>

**DETAILS** -

E500

**ELECTRICAL** 

3" GALVANIZED RIGID METAL CONDUITS. OFF-ON-AUTO KEYED SWITCHES' CAPPED AND CONCRETE ENCASED IN DIGITAL CELLULAR ANTENNA -GROUND, TYP. ONE FOR EACH SPORTS LIGHTING ONE FOR EACH STORIO E.E.


POLE AND EACH PARKING LOT


ALL HARDWARE SHALL BE GROUNDED PER NEC CONTROL AND MONITORING - 400A 3-PHASE PANEL 'SF2' CABINET METER SOCKET 9996 PAD/VAULT MOUNTED 9999 UTILITY TRANSFORMER — CONDUIT SHALL BE GROUNDED AT TRANSFORMER CONCRETE ENCASED POSTS; 36" INTO GROUND, MIN., TYP.

3 POLE MOUNTED LUMINAIRE DETAIL (PL1 & PL2)

MOUNTING HARDWARE, USE (5) 12-GAUGE 1-5/8" X 1-5/8" CONTINUOUS SLOT HOT DIPPED GALVANIZE CHANNELS WITH 1-1/4" X 5/16" DIA. 13 THREAD SPRING NUT (2 PER CHANNEL), 5/16" HEX NUT, AND LOCK WASHER SECURELY MOUNTED TO SUPPORT POSTS, TYP.

8 SOCCER FIELD ELECTRICAL SERVICE ELEVATION





# Required Landscape Plantings

	BUFFER	ARD LANDSCAPING						
		rs Development – 645 LF – Buff Drive Plantings and Wood's Ed			derstory Tree	s, 9 Shrubs / 10	00 LF)	
	Symbol	Botanical Name / Common Name	Size	Condition	Mature Height	Mature Spread	Quantity – Req. by Ordinance	Phase I Quantity
	Trees						13	11+5*+1**=17
	AS	Acer saccharum Sugar Maple	1.5" Cal.	B&B	70′	75′		2
	QB	Quercus bicolor Swamp White Oak	1.5" Cal.	7 gal. or bareroot	55′	50′		4
	QC	Quercus coccinea Scarlet Oak	1.5" Cal.	7 gal. or bareroot	60′	50′		3
	QM	Quercus macrocarpa Burr Oak	1.5" Cal.	7 gal. or bareroot	70′	75′		2
	QP	Quercus phellos Willow Oak	1.5" Cal.	7 gal. or bareroot	50′	40′		3
	QS	Quercus shumardii Shumard Oak	1.5" Cal.	7 gal. or bareroot	65′	65′		3
	Understor	y Trees / Evergreen					32 1	1+28*+3**=42
(+)(+)	AL	Amelanchier laevis Allegheny Serviceberry	1" Cal.	5 gal. or bareroot	20′	20′		10
4	CaC	Carpinus caroliniana American Hornbeam	1" Cal.	5 gal. or bareroot	25′	25′		11
	СС	Cercis canadensis Eastern Redbud	1" Cal.	5 gal. or bareroot	25′	25′		10
	CF	Cornus florida Flowering Dogwood	1" Cal.	5 gal. or bareroot	25′	25′		11
	Shrubs						58	28+0*+30**=58
	CA	Clethera alnifolia Sweet Pepperbush	#2 Gal	3-4' Ht.	5′	5′		5
	IG	llex glabra Inkberry	#2 Gal	3-4'Ht.	5′	5′		9
	ltV	Itea virginica Virginia Sweetspire	#2 Gal	3-4' Ht.	8′	8′		4
	SC	Sambucus Canadensis American Black Elderberry	#2 Gal	3-4' Ht.	10′+	10′+		2
	VN	Viburnum nudum Possum Haw Viburnum	#2 Gal	3-4' Ht.	8'+	8′		5
	VD	Viburnum dentatum Arrowwood Viburnum	#2 Gal	3-4' Ht.	8'+	8'+		3
		m the Woods Edge planting. derstory Trees and Shrubs in Er	ntry Sign / O	rnamental Mem	orial Garden	planting.		
	Habitat ar	d Pollinator Plantings			Additi	onal La	ndscape P	lantings **
	Forested E	dge / Flowering Roadside Mix	lbs.	16,000 SF / (	0.37 Acres	·	C108.8 Jaded Area Roadside Onservation Seed or	

	Symbol	Botanical Name / Common Name	Size	Condition	Mature Height	Mature Spread	Quantity – Req. by Ordinance	Phase I Quantity
	Trees						NA	1
$\overline{}$	AS	Acer saccharum Sugar Maple	1.5″ Cal.	B&B	70′	75′		1
$\overline{\bigcirc}$	Understor	ry Trees / Evergreen					NA	3
	CF	Cornus florida Flowering Dogwood	1" Cal.	B&B	25′	25′		3
Ωο	Shrubs						NA	30
	TBD	Large Shrubs (14) TBD	3 Gal	3-4' Ht.	12′	12′		14
	TBD	Small Shrubs (16) TBD	3 Gal	3-4'Ht.	8′	8′		16
	Annual an	d Perennial Planting Beds		La	ndscap	oe Plant	tings **	
	Annual and	d Perennial Beds (4)	1,200 SF	4" Plugs*	1.5-3′	2-3′	NA	

	BUFFER YARD LANDSCAPING									
		SCBWA Land – 1,090 LF – Buffer Type D (2 Trees, 6 Understory Trees, 12 Shrubs / 100 LF) North - Northwest Boundary to Buffer Future Native Grassland Planting and Source Water Protection Area								
	Symbol	Botanical Name / Common Name	Size	Condition	Mature Height	Mature Spread	Quantity – Req. by Ordinance	Phase I Quantity		
	Trees						22	22		
XTX	CS	Catalpa speciosa Catalpa	1.5" Cal.	7 gal. or bareroot	50′	40′		6		
	PS	Pinus strobus White Pine	1.5" Cal.	B&B	70′	50′		9		
	QC	Quercus coccinea Scarlet Oak	1.5" Cal.	7 gal. or bareroot	60′	50′		3		
	QP	Quercus phellos Willow Oak	1.5" Cal.	7 gal. or bareroot	50′	40′		4		
	Understory	,					65	65		
	AL	Amelanchier laevis Allegheny Serviceberry	1" Cal.	5 gal. or bareroot	20′	20′		11		
	CaC	Carpinus caroliniana American Hornbeam	1" Cal.	5 gal. or bareroot	25′	25′		11		
	CC	Cercis canadensis Eastern Redbud	1" Cal.	5 gal. or bareroot	25′	25′		11		
	CF	Cornus florida Flowering Dogwood	1" Cal.	5 gal. or bareroot	25′	25′		11		
	MS	Malus 'Sutyzam 'Sugar Tyme 'Sugar Tyme' Flowering Crak		5 gal. or bareroot	40′	35′		11		
	PVS	Prunus sargentii 'Sargents' Sargent Cherry	1"Cal.	5 gal. or bareroot	35′	30′		10		
	Shrubs						131	131		
	CA	Clethera alnifolia Sweet Pepperbush	#2 Gal	3-4′Ht.	5′	5′		17		
	IG	llex glabra Inkberry	#2 Gal	3-4'Ht.	5′	5′		16		
	IV	llex verticillata Winterberry	#2 Gal	3-4'Ht.	5′	5′		16		
	ltV	Itea virginica Virginia Sweetspire	#2 Gal	3-4′Ht.	8′	8′		16		
	LB	Lindera benzoin Spicebush	#2 Gal	3-4′Ht.	8′	8′		17		
	SC	Sambucus Canadensis American Black Elderberry	#2 Gal	3-4′Ht.	10'+	10'+		16		
	VN	Viburnum nudum Possum Haw Viburnum	#2 Gal	3-4′Ht.	8'+	8′		16		
	VD	Viburnum dentatum Arrowwood Viburnum	#2 Gal	3-4′Ht.	8'+	8'+		17		

		BOFFER IARD LANDSCAFING								
		Penn State University Land (South) - 1,825 LF - Buffer Type A South Boundary to Buffer Future Natural / Recreation Area  (6 Trees, 2 Understory Trees, 0 Shrubs / 100 LF)								
	Symbol	Botanical Name / Common Name	Size	Condition	Mature Height	Mature Spread	Quantity – Req. by Ordinance	Phase I Quantity		
	Trees						110	110		
	CS	Catalpa speciosa Catalpa	1.5" Cal.	7 gal. or bareroot	50′	40′		18		
	PS	Pinus strobus White Pine	1.5" Cal.	B&B	70′	50′		37		
	QB	Quercus bicolor Swamp White Oak	1.5" Cal.	7 gal. or bareroot	55′	50′		18		
	QC	Quercus coccinea Scarlet Oak	1.5" Cal.	7 gal. or bareroot	60′	50′		14		
	QP	Quercus phellos Willow Oak	1.5" Cal.	7 gal. or bareroot	50′	40′		23		
	Understory	1					36	36		
	AL	Amelanchier laevis Allegheny Serviceberry	1" Cal.	5 gal. or bareroot	20′	20′		6		
+	CaC	Carpinus caroliniana American Hornbeam	1" Cal.	5 gal. or bareroot	25′	25′		6		
	СС	Cercis canadensis Eastern Redbud	1" Cal.	5 gal. or bareroot	25′	25′		6		
	CF	Cornus florida Flowering Dogwood	1" Cal.	5 gal. or bareroot	25′	25′		6		
	MS	Malus 'Sutyzam 'Sugar Tyme' 'Sugar Tyme' Flowering Crab		5 gal. or bareroot	40′	35′		6		
	PVS	Prunus sargentii ' Sargents' Sargent Cherry	1" Cal.	5 gal. or bareroot	35′	30′		6		
	Shrubs						0	0		
	Habitat and	d Pollinator Plantings			Additi	onal La	ndscape Pla	antings **		
	Pollinator So	eed Mix	lbs.	5,500 SF / 0.	13Acres		ry Native Pollinator Mi Inservation Seed or ap 108.8			
	Little Bluest	em Upland Meadow	lbs.	26,000 SF / 0	0.61 Acres	Schizachyr	ium scoparium PA-Ecc	otype		

**BUFFER YARD LANDSCAPING** 

		Penn State University Land (East) - 1,320 LF - Buffer Type A (6 Trees, 2 Understory Trees, 0 Shrubs / 100 LF) East Boundary to Buffer Future Natural / Recreation Area							
	Symbol	Botanical Name / Common Name	Size	Condition	Mature Height	Mature Spread	Quantity – Req. by Ordinance	Phase I Quantity	
	Trees						79	79	
	AS	Acer saccharum Sugar Maple	1.5" Cal.	7 gal. or bareroot	70′	50′		6	
	CG	Carya glabra Pignut Hickory	1.5" Cal.	7 gal. or bareroot	60′	35′		7	
	CS	Catalpa speciosa Catalpa	1.5" Cal.	7 gal. or bareroot	50′	40′		4	
	НС	Halesia carolina Carolina Silverbell	1.5" Cal.	7 gal. or bareroot	30′	35′		8	
	LT	Liriodendron tulipifera Tulip Tree	1.5" Cal.	7 gal. or bareroot	70′	50′		8	
	NS	Nyssa sylvatica Blackgum	1.5" Cal.	7 gal. or bareroot	40′	35′		8	
	OV	Ostrya virginiana American Hophornbeam	1.5" Cal.	7 gal. or bareroot	40′	35′		8	
	OA	Oxydendrum arboreum Sourwood	1.5" Cal.	7 gal. or bareroot	35′	25′		8	
	PSC	Prunus sargentii 'Columnar' Columnar Sargents Cherry	1.5" Cal.	7 gal. or bareroot	30′	30′		8	
	QB	Quercus bicolor Swamp White Oak	1.5" Cal.	7 gal. or bareroot	55′	50′		8	
	QM	Quercus macrocarpa Burr Oak	1.5" Cal.	7 gal. or bareroot	70′	75′		6	
	Understor	у					26	26	
•	AL	Amelanchier laevis Allegheny Serviceberry	1" Cal.	5 gal. or bareroot	20′	20′		5	
	CaC	Carpinus caroliniana American Hornbeam	1" Cal.	5 gal. or bareroot	25′	25′		5	
	CF	Cornus florida Flowering Dogwood	1" Cal.	5 gal. or bareroot	25′	25′		5	
	MS	Malus 'Sutyzam 'Sugar Tyme 'Sugar Tyme' Flowering Crab		5 gal. or bareroot	40′	35′		5	
	PVS	Prunus sargentii 'Sargents' Sargent Cherry	1" Cal.	5 gal. or bareroot	35′	30′		6	
	Shrubs						0	0	
	Habitat ar	nd Pollinator Plantings		A	dditio	nal Land	dscape Plar	ntings *	
	Forested E	dge / Flowering Roadside Mix	lbs.	7,150 SF / 0.	16 Acres		aded Area Roadside S nservation Seed or ap 108.8		
	Pollinator S	Seed Mix	lbs.	14,000 SF / (	0.32 Acres	Mesic to Dr by Ernst Co	y Native Pollinator Mi nservation Seed or ap		
	Little Blues	stem Upland Meadow	lbs. 40,000 SF / 0.91 Acres			See Sheet C108.8  Schizachyrium scoparium PA-Ecotype			

PARKING	PARKING LOT (EAST)							
Symbol	Botanical Name / Common Name	Size	Condition	Mature Height	Mature Spread	Quantity – Req. by Ordinance	Phase I Quantity	
Trees						20	24	
AR	Acer rubrum 'Red Sunset' Red Sunset Red Maple	1.5" Cal.	B&B	50′	40′		12	
CCI	Crataegus crus-galli var. iner Thornless Cockspur Hawthor		B&B	20′	20′		12	

	PARKING	PARKING LOT (WEST)								
	Symbol	Botanical Name / Common Name	Size	Condition	Mature Height	Mature Spread	Quantity – Req. by Ordinance	Phase I Quantity		
	Trees						29	33		
	AR	Acer rubrum 'Red Sunset' Red Sunset Red Maple	1.5" Cal.	B&B	50′	40′		17		
	CCI	Crataegus crus-galli var. ine Thornless Cockspur Hawth		B&B	20′	20′		16		

2643 Gateway Drive, Suite #1
State College, PA 16801
Phone: (814) 231-3071
Fax: (814) 235-7832
www.crpr.org

STAHL SHEAFFER
ENGINEERING

301 SCIENCE PARK ROAD, SUITE 333
STATE COLLEGE, PA 16803
PH: 814-689-1562

Fernsler Hutchinson

FAX: 814-689-1885 WWW.SSE-LLC.COM

521 EAST BEAVER AVENUE STATE COLLEGE, PA 16801 t: 814-234-6806 f: 814-234-0256 e: fjfaia@aol.com



182 FAIRMOUNT DRIVE LEWISBURG, PA 17837 PH: 570-847-9519

brian@bsalandplan.com

SSE PROJECT No: 16-248

DRAWN BY: CHECKED BY:

REVISIONS

SYM DATE DESCRIPTION

IDMICOLONIO

SUBMISSIONS


DATE DESCRIPTION
06/07/19 TWP. SUBMISSION 1
10/02/19 TWP. SUBMISSION 2

WHITEHALL ROAD REGIONAL PARK PHASE 1


<PRELIMINARY
NOT FOR
CONSTRUCTION>

LANDSCAPING PLANTING LIST


101



## EVERGREEN TREE PLANTING DETAIL



## UNDERSTORY TREE (BARE ROOT) PLANTING DETAIL



## NOTES:

- 1. TREE SHALL BE MARKED ON ITS NORTH FACING SIDE AT NURSERY. TREE SHALL BE PLANTED
- WITH ORIGINAL NORTH FACING SIDE FACING NORTH ON SITE.
- 2. REMOVE AND SEPARATE TOPSOIL AND SUBSOIL FROM PLANTING HOLE FOR USE AS BACKFILL,
  3. IF ROOTBALL IS PACKAGED IN 'PLASTIC BURLAP' OR TREATED BURLAP, REMOVE BURLAP
- 4. HEAL-IN SOIL AROUND THE ENTIRE ROOTBALL TO ELIMINATE AIR POCKETS.
- 5. WATER AFTER PLANTING AND AS NECESSARY UNTIL ESTABLISHED.
- PLANT SHRUBS IN SPRING (APRIL MAY) OR FALL (SEPTEMBER EARLY OCTOBER).
   DO NOT DAMAGE MAIN ROOTS OR ROOT BALL WHEN INSTALLING TREE STAKES.
- ALL STAKES, GUYWIRES, AND TIES TO BE REMOVED AFTER THE FIRST YEAR OF GROWTH, UNLESS OTHERWISE SPECIFIED BY THE LANDSCAPE ARHICTECT.


6" DEPTH BARK MULCH ✓ KEEP 3" AWAY FROM TRUNK REMOVE TOP OF BASKET, ROPE AND BURLAP PRIOR TO BACKFILLING FORM 6" MULCH SAUCER OR BERM ON DOWNSLOPE EDGE ELECTRICATED SO BETHETHETES BACKFILL WITH UNAMENDED SOIL PREVIOUSLY REMOVED FROM PIT ROOTBALL WIDTH , PLACE ORIGINAL SUBSOIL FIRST, THEN TOPSOIL 3X DIAMETER OF ROOTBALL UNDISTURBED SUBGRADE OR COMPACTED BACKFILL

NOTES

- 1. REMOVE AND SEPARATE TOPSOIL AND SUBSOIL FROM PLANTING HOLE FOR USE AS BACKFILL.
- REMOVE TOP OF BASKET, ROPE AND BURLAP PRIOR TO BACKFILLING.
   IF ROOTBALL IS PACKAGED IN 'PLASTIC BURLAP' OR TREATED BURLAP, REMOVE BURLAP
- COMPLETELY.

  4. HEAL-IN SOIL AROUND THE ENTIRE ROOTBALL TO ELIMINATE AIR POCKETS.
- WATER AFTER PLANTING AND AS NECESSARY UNTIL ESTABLISHED.
   PLANT SHRUBS IN SPRING (APRIL MAY) OR FALL (SEPTEMBER EARLY OCTOBER).

SHRUB PLANTING DETAIL



2643 Gateway Drive, Suite #1
State College, PA 16801
Phone: (814) 231-3071
Fax: (814) 235-7832
www.crpr.org

STAHL SHEAFFER
ENGINEERING

301 SCIENCE PARK ROAD, SUITE 333
STATE COLLEGE, PA 16803

PH: 814-689-1562

FAX: 814-689-1885

Fernsler Hutchinson

ARCHITECTURE LLC

521 EAST BEAVER AVENUE STATE COLLEGE, PA 16801 t: 814-234-6806 f: 814-234-0256 e: fjfaia@aol.com





182 FAIRMOUNT DRIVE LEWISBURG, PA 17837 PH: 570-847-9519

brian@bsalandplan.com

SSE PROJECT No:

DRAWN BY: CHECKED BY:

REVISIONS

SYM DATE DESCRIPTION

SUBMISSIONS
DATE DESCRIPTION

06/07/19 TWP. SUBMISSION 1 10/02/19 TWP. SUBMISSION 2

WHITEHALL ROAD REGIONAL PARK PHASE 1

<PRELIMINARY
NOT FOR
CONSTRUCTION>

SHEET NAME

LANDSCAPING DETAILS

I 102

CANOPY TREE PLANTING DETAIL