

# 

# PRELIMINARY SUBDIVISION PLAN


# FERGUSON TOWNSHIP \* CENTRE COUNTY \* PENNSYLVANIA MAY 14, 2019


LAST REVISED: MARCH 25, 2020







SHEET	DESCRIPTION	
1	COVER PAGE	
2	EXISTING CONDITIONS PLAN	
3	RECORD PLAN	
4	SIGNATURE & NOTES PAGE	
5	GRADING PLAN	
6	GRADING PLAN - ENLARGEMENTS	
7	POST CONSTRUCTION STORMWATER MANAGEMENT PLAN	
8	UTILITY PLAN	
9	PROFILE - APPLE VIEW DRIVE	
10	GENERAL CONSTRUCTION DETAILS	
11	STORMWATER MANAGEMENT DETAILS	
12	EROSION & SEDIMENTATION CONTROL PLAN	
13	EROSION & SEDIMENTATION CONTROL NARRATIVE	
14	EROSION & SEDIMENTATION CONTROL DETAILS	
15	APPLE VIEW DRIVE SIGHT DISTANCE PLAN	





BEFORE YOU DIG ANYWHERE IN
PENNSYLVANIA! CALL 1-800-242-1776
NON-MEMBERS MUST BE CONTACTED DIRECTLY





Location Map	Key Map		Project Notes:	
SCALE: 1"=2000'	SCALE: 1"=1000'		General Site Information:     a. Owner Information:	Aspen Whitehall Partners LLC 116 Union Avenue
			b. Tax Parcel Number:	Altoona, PA 16602 (Pe
			c. Deed Information: d. Property Address:	Record Book, Page (Pe State College, PA 16801
			e. Municipality: f. Zoning:	Ferguson Township Single Family Residential Distr
Represented to the second seco		SITE	g. Existing Site Use: h. Proposed Site Use:	Corridor Overlay District Vacant Lot/Open Space Single Family Residential
SITE			i. Lot Size: j. Maximum Building Coverage:	16.568 AC (721,716 SF) 30% (216,515 SF)
			<ul> <li>k. Proposed Building Coverage:</li> <li>l. Maximum Impervious Coverage:</li> <li>m. Proposed Impervious Coverage:</li> </ul>	0.00% (0 SF) 50% (360,858 SF)
grande de la companya			Pavement/Concrete Area:  Residential Lots Impervious:	8.64% (62,378 SF) 24.94% (180,000 SF) (Assume
0 1000 2000		0 500 10	Total Impervious Coverage: n. Maximum Building Height:	33.58% (242,378 SF)
GRAPHIC SCALE 1 inch = 2000 ft.		GRAPHIC SCALE 1 inch = 1000 ft.	o. Proposed Building Height: p. Total Number of Lots:	0' (No Buildings Proposed) 37 (Includes 36 Residential Lo
Owner's Certification: TP#	Township Engineer Cerl	tification	2. Building Setbacks: a. Single Family Residential (R-1): Front: 25' (50' On Arterial Stree	its – West College Avenue & Whi
State of County of	I,, have certify that the plan meets all engineering design	e reviewed and hereby standards and	Side: 10' Rear: 30'	·
On this the day of, 20,	criteria of the Ferguson Township Code of Ordinar	nces.	b. Corridor Overlay District: West Co Front: 50' when abutting a Corri	•
personally appeared before me and certified that they were the owners of the properties shown on this plan and acknowledge the same to be their act and	Municipal Storm Water Ce	rtification	access road. See §27-210 Side: Same as underlying Zoning	0.1.C.(2)(a) District
plan and designs, the same to be recorded as such, according to the law.		20 ,	Rear: Rear yard setbacks as des c. A 50' Buffer Yard shall be provid	
	have reviewed the Stormwater Management Plan with the design standards and criteria of the Fe	in accordance	3. The purpose of this plan is to Subo	·
witness my hand and seal, this date	Stormwater Management Ordinance.			Number: 20183162948) erified prior to any construction. I stor shall notify pa one call prior
	<b>Township Planning Com</b> Ferguson Township Planning Commission Approved		a. Water:	State College Borough Water 1201 West Branch Road, State
			<ul><li>b. Sanitary Sewer:</li><li>c. Telephone:</li></ul>	University Area Joint Authority 1576 Spring Valley Road, Stat Verizon
	Chairman 	Date	d. Electric:	224 South Allen Street, State West Penn Power Company
Notary Public Commission Expires	Secretary	Date	e. Cable television:	2800 East College Avenue, St Comcast 60 Decibel Road, State Colleg
Owner's Certification: TP#	<b>Township Supervis</b> Ferguson Township Supervisors Approved	ors	f. Gas: g. Stormwater & Traffic Signals:	Columbia Gas of Pennsylvania 2550 Carolean Drive, State Co Ferguson Township
State of County of	Chairman	Date	5. Natural Site Features & Survey Info	3147 Research Drive, State Communication:
On this the day of, 20,	 Secretary	Date	<ul><li>a. Soil limits and descriptions have</li><li>b. There are not wetlands on the si</li></ul>	been taken from the Natural Res te according to the National Wetl
personally appeared before me and certified that they were the owners of the properties shown on this plan and acknowledge the same to be their act and	Fire Chief Certifica	tion	<ul> <li>c. There are no portions of this site</li> <li>d. Contours shown are taken from se. Horizontal Datum is Pennsylvania</li> </ul>	survey data collected in the field
plan and designs, the same to be recorded as such, according to the law.	I have reviewed and hereby certify that the location and Fire Hydrants shown on this plan are adequate		f. Elevation Datum is the North Amo g. The Project Benchmark is a 'X' o	erican Vertical Datum of 1988 (N cut bolt over the large opening o
			h. There are no sinkholes on site at 6. Easement Information:	ccording to the Preliminary Geolog
witness my hand and seal, this date	Fire Chief	 Date	a. There is a 10' Utility and Sidewal b. There is a 5' Sidewalk Easement	•
	Professional Land Survey	or Cortification	7. Street Lighting: Each lot shall be e	quipped with a "dusk 'til dawn" p
	Professional Land Surveyo	or in the Commonwealth	8. Any signage required by the Townsh	
	of Pennsylvania, do hereby certify that this pl the tracts of lands as shown.	idir correctly represents	<ul><li>9. Property monuments and pins shall</li><li>10. Apple View Drive shall have a 26'</li></ul>	·
Notary Public Commission Expires	 Signature	 Date	11. All pedestrian walkways , drainage recorded HOA documents. All sidewa	
Offer of Dedication	Storm Water Certific		not including the back of the curb)	shall be maintained by the Orcho
State of County of			<ol> <li>For additional information, refer to a. "Harner Farm Final Subdivision Plots." State College, PA (Whitehall Roa</li> </ol>	an", prepared by PennTerra Engin
On this the day of, 20,	I,, hereb that the Stormwater Management Plan meets all and criteria of the Ferguson Township Stormwater	design standards	c. "Traffic Impact Study For The Product A Stormwater Management Site F	oposed Harner Farm Redevelopme
certifies that all proposed streets, right of ways, and easements not heretofore dedicated shown on this plan, are hereby offered for public use.			13. As-Built drawings/documentation of prerequisite of the release of surety	
He acknowledges responsibility for maintenance of lands and/or facilities until they are complete and accepted for dedication by the Municipality.	Design Engineer Certif	ication	14. Street trees along Apple View Drivi	, ,
- Owner	l,, hereb land development meets all design requirements o	of the Subdivision and	installation of street trees within thi Ferguson Township Subdivision Ordino	
witness my hand and seal, this date	Land Development Ordinance, Zoning Ordinance an Chapters of Ferguson Township Code.	d all other applicable	15. A Sidewalk Easement Agreement h	
			<ul><li>16. No structure is required to have a</li><li>17. This Record Plan Conforms with th</li></ul>	,,
			manner and time so specified the	rein.
			18. A fee-in-lieu payment of \$112,014 Parkland fee-in-lieu = \$1,225.00 \$1,225.00 per person * 2.54 person	per person. Fee is based on 2.54 ons per dwelling unit = \$3,111.50
Notary Public Commission Expires			\$3,111.50 per dwelling unit * 36 d	ay be constructed on the land w
Storm Water Facilities Acknowledgement			accepts an additional fee-in-lieu  20. On May 29, 2019, a Variance was	'
I/We, the landowner(s), my/our heirs and assigns, acknowledge the Stormwater Management System to be a			On, a Mod along West College Avenue connec	ification Request was granted by ting the proposed Sheetz site an
permanent facility which can be altered or removed only after approval of a revised plan by the Ferguson Township Board of Supervisors. The stormwater management system is to be maintained in accordance with the approved			Parcel C will be installed as a par 21. A Highway Occupancy Permit is re	•
ownership and maintenance program.			22. The 50' Rural Agriculture District (	(RA) Buffer located in the rear o
Recorder of Deeds  Recorded in the Office of the Recorder of Deeds at Centre			than the placement of an accessor from being located within the fifty	,
County, Pennsylvania, in Plat Book,Page, on this theday of, 20			23. The corner lots 1, 19, 20, and 36	shall be permitted to gain access

Recorder

c. A 50' Buffer Yard shall be provided when adjoining land is in the Rural Agriculture District (RA). See §27-206.1.C

All utility locations should be verified prior to any construction. utility information and locations should be

State College Borough Water Authority

d. Contours shown are taken from survey data collected in the field by PennTerra Engineering, Inc.

a. There is a 10' Utility and Sidewalk Easement located along the street frontage of all lots. b. There is a 5' Sidewalk Easement located along the West College Avenue side of Lots 19 & 20.

8. Any signage required by the Township shall be acquired and erected at the expense of the developer.

not including the back of the curb) shall be maintained by the Orchard View Homeowners Association.

a. "Harner Farm Final Subdivision Plan", prepared by PennTerra Engineering, Inc., dated April 19, 2019. b. "State College, PA (Whitehall Road) Sheetz", prepared by PennTerra Engineering, Inc., dated April 19, 2019.

Parkland fee—in—lieu = \$1,225.00 per person. Fee is based on 2.54 persons per dwelling unit

\$1,225.00 per person \* 2.54 persons per dwelling unit = \$3,111.50 per dwelling unit \$3,111.50 per dwelling unit \* 36 dwelling units = \$112,014.00 fee—in—lieu payment

from being located within the fifty-foot buffer yard. See §27-206.1.1.(2)

Documents. See details on Sheet 11.

9. Property monuments and pins shall be set after lot development and landscaping is completed.

f. Elevation Datum is the North American Vertical Datum of 1988 (NAVD 88).

1201 West Branch Road, State College, PA 16801; (814) 238-6766

1576 Spring Valley Road, State College, PA 16801; (814) 238-9662

224 South Allen Street, State College, PA 16801; (814) 231-6511

60 Decibel Road, State College, PA 16801; (800) 992-3515

2550 Carolean Drive, State College, PA 16801; (814) 238-6775

3147 Research Drive, State College, PA 16801; (814) 238-4651

b. There are not wetlands on the site according to the National Wetland Inventory Mapping (U.S. Fish & Wildlife Service) for State College, PA last updated March 2019.

c. There are no portions of this site within Flood Plain according to the Federal Emergency Management Agency (FEMA) Map Number 42027C0619F, effective date May 4, 2009.

11. All pedestrian walkways , drainage easements, detention basins, and all drainage structures located outside of the street R—0—W shall be maintained by the Orchard View Homeowners Association in accordance with the

13. As—Built drawings/documentation of the stormwater management facilities must be prepared in accordance with Chapter 26 \$26—402D.4 and submitted to Ferguson Township at the completion of construction as a

14. Street trees along Apple View Drive shall be as follows: (Min. Spacing: 41', Max. Spacing: 50', Min. Caliper: 2") (Refer to Plan Sheet 3). Due to potential conflicts with driveway entrances and construction equipment, the installation of street trees within this subdivision shall be done all at the same time after all sidewalks are completed in this phase. Street tree planting shall be in compliance with Chapter 25 (Shade Trees) of the

17. This Record Plan Conforms with the plan receiving final approval by the Ferguson Township Board of Supervisors on \_\_\_\_\_\_\_\_. All improvements are or will be installed in accordance with such plan in a

19. No more than 36 dwelling units may be constructed on the land which is the subject of this Subdivision Plan unless additional land is dedicated to the Township of Ferguson for parkland and/or the Board of Supervisors

along West College Avenue connecting the proposed Sheetz site and the Orchard View Subdivision will be constructed at the time of development on Parcel B. Sidewalks along Lots 1, 19, 20, and 36, as well as in front of

22. The 50' Rural Agriculture District (RA) Buffer located in the rear of Lots 14—19 shall be subject to the following. No structure, including decks, patios or building additions may encroach in this fify—foot buffer yard other than the placement of an accessory structure/shed of less than 144 square feet, which is permitted to be located within the buffer and as close as three feet from the property line. Swimming pools shall be prohibited

24. The 20' Stormwater Access Easement between Lots 11 & 12 shall be subject to the following; No structures, landscaping & above ground obstructions shall be located within the Easement Area except for the Easement delineation items proposed and shown on the Basin Easement Delineation Details on Sheet 11. The 20' Easement area is to be kept open for access and shall be maintained in accordance with the recorded HOA

\_\_\_\_, a Modification Request was granted by the Ferquson Township Board of Supervisors to defer the construction of required sidewalks to the time of individual lot development. The sidewalk along

18. A fee—in—lieu payment of \$112,014.00 will be provided by the developer to meet the parkland requirement. The calculations for this payment are as follows based on the Ferguson Township 2019 Fee Schedule:

20. On May 29, 2019, a Variance was granted by the Ferguson Township Zoning Hearing Board to defer the construction of required sidewalks on the undeveloped lots to the time of individual lot development.

21. A Highway Occupancy Permit is required persuant to Section 420 of the Act of June 1, 1945 (P.L. 1242, No. 428), known as the "State Highway Law", before driveway access to a State Highway is permitted.

recorded HOA documents. All sidewalks adjacent to residential lots shall be maintained in accordance with the recorded HOA documents. The interior of the two entrance median islands on Apple View Drive (inward from, but

a. Soil limits and descriptions have been taken from the Natural Resources Conservation Service Web Soil Survey dated March 2019.

e. Horizontal Datum is Pennsylvania North Zone State Plane Coordinates, North American Datum of 1983 (PA NAD83) U.S. Feet.

g. The Project Benchmark is a 'X' cut bolt over the large opening on a fire hydrant along Whitehall Road. Elevation = 1240.56'.

h. There are no sinkholes on site according to the Preliminary Geologic Investigation prepared by CMT Laboratories, Inc, dated dated May 1, 2019.

Street Lighting: Each lot shall be equipped with a "dusk 'til dawn" photocell controlled lamp on a post placed on the front lawn within 15' of the driveway.

10. Apple View Drive shall have a 26' wide paved cartway bordered by extruded plain cement concrete curb and centered within a dedicated 50' R-0-W.

c. "Traffic Impact Study For The Proposed Harner Farm Redevelopment", prepared by David E. Wooster and Associates, Inc., dated April 2019.

d. A Stormwater Management Site Plan/PCSM Plan and Soil Erosion & Sedimentation Control Plan have been prepared for Orchard View, dated May 10, 2019.

15. A Sidewalk Easement Agreement has been recorded in Record Book \_\_\_\_\_\_ Page \_\_\_\_\_ for the concrete sidewalk along the street frontage of all single family lots.

23. The corner lots 1, 19, 20, and 36 shall be permitted to gain access from Appleview Drive only, and at a distance of at least 55 feet from the edge of the through street.

2800 East College Avenue, State College, PA 16801; (814) 237-5821

considered approximate. contractor shall notify pa one call prior to any excavation.

Front: 25' (50' On Arterial Streets - West College Avenue & Whitehall Road)

Single Family Residential District (R-1)

24.94% (180,000 SF) (Assumed 5,000 SF per lot)

37 (Includes 36 Residential Lots and 1 Stormwater Management Lot)

Aspen Route 26 Partners, LLC

(Pending approval of "Harner Farm Final Subdivision Plan")

(Pending approval of "Harner Farm Final Subdivision Plan")

Corridor Street front yard setbacks may be reduced by not more than 10 feet at its corner lots; to become a forty-foot setback, when the only access to the site is provided from a collector or subcollector

\_\_\_ into 36 Single Family Residential lots, 1 Stormwater Management Lot, construct a public street, and install all associated utilities.

Rear: Rear yard setbacks as designated in the underlying Zoning District may be reduced up to 10 feet when the designated rear yard does not abut a corridor street. See \$27—210.1.C.(2)(d)

116 Union Avenue

Record Book \_\_\_\_\_, Page (Pending approval of "Harner Farm Final Subdivision Plan"

Altoona, PA 16602

#### Stormwater BMPs Long Term Ownership, Operation and Maintenance Program

All stormwater management BMPs on this site not contained in a Ferguson Township Right-of-Way shall be owned and maintained by the Home Owners Associations their executors, heirs and assigns. The owners agree to provide perpetual maintenance, access to and ownership of the BMPs. Ferguson Township, its agents and assigns shall have the uninterrupted right to access the property for inspection and maintenance of the stormwater BMPs. This note applies to the entire property shown on these plans and shall be in effect for perpetuity. The responsibility for long—term operation and maintenance of the BMPs is a covenant that runs with the land and binding upon and enforceable by subsequent grantees.

Ferguson Township and/or the Centre County Conservation District requires the Owners to maintain a record of all inspections, repairs, and maintenance activities associated with the proposed stormwater management and permanent erosion and sediment pollution control facilities at this project site. The Owners shall immediately notify Ferguson Township and Centre County Conservation District prior to initiating any major repair

The Owners hereby acknowledges Ferguson Township's right to periodically access the project site to inspect the permanent stormwater management facilities that are part of this project. The Owners acknowledges Ferguson Township's right to access the project site with notice to repair and/or maintain the permanent stormwater management facilities in accordance with this Maintenance Program. Any maintenance and/or repair activities conducted by Ferguson Township shall be at the expense of the Owners.

The facilities that will require maintenance are inlets, storm sewer pipes, rip—rap aprons, swales and detention/infiltration basins. All stormwater facilities should be inspected monthly or after any rainfall producing runoff and maintained as follows:

MAINTENANCE ITEM	MAINTENANCE DUTY	OCCURRENCE INTERVAL
STORM SEWER INLETS AND PIPES	STORM SEWER INLETS AND PIPES SHALL BE CLEANED OF ALL DEBRIS, LITER, AND OTHER DELETERIOUS MATERIAL.	MONTHLY OR AFTER EACH RAINFAL EVENT PRODUCING 1" OR MORE O RAINFALL
RIP RAP APRONS	THE RIP-RAP APRONS AT THE OUTLETS OF THE PIPES NEED TO BE INSPECTED TO ENSURE PROPER EROSION PROTECTION. IF EROSION OCCURS, ADDITIONAL RIP-RAP SHOULD BE ADDED.	MONTHLY OR AFTER EACH RAINFA EVENT PRODUCING 1" OR MORE C RAINFALL
DETENTION BASINS -GENERAL	THE STORMWATER DETENTION BASINS SHALL BE CLEANED OF DEBRIS AND IF ANY EROSION IS PRESENT THE AREA IS TO BE BACKFILLED WITH TOPSOIL AND SEEDED WITH A PERMANENT MIXTURE. THE OUTLET STRUCTURES SHALL BE KEPT CLEAN OF TRASH AND DEBRIS.	MONTHLY OR AFTER EACH RAINFA EVENT PRODUCING 1" OR MORE C RAINFALL
DETENTION BASINS - VEGETATION -FIRST GROWING SEASON	ONE END OF SEASON MOWING SHALL BE DONE IN LATE FALL/WINTER. USE A WALK BEHIND BRUSH HOG MOWER OR STRING TRIMMER TO TRIM THE MEADOW TO A HEIGHT OF 8" (NOTE: A LAWN MOWER IS NOT RECOMMENDED AS THE MOWER HEIGHT WILL BE TOO LOW AND NATIVE SEEDLINGS WILL BE KILLED). MOWING SHOULD CEASE BY MID-SEPTEMBER.PROBELM WEEDS SHOULD BE HAND PULLED OR SPOT SPRAYED WITH AN APPROVED HERBICDE (SUCH AS RODEO). ALL CLIPPINGS IN EXCESS OF TWO INCHES IN LENGTH SHALL BE REMOVED FROM THE BASIN.	AS REQUIRED WITHIN FIRST GROW SEASON
DETENTION BASINS- VEGETATION SECOND GROWING SEASON AND BEYOND	TRIM STANDING PLANTS CLOSE TO THE GROUND (APPROXIMATELY 2").IT WILL REDUCE THE LIKELIHOOD OF THE MEADOW BEING INVADED BY SHRUBS.PROBELM WEEDS SHOULD BE HAND PULLED OR SPOT SPRAYED WITH AN APPROVED HERBICDE (SUCH AS RODEO). ALL CLIPPINGS IN EXCESS OF TWO INCHES IN LENGTH SHALL BE REMOVED FROM THE BASIN.	ANNUALLY IN FALL
INFILTRATION BASINS -GENERAL	THE STORMWATER INFILTRATION BASINS SHALL BE CLEANED OF DEBRIS AND IF ANY EROSION IS PRESENT THE AREA IS TO BE BACKFILLED WITH TOPSOIL AND SEEDED WITH A PERMANENT MIXTURE. THE OUTLET STRUCTURES SHALL BE KEPT CLEAN OF TRASH AND DEBRIS. VEHICULAR TRAFFIC IN INFILTRATION BASINS SHALL BE LIMITED TO THE MAXIMUM EXTENT POSSIBLE. NO VEHICULAR TRAFFIC SHOULD OPERATE WITHIN THE BASIN BOTTOMS WHEN THE SOILS ARE SATURATED	MONTHLY OR AFTER EACH RAINFA EVENT PRODUCING 1" OR MORE O RAINFALL
INFILTRATION BASINS - VEGETATION -FIRST GROWING SEASON	ONE END OF SEASON MOWING SHALL BE DONE IN LATE FALL/WINTER. USE A WALK BEHIND BRUSH HOG MOWER OR STRING TRIMMER TO TRIM THE MEADOW TO A HEIGHT OF 8" (NOTE: A LAWN MOWER IS NOT RECOMMENDED AS THE MOWER HEIGHT WILL BE TOO LOW AND NATIVE SEEDLINGS WILL BE KILLED). MOWING SHOULD CEASE BY MID-SEPTEMBER.PROBELM WEEDS SHOULD BE HAND PULLED OR SPOT SPRAYED WITH AN APPROVED HERBICDE (SUCH AS RODEO). ALL CLIPPINGS IN EXCESS OF TWO INCHES IN LENGTH SHALL BE REMOVED FROM THE BASIN. VEHICULAR TRAFFIC IN INFILTRATION BASINS SHALL BE LIMITED TO THE MAXIMUM EXTENT POSSIBLE. NO VEHICULAR TRAFFIC SHOULD OPERATE WITHIN THE BASIN BOTTOMS WHEN THE SOILS ARE SATURATED	AS REQUIRED WITHIN FIRST GROW SEASON
INFILTRATION BASINS- VEGETATION SECOND GROWING SEASON AND BEYOND	TRIM STANDING PLANTS CLOSE TO THE GROUND (APPROXIMATELY 2").IT WILL REDUCE THE LIKELIHOOD OF THE MEADOW BEING INVADED BY SHRUBS.PROBELM WEEDS SHOULD BE HAND PULLED OR SPOT SPRAYED WITH AN APPROVED HERBICDE (SUCH AS RODEO). ALL CLIPPINGS IN EXCESS OF TWO INCHES IN LENGTH SHALL BE REMOVED FROM THE BASIN. VEHICULAR TRAFFIC IN INFILTRATION BASINS SHALL BE LIMITED TO THE MAXIMUM EXTENT POSSIBLE. NO VEHICULAR TRAFFIC SHOULD OPERATE WITHIN THE BASIN BOTTOMS WHEN THE SOILS ARE SATURATED	ANNUALLY IN FALL

\*DOCUMENTATION OF INSPECTIONS MUST BE MAINTAINED BY THE OWNER AND SUBMITTED TO TOWNSHIP UPON REQUEST. MAINTENANCE INSPECTIONS MAY BE PERFORMED BY THE TOWNSHIP TO ENSURE PROPER FUNCTIONING OF ALL STORMWATER FACILITIES.

25. A Conditional Use for the Lot 37 flag lot layout was approved by the Ferguson Township Board of Supervisors on 26. The Existing 20' Utility Easement for water service to Harner Farm Subdivision Lot 1 at the Orchard View Lots 31 & 32 property line shall be eliminated and any installed water service abandoned or removed to the SCBWA's requirements upon the recording of the "State College, PA (Whitehall Road) Sheetz" Land Development Plan for which surety for a new water service off of West College Avenue will be

STORMWATER BMP

Right-Of-Way shown on these plans.

posted for that Lot. 27. Upon the Dedication of the Apple View Drive Right-Of-Way, the existing Temporary Sanitary Sewer, Stormwater Management, and Water Easement shown in the same area on the Harner Farm Final Subdivision Plan will be eliminated and replaced with the Public

LOT NUMBER	STREET ADDRESS
1	106 APPLE VIEW DRIVE
2	110 APPLE VIEW DRIVE
3	114 APPLE VIEW DRIVE
4	118 APPLE VIEW DRIVE
5	122 APPLE VIEW DRIVE
6	126 APPLE VIEW DRIVE
7	130 APPLE VIEW DRIVE
8	134 APPLE VIEW DRIVE
9	138 APPLE VIEW DRIVE
10	142 APPLE VIEW DRIVE
11	146 APPLE VIEW DRIVE
12	150 APPLE VIEW DRIVE
13	154 APPLE VIEW DRIVE
14	158 APPLE VIEW DRIVE
15	162 APPLE VIEW DRIVE
16	166 APPLE VIEW DRIVE
17	170 APPLE VIEW DRIVE
18	174 APPLE VIEW DRIVE
19	178 APPLE VIEW DRIVE
20	179 APPLE VIEW DRIVE
21	173 APPLE VIEW DRIVE
22	171 APPLE VIEW DRIVE
23	169 APPLE VIEW DRIVE
24	159 APPLE VIEW DRIVE
25	153 APPLE VIEW DRIVE
26	145 APPLE VIEW DRIVE
27	141 APPLE VIEW DRIVE
28	137 APPLE VIEW DRIVE
29	135 APPLE VIEW DRIVE
30	131 APPLE VIEW DRIVE
31	129 APPLE VIEW DRIVE
32	125 APPLE VIEW DRIVE
33	119 APPLE VIEW DRIVE
34	115 APPLE VIEW DRIVE
35	111 APPLE VIEW DRIVE
36	107 APPLE VIEW DRIVE

STREET ADDRESS TABLE

**PennTerra ENGINEERING INC** 

CENTRAL PENNSYLVANIA **REGION OFFICE:** 3075 ENTERPRISE DRIVE

SUITE 100 STATE COLLEGE, PA 1680° PH: 814-231-8285 Fax: 814-237-2308


**LANCASTER** REGION OFFICE: 3904 B ABEL DRIVE COLUMBIA, PA 17512

PH: 717-522-5031

Fax: 717-522-5046 WWW.PENNTERRA.COM

COPYRIGHT 2020 BY THE ENGINEE! THE INFORMATION CONTAINED HEREON MAY NO BE USED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF THE ENGINEER EXCEPT AS OTHERWISE PROVIDED BY APPROPRIA

© PENNTERRA ENGINEERING 2020 ALL RIGHTS RESERVED



ONWEAL

roi.Manaaer Perimeter Ck. Acad 17125-RESIDENTIAL-SUB-SIG 03/25/20 REVISED PER FERGUSON TOWNSHIP COMMENTS 01/31/20 REVISED PER FERGUSON TOWNSHIP

Draftsman

10/03/19 REVISED PER FERGUSON TOWNSHIP COMMENTS 08/07/19 REVISED PER FERGUSON TOWNSHIP COMMENTS Description REVISIONS


ORCHARD VIEW

FERGUSON TOWNSHIP CENTRE COUNTY PENNSYLVANIA

PRELIMINARY SUBDIVISION PLAN

SIGNATURE & NOTES PAGE

MAY 14, 2019



#### GRADING NOTES

- 1. ALL SITE WORK SHALL BE DONE IN ACCORDANCE WITH THE PLANS PREPARED BY PENNTERRA, THE CURRENT REQUIREMENTS OF THE FERGUSON TOWNSHIP, THE APPLICABLE SECTIONS OF THE PENNDOT STANDARD SPECIFICATIONS FOR ROADWAY CONSTRUCTION, AND ALL OTHER PERTINENT FEDERAL AND STATE LAWS.
- 2. THE CONTRACTOR SHALL COMPLY AT ALL TIMES WITH APPLICABLE FEDERAL, STATE AND LOCAL LAWS, PROVISIONS, AND POLICIES GOVERNING SAFETY AND HEALTH, INCLUDING THE FEDERAL CONSTRUCTION SAFETY ACT (PUBLIC LAW 91–54), FEDERAL REGISTER, CHAPTER XVII, PART 1926 OF TITLE 29 REGULATIONS, OCCUPATIONAL SAFETY AND HEALTH REGULATIONS FOR
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR EXAMINING THE AREAS AND CONDITIONS UNDER WHICH THE PROJECT IS TO BE CONSTRUCTED PRIOR TO THE SUBMISSION OF A BID. SUBMISSION OF A BID SHALL BE CONSTRUED TO MEAN THE CONTRACTOR HAS REVIEWED THE SITE AND IS FAMILIAR WITH CONDITIONS AND CONSTRAINTS OF THE SITE.

CONSTRUCTION, AND SUBSEQUENT PUBLICATIONS UPDATING THESE REGULATIONS.


- 4. BEFORE EXCAVATION, ALL UNDERGROUND UTILITIES SHALL BE LOCATED IN THE FIELD BY THE PROPER AUTHORITIES. THE CONTRACTOR SHALL NOTIFY PA ONE CALL 1-800-242-1776. THE LOCATION OF ALL UTILITIES AND UNDERGROUND STRUCTURES ARE APPROXIMATE AND MAY NOT ALL BE SHOWN. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE THE EXISTENCE AND EXACT LOCATION OF ALL UTILITIES AND UNDERGROUND STRUCTURES.
- 5. MAXIMUM SLOPES SHALL BE 3:1 (HORIZONTAL: VERTICAL) EXCEPT WHERE SPECIFICALLY NOTED.

ALL AREAS NOT PAVED SHALL BE TOPSOILED, SEEDED, MULCHED OR LANDSCAPED UNLESS


- OTHERWISE NOTED IN THE CONSTRUCTION DRAWINGS, SITE SPECIFICATIONS OR INSTRUCTED BY THE OWNER.
- 7. THE MAXIMUM SLOPE FOR ALL ON-SITE SIDEWALKS SHALL BE 4.90% WITH A MAXIMUM CROSS SLOPE OF 2.00% AND CURB RAMPS SHALL HAVE A MAXIMUM SLOPE OF 8.30%.
- 8. CONTOURS SHOWN ARE GENERATED FROM A FIELD SURVEY BY PENNTERRA ENGINEERING, INC. AND ARE BASED ON AN ASSUMED ELEVATION. THE PROJECT BENCHMARK IS A 'X' CUT BOLT OVER THE LARGE OPENING ON A FIRE HYDRANT ALONG WHITEHALL ROAD. ELEVATION = 1240.56'.

#### SURVEY FEATURES LEGEND

#### EXISTING FEATURES LEGEND




#### PROPOSED FEATURES LEGEND




PROPOSED DEPRESSED CURB W/ CURB TRANSITION

Existing Evergreen Tree




INTERSECTION ENLARGEMENT
WHITEHALL ROAD & PROPOSED ROAD
SCALE: 1"=10'




SIDEWALK CONNECTION TO WHITEHALL ROAD

SCALE: 1"=10'



INTERSECTION ENLARGEMENT
WEST COLLEGE AVENUE & PROPOSED ROAD
SCALE: 1"=10'





CENTRAL PENNSYLVANIA REGION OFFICE: 3075 ENTERPRISE DRIVE

SUITE 100 STATE COLLEGE, PA 16801 PH: 814-231-8285 Fax: 814-237-2308


LANCASTER REGION OFFICE: 3904 B ABEL DRIVE COLUMBIA, PA 17512

Fax: 717–522–5046 **WWW.PENNTERRA.COM** 

PH: 717-522-5031

COPYRIGHT 2020 BY THE ENGINEER
THE INFORMATION CONTAINED HEREON MAY NOT
BE USED OR COPIED IN ANY MANNER WITHOUT
THE WRITTEN PERMISSION OF THE ENGINEER
EXCEPT AS OTHERWISE PROVIDED BY APPROPRIATE

© PENNTERRA ENGINEERING 2020 ALL RIGHTS RESERVED



Designer EAH

Draftsman EAH

Proj.Manager MAT/JCS

Surveyor MAK/JDF

Perimeter Ck.

Book 543 Pg 1

Acad 17125—RESIDENTIAL—SUB—GP2

03/25/20 REVISED PER FERGUSON TOWNSHIP COMMENTS
01/31/20 REVISED PER FERGUSON TOWNSHIP COMMENTS
10/03/19 REVISED PER FERGUSON TOWNSHIP COMMENTS
08/07/19 REVISED PER FERGUSON TOWNSHIP COMMENTS

Date Description

REVISIONS

ORCHARD VIEW

FERGUSON TOWNSHIP CENTRE COUNTY PENNSYLVANIA

PRELIMINARY SUBDIVISION PLAN

GRADING PLAN -ENLARGEMENTS


PROJECT NO. **17125** DATE

MAY 14, 2019

1"=10'

1 inch = 10 ft.





**ENGINEERING INC** 

CENTRAL PENNSYLVANIA REGION OFFICE: 3075 ENTERPRISE DRIVE

SUITE 100 STATE COLLEGE, PA 1680 PH: 814-231-8285 Fax: 814-237-2308

**LANCASTER REGION OFFICE:** 3904 B ABEL DRIVE COLUMBIA, PA 17512

PH: 717-522-5031 Fax: 717-522-5046

**WWW.PENNTERRA.COM** COPYRIGHT 2020 BY THE ENGINEE! THE INFORMATION CONTAINED HEREON MAY NO BE USED OR COPIED IN ANY MANNER WITHOUT

© PENNTERRA ENGINEERING 2020 ALL RIGHTS RESERVED



Draftsman Proj.Manager Perimeter Ck. Acal 7125-RESIDENTIAL-SUB-PCSM

03/25/20 REVISED PER FERGUSON TOWNSHIP COMMENTS 01/31/20 REVISED PER FERGUSON TOWNSHIP COMMENTS 10/03/19 REVISED PER FERGUSON TOWNSHIP COMMENTS 08/07/19 REVISED PER FERGUSON TOWNSHIP COMMENTS

ORCHARD VIEW

FERGUSON TOWNSHIP CENTRE COUNTY PENNSYLVANIA


PRELIMINARY SUBDIVISION PLAN


CONSTRUCTION STORMWATER MANAGEMENT PLAN


PROJECT NO. 17125

MAY 14, 2019

1"=60'







CENTRAL PENNSYLVANIA REGION OFFICE: 3075 ENTERPRISE DRIVE

SUITE 100 STATE COLLEGE, PA 16801 PH: 814-231-8285 Fax: 814-237-2308


LANCASTER **REGION OFFICE:** 3904 B ABEL DRIVE COLUMBIA, PA 17512 PH: 717-522-5031

Fax: 717-522-5046

WWW.PENNTERRA.COM

COPYRIGHT 2020 BY THE ENGINEER THE INFORMATION CONTAINED HEREON MAY NOT BE USED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF THE ENGINEER EXCEPT AS OTHERWISE PROVIDED BY APPROPRIAT LAWS OR STATUTES.

© PENNTERRA ENGINEERING 2020 ALL RIGHTS RESERVED



Draftsman Proj.Manager Surveyor Perimeter Ck. Acad 17125-RESIDENTIAL-SUB-PF

03/25/20 REVISED PER FERGUSON TOWNSHIP COMMENTS 01/31/20 REVISED PER FERGUSON TOWNSHIP COMMENTS 10/03/19 REVISED PER FERGUSON TOWNSHIP COMMENTS 08/07/19 REVISED PER FERGUSON TOWNSHIP COMMENTS Description revisions

ORCHARD VIEW

FERGUSON TOWNSHIP CENTRE COUNTY PENNSYLVANIA

PRELIMINARY SUBDIVISION PLAN


PROFILE -APPLE VIEW DRIVE


> PROJECT NO. 17125

MAY 14, 2019

( IN FEET ) 1 inch = 60 ft.

HZ: 1"=60'






Any Type 'M' Inlet exceeding 4' in depth is required to have steps installed.

### TYPE 'M' PRECAST CONCRETE INLET


NOT TO SCALE



NOTE: ALL HDPEP PIPE SHALL HAVE A SMOOTH LINED INTERIOR WALL TRENCHING, BEDDING AND BACKFILLING REQUIREMENTS AND MATERIALS SHALL CONFORM TO PENNDOT PUBLICATION 408 SPECIFICATIONS

### STORMSEWER (HDPEP) INSTALLATION

NOT TO SCALE



#### REPAIR STEPS

UPON DISCOVERY OF A SINKHOLE, THE FOLLOWING STEPS SHALL IMMEDIATELY OCCUR:


1. INSTALL SILT SOCK OR SOME OTHER PERIMETER EROSION AND SEDIMENT CONTROL BMP AROUND THE SINKHOLE PERIMETER, AS SHOWN ABOVE UNDER THE SUGGESTED FIRST COURSE OF REPAIR ACTION.


2. INSTALL CONSTRUCTION FENCE AROUND THE SINKHOLE PERIMETER, AS SHOWN ABOVE UNDER THE SUGGESTED FIRST COURSE OF REPAIR ACTION.

3. CONTACT THE PROJECT GEOTECHNICAL AND CIVIL CONSULTING ENGINEERS TO ARRANGE A FIELD VIEWING OF THE SINKHOLE AND DETERMINE THE FINAL COURSE OF ACTION TO REPAIR THE SINKHOLE.

4. IMPLEMENT THE FINAL COURSE OF ACTION TO REPAIR THE SINKHOLE UNDER THE DIRECTION AND SUPERVISION OF THE GEOTECHNICAL ENGINEER. REFER TO THE INVERTED FILTER FOR A TYPCIAL REPAIR. THE FINAL REPAIR APPROACH SHALL BE DETERMINED BY THE GEOTECHNICAL ENGINEER.


# SINKHOLE REPAIR—COURSE OF ACTION PLAN (NOT INCLUDED IN UTILITY/EARTHWORK BASE BID) NOT TO SCALE





TYPICAL REAR LOT SWALE DETAIL

NOT TO SCALE



## BASIN ACCESS EASEMENT DELINEATION DETAIL

Mid Rail (A): 2" x 3-1/2" x 94-1/2" Routed to accept pickets

Post centers

5 x 5 POST = 96"

Picket Spacing (B): 30 spaces of 1 9/16"

Pickets(with caps attached) (C): 29 pieces of 1-1/2" x 1-1/2" x 32-1/2" with cap, Drilled to accept fasteners

Bottom Rail (D): 2" x 6" x 94-1/2" Routed to accept pickets,

Steel reinforcement: Yes, channel located in bottom rail

Aluminum reinforcement: none

Post (in-ground) (E): 5" x 5" x 72"

Picket Caps (F): 1-1/2" x 1-1/2" x 3/4" pointed picket cap

Post Spacing (center to center): 96"

Color(s): White

## BASIN ACCESS EASEMENT FENCE DETAIL

BUFFTECH MANCHESTER 3' HIGH WHITE PICKET FENCE NOT TO SCALE





ENGINEERING INC
CENTRAL PENNSYLVANIA
REGION OFFICE:
3075 ENTERPRISE DRIVE

SUITE 100 STATE COLLEGE, PA 16801 PH: 814-231-8285 Fax: 814-237-2308

**LANCASTER REGION OFFICE:**3904 B ABEL DRIVE
COLUMBIA, PA 17512


PH: 717-522-5031 Fax: 717-522-5046

COPYRIGHT 2020 BY THE ENGINEER
THE INFORMATION CONTAINED HEREON MAY NOT
BE USED OR COPIED IN ANY MANNER WITHOUT
THE WRITTEN PERMISSION OF THE ENGINEER

EXCEPT AS OTHERWISE PROVIDED BY APPROPRIAT

© PENNTERRA ENGINEERING 2020 ALL RIGHTS RESERVED

LAWS OR STATUTES.



Designer \_\_\_\_\_\_EAH

Draftsman \_\_\_\_\_EAH

Proj.Manager \_\_\_\_\_MAT/JCS

Surveyor \_\_\_\_\_MAK/JDF

Perimeter Ck. \_\_\_\_\_

Book \_\_\_\_\_543 Pg \_\_\_\_\_1

Acab7125-RESIDENTIAL-SUB-SWDT

Lavout SWDT

03/25/20 REVISED PER FERGUSON TOWNSHIP
COMMENTS

01/31/20 REVISED PER FERGUSON TOWNSHIP
COMMENTS

10/03/19 REVISED PER FERGUSON TOWNSHIP
EAH COMMENTS

08/07/19 REVISED PER FERGUSON TOWNSHIP
EAH COMMENTS

Date Description

REVISIONS

ORCHARD VIEW

FERGUSON TOWNSHIP CENTRE COUNTY PENNSYLVANIA

PRELIMINARY SUBDIVISION PLAN

STORMWATER MANAGEMENT DETAILS

PROJECT NO.


17125

DATE

MAY 14, 2019

N.T.S.

11



ENGINEERING INC

**CENTRAL PENNSYLVANIA** 

WWW.PENNTERRA.COM

COPYRIGHT 2020 BY THE ENGINEE THE INFORMATION CONTAINED HEREON MAY NO BE USED OR COPIED IN ANY MANNER WITHOUT EXCEPT AS OTHERWISE PROVIDED BY APPROPRIA



171205-RESIDENTIAL-SUB-ES-PLAN

#### Standard Erosion and Sediment Control Plan Notes

- 1. All earth disturbances, including clearing and grubbing as well as cuts and fills shall be done in accordance with the approved E&S plan. A copy of the approved drawings (stamped, signed and dated by the reviewing agency) must be available at the project site at all times. The reviewing agency shall be notified of any changes to the approved plan prior to implementation of those changes. The reviewing agency may require a written submittal of those changes for review and
- 2. At least 7 days prior to starting any earth disturbance activities, including clearing and grubbing, the owner and/or operator shall invite all contractors, the landowner, appropriate municipal officials, the E&S plan preparer, the PCSM plan preparer, the licensed professional responsible for oversight of critical stages of implementation of the PCSM plan, and a representative from the Centre County Conservation District to an on-site preconstruction meeting.
- 3. At least 3 days prior to starting any earth disturbance activities, or expanding into an area previously unmarked, the Pennsylvania One Call System Inc. shall be notified at 1-800-242-1776 for the location of existing underground utilities.
- 4. All earth disturbance activities shall proceed in accordance with the sequence provided on the plan drawings. Deviation from that sequence must be approved in writing from the local conservation district or by the Department prior to implementation.
- 5. Areas to be filled are to be cleared, grubbed, and stripped of topsoil to remove trees, vegetation, roots and other objectionable material.
- 6. Clearing, grubbing, and topsoil stripping shall be limited to those areas described in each stage of the construction sequence. General site clearing, grubbing and
- topsoil stripping may not commence in any stage or phase of the project until the E&S BMPs specified by the BMP sequence for that stage or phase have been installed and are functioning as described in this E&S plan.
- 7. At no time shall construction vehicles be allowed to enter areas outside the limit of disturbance boundaries shown on the plan maps. These areas must be clearly marked and fenced off before clearing and grubbing operations begin.
- 8. Topsoil required for the establishment of vegetation shall be stockpiled at the location(s) shown on the plan maps(s) in the amount necessary to complete the finish grading of all exposed areas that are to be stabilized by vegetation. Each stockpile shall be protected in the manner shown on the plan drawings. Stockpile heights shall not exceed 35 feet. Stockpile slopes shall be 2H:1V or flatter.
- 9. Immediately upon discovering unforeseen circumstances posing the potential for accelerated erosion and/or sediment pollution, the operator shall implement appropriate best management practices to minimize the potential for erosion and sediment pollution and notify the local conservation district and/or the regional
- 10. All building materials and wastes shall be removed from the site and recycled or disposed of in accordance with the Department's Solid Waste Management Regulations at 25 Pa. Code 260.1 et seq., 271.1, and 287.1 et. seq. No building materials or wastes or unused building materials shall be burned, buried, dumped,
- 11. All off-site waste and borrow areas must have an E&S plan approved by the local conservation district or the Department fully implemented prior to being
- 12. The contractor is responsible for ensuring that any material brought on site is clean fill. Form FP-001 must be retained by the property owner for any fill material affected by a spill or release of a regulated substance buy qualifying as clean fill due to analytical testing.
- 13. Until the site is stabilized, all erosion and sediment BMPs shall be maintained properly. Maintenance shall include inspections of all erosion and sediment BMPs after each runoff event and on a weekly basis. All preventative and remedial maintenance work, including clean out, repair, replacement, regrading, reseeding, remulching and renetting must be performed immediately. If the E&S BMPs fail to perform as expected, replacement BMPs, or modifications of those installed will
- 14. A log showing dates that E&S BMPs were inspected as well as any deficiencies found and the date they were corrected shall be maintained on the site and be made available to regulatory agency officials at the time of inspection.
- 15. Sediment tracked onto any public roadway or sidewalk shall be returned to the construction site by the end of each work day and disposed in the manner described in this plan. In no case shall the sediment be washed, shoveled, or swept into any roadside ditch, storm sewer, or surface water.
- 16. All sediment removed from BMPs shall be disposed of in the manner described on the plan drawings.
- 17. Areas which are to be topsoiled shall be scarified to a minimum depth of 3 to 5 inches 6 to 12 inches on compacted soils prior to placement of topsoil. Areas to be vegetated shall have a minimum 4 inches of topsoil in place prior to seeding and mulching. Fill outslopes shall have a minimum of 2 inches of
- 18. All fills shall be compacted as required to reduce erosion, slippage, settlement, subsidence or other related problems. Fill intended to support buildings, structures and conduits, etc. shall be compacted in accordance with local requirements or codes.
- 19. All earthen fills shall be placed in compacted layers not to exceed 9 inches in thickness.
- 20. Fill materials shall be free of frozen particles, brush, roots, sod, or other foreign or objectionable materials that would interfere with or prevent construction of satisfactory fills.
- 21. Frozen materials or soft, mucky, or highly compressible materials shall not be incorporated into fills.
- 22. Fill shall not be placed on saturated or frozen surfaces.
- 23. Seeps or springs encountered during construction shall be handled in accordance with the standard and specification for subsurface drain or other approved
- 24. All graded areas shall be permanently stabilized immediately upon reaching finished grade. Cut slopes in competent bedrock and rock fills need not be vegetated. Seeded areas within 50 feet of a surface water, or as otherwise shown on the plan drawings, shall be blanketed according to the standards of this plan.
- 25. Immediately after earth disturbance activities cease in any area or subarea of the project, the operator shall stabilize all disturbed areas. During non-germinating months, mulch or protective blanketing shall be applied as described in the plan. Areas not at finished grade, which will be reactivated within 1 year, may be stabilized in accordance with the temporary stabilization specifications. Those areas which will not be reactivated within 1 year shall be stabilized in accordance with the permanent stabilization specifications.
- 26. Permanent stabilization is defined as a minimum uniform, perennial 70% vegetative cover or other permanent non-vegetative cover with a density sufficient to resist accelerated erosion. Cut and fill slopes shall be capable of resisting failure due to slumping, sliding, or other movements.
- 27. E&S BMPs shall remain functional as such until all areas tributary to them are permanently stabilized or until they are replaced by another BMP approved by the local conservation district or the Department.
- 28. Upon completion of all earth disturbance activities and permanent stabilization of all disturbed areas, the owner and/or operator shall contact the local conservation district for an inspection prior to removal/conversion of the E&S BMPs.
- 29. After final site stabilization has been achieved, temporary erosion and sediment BMPs must be removed or converted to permanent post construction stormwater management BMPs. Areas disturbed during removal or conversion of the BMPs shall be stabilized immediately. In order to ensure rapid revegetation of disturbed areas, such removal/conversions are to be done only during the germinating season.
- 30. Upon completion of all earth disturbance activities and permanent stabilization of all disturbed areas, the owner and/or operator shall contact the local conservation district to schedule a final inspection.
- 31. Failure to correctly install E&S BMPs, failure to prevent sediment—laden runoff from leaving the construction site, or failure to take immediate corrective action to resolve failure of E&S BMPs may result in administrative, civil, and/or criminal penalties being instituted by the Department as defined in Section 602 of the Pennsylvania Clean Streams Law. The Clean Streams Law provides for up to \$10,000 per day in civil penalties, up to \$10,000 in summary criminal penalties, and up to \$25,000 in misdemeanor criminal penalties for each violation.
- 32. All channels shall be kept free of obstructions including but not limited to fill, rocks, leaves, woody debris, accumulated sediment, excess vegetation, and construction material/wastes.
- 33. Underground utilities cutting through any active channel shall be immediately backfilled and the channel restored to its original cross-section and protective lining. Any base flow within the channel shall be conveyed past the work area in the manner described in this plan until such restoration is complete.
- 34. Channels having stone linings must be sufficiently over-excavated so that the design dimensions will be provided after placement of the protective lining.

#### Staging of Earthmoving Activities

REFER TO THE EROSION AND SEDIMENTATION CONTROL PLAN PREPARED FOR THE HARNER FARM FOUR LOT SUBDIVISION AND SHEETZ STATE COLLEGE, PA (WHITEHALL ROAD PLAN) FOR CONSTRUCTION STAGING RELATED TO THE SEDIMENT BASIN AND STORMWATER MANAGEMENT DETENTION AND INFILTRATION BASIN CONSTRUCTION. CONSTRUCTION OF RESIDENTIAL SUBDIVISION ROADWAY AND INFRASTRUCTURE CAN OCCUR CONCURRENTLY WITH THE SHEETZ STATE COLLEGE, PA (WHITEHALL ROAD PLAN) THE SEDIMENT BASIN SHALL REMAIN OPERATIONAL AND BE MAINTAINED UNTIL THE APPROPRIATE STABILIZATION FOR BOTH PROJECTS IS ACHIEVED. LIKEWISE, ALL OTHER BASINS SHALL REMAIN AT THEIR INTERIM ELEVATIONS UNTIL THE APPROPRIATE STABILIZATION OF UPSLOPE AREAS IS ACHIEVED. SUCH STABILIZATION IS DEFINED IN CONSTRUCTION STAGING STEP 'I' OF THE SHEETZ STATE COLLEGE. PA (WHITEHALL ROAD PLAN.) FINAL CONVERSION OF ALL SEDIMENT AND STORMWATER BASIN FACILITIES CAN OCCUR PRIOR TO INDIVIDUAL RESIDENTIAL LOT CONSTRUCTION. INDIVIDUAL RESIDENTIAL LOT CONSTRUCTION MAY SHALL OCCUR WITH SPECIFIC ON-LOT CONTROLS IN PLACE.

Sequence: All earth disturbance activities shall proceed in accordance with the following staging of earthmoving activities. Each stage shall be completed before a subsequent stage in initiated.

- A. Install the rock construction entrances for Apple View Drive public roadway at the locations shown on the Erosion and Sedimentation Control Plan (E&SCP).All controls installed as a part of the Harner Farm Four Lot Subdivision Plan shall be inspected, repaired/replaced immediately as necessary and continue to be implemented and maintained throughout construction of this project
- B. Commence with any necessary subgrade work from where the Harner Farm Four Lot Subdivision Plan left off. As fill is needed within the site development area, it shall be removed and relocated onsite where necessary from the Material Borrow Area.
- Commence with construction of all utilities. All utilities are to be installed at the rate of the length of the utility that can be installed and backfilled in one day. All stormsewer shall be installed beginning at the downstream end and working upstream. Inlet protection shall be placed immediately on all newly installed inlets and outlet protection installed at outlets.
- Continue with the roadway construction until all utilities are installed. Bring to sub grade and stabilize with stone.
- Continue with all site grading. Stabilize all vegetated areas, which shall include the Material Borrow Area, with topsoil and the appropriate seeding mixture immediately after they are brought to final grade. Install the appropriate erosion control lining, where shown on the E&SCP.
- Begin the paving operations, thus removing the rock construction entrances. All curbing and sidewalks shall also be installed. Check all erosion controls on a daily basis and make any needed repairs or replacements as needed immediately. Any erosion control disturbed or removed by the
- installation of utilities shall be repaired or replaced to proper functioning condition by the end of that same day. All areas abandoned for more than four (4) days are to be seeded with the temporary seeding mixture. H. So long as the NPDES Permit for the site is maintained, Detention Basin A shall remain a sediment basin and Infiltration Basin 1 remain at it's interim elevation
- and be maintained in place until full construction of Sheetz and Apple View Drive are complete to permanent stabilization. Should construction of Sheetz fail to occur or cease at any time, permanent stabilization of all disturbed areas (including the conversion of Basin A and Infiltration Basin 1) shall occur as indicated in Stage I below and temporary controls shall be removed as indicated in Stage I.
- Current regulations state: (a) Upon completion of an earth disturbance activity or any stage or phase of an activity, the site shall be immediately seeded, mulched or otherwise protected from accelerated erosion and sedimentation. (b) Erosion and sediment control BMP's shall be implemented and maintained until the permanent stabilization is completed. (c) For an earth disturbance activity or any stage or phase of an activity to be considered permanently stabilized, the disturbed areas shall be covered with one of the following: (1) A minimum uniform 70% perennial vegetative cover, with a density capable of resisting accelerated erosion and sedimentation. (2) An acceptable BMP which permanently minimizes accelerated erosion and sedimentation. Once stabilization has been achieved, all temporary erosion and sediment controls may be removed as follows:
  - Finalize Infiltration Basin 1 and install the GrowSoxx Forebay Berm. Convert the Detention Basin A from a sediment facility. Remove all sediment and the skimmer. Install the 8" riser and trash rack onto the 6" pipe, once the skimmer is removed. Finalize the outlet structure to its permanent configuration, as per the stormwater details. Place topsoil over all remaining areas in the basin. Apply the appropriate permanent seeding to all disturbed areas of the
  - Remove all remaining temporary controls, such as silt sock, topsoil stockpiles and inlet protection. Any areas disturbed by the removal of these controls shall be stabilized immediately with a permanent seeding mixture.
- J. Upon stabilization of all disturbed areas, individual lot construction may proceed by the individual lot owners/builders with specific on—lot controls.

#### Construction for the individual lots shall proceed with the following sequence:


- A. The proposed driveway entrance area will be stabilized with AASHTO #1 stone as shown in the construction entrance detail. The proposed silt sock is to be installed as shown on the typical on—lot erosion controls details depending on drainage direction. A minimum 12"silt sock must be installed along the downslope end of all disturbed area associated with the driveway construction.
- B. The proposed lawn area will have the topsoil stripped and stockpiled as shown on the typical on-lot erosion controls details. The stockpiles will be stabilized with the temporary seeding mixture.
- C. The building foundation will be constructed.
- D. Utilities will be installed. Any facilities crossing temporary erosion control facilities will be installed and completed in one day and the control facility must be restored that same day.
- E. As building construction proceeds, lawn areas shall be brought to final grade and topsoil placed. All lawn areas shall be seeded andmulched as per the rates shown in the section labeled "PERMANENT CONTROL MEASURES". All slopes 3:1 and steeper shall be stabilized with Curlex I (or equal) erosion control lining.
- F. As construction proceeds, temporary erosion control facilities will be maintained as specified in the maintenance program included in this report. All areas abandoned for more than four (4) days are to be seeded with the temporary seeding mixture.
- G. When construction is complete and the area stabilized with pavement or a uniform 70% vegetative cover over the entire disturbed area, all temporary erosion and sediment control measures will be removed.


#### Temporary Control Measures


Temporary control measures will be implemented to ensure that erosion is minimized and that sediment is retained during construction. The rock construction entrance will be provided at the site entrance to prevent tracking of sediment from the site. Silt sock will be placed at the locations shown on the Erosion and Sedimentation Control Plan to provide proper filtration of the site runoff. Inlet protection will be installed at inlets to prevent the sedimentation of the storm sewer systems. A sediment basin will filter site runoff. Stone diversion swales will ensure runoff iis adequately directed to the sediment basin.

Temporary seeding on all disturbed areas shall be done immediately after grading is finished and shall consist of the following:

1. Agricultural grade limestone 1 ton / acre 2. Fertilizer 10-10-10 500 lbs. / acre 3. Annual ryegrass 40 lbs. / acre 4. Mulch (straw) 3 tons / acre







TYPICAL ON-LOT EROSION CONTROL

NOT TO SCALE

#### **Permanent Control Measures**

Permanent control measures include the storm sewer, curbing, basins, swales and seeding / landscaping.

Permanent seeding on all disturbed areas may consist of the following:

Soil Enhancements: For permanent seeding outside of the basin bottom, it is recommended that site specific soil testing be performed. Lieu of soil test recommendations, use the following acceptable schedule:

Apply 6 tons/acre (240 lbs/1,000 s.f.) Dolomoitic Limestone and 1,000 lbs/acre (25 lbs/1,000 s.f) of 10—20—20 fertilizer before seeding. Harrow or disc into upper three inches of

Permanent seeding on all basin bottom areas may consist of the following: Permanent seeding on all other disturbed areas may consist of the following:

1. Seed Mixture Consists of:

50% Poa pratensis (Kentucky Bluegrass) 30% Festuca rubra (Creeping Red Fescue)

102 lbs. / acre 20% Lolium perenne L. (Perennial Rye) Mulch 3 tons / acre

For lawn areas, a suitable lawn mixture, such as Agway's Royal Green, shall be substituted for Item 3 of the permanent seeding mixture and applied at the rate directed by the

\*Mulching: Apply mulch immediately after seeding and anchor properly with an anchoring tool or following one of the methods listed below.

1) Tracking: The process of cutting mulch into the soil via equipment that runs n tracks, is employed primarily on slopes 3:1 or steeper.

- 2) Mulch Nettings: Staple lightweight biodegradable paper, plastic or cotton netting over the mulch according to the manufacturer's recommendations. 3) Synthetic Binders: Synthetic binders such as acrylic DLR (AGRI—TAC), DCA—70, Petroset or Terratack may be used at rates recommended by the manufacturer to anchor mulch
- 4) Wood Cellulose Fiber: The fiber binder shall be applied at a net dry weight of 750 lb/acre. The wood cellulose fiber shall be mixed with water, and the mixture shall contain a
- maximum of 50 lbs of wood cellulose fiber per 100 gallons.
- 5) Peg & Twine: Drive 8 to 10 inch wooden pegs to within 2 to 3 inches of the soil surface every 4 feet in all directions. Stakes may be driven before or after applying mulch. Secure mulch to surface by stretching twine between pegs in a criss—cross within a square pattern. Secure twine around each peg with two or more turns.

#### Maintenance Program

During construction, the contractor will be responsible for maintenance and repair of all erosion and sedimentation control facilities. These facilities should be inspected weekly and after every runoff event. Any erosion control disturbed during construction or found to be inadequate upon inspection shall be repaired or replaced within 24 hours after the disturbance or the discrepancy is discovered. All inspections and repairs shall be documented within a written report and retained for record keeping. The maintenance of the erosion control facilities will include the following:

a. The entrance shall be maintained in a condition that will prevent tracking or flowing of sediment onto public rights—of—way. This may require periodic top dressing with additional stone as conditions demand and repair and/or cleanout of any measure used to trap sediment. All sediment spilled, dropped, washed or tracked onto public rights—of— Any section of the filter fabric fence which has been undermined or topped must be immediately replaced with a rock filter outlet.

a. Sediment shall be removed from the structure and spread over an existing stockpile with controls already in place, or spread over an existing windrow and seeded with the temporary seeding

a. The structure should be checked regularly to ensure its soundness. If the stone filter has been disturbed and cannot perform its proper protective function, additional stone should be installed to provide adequate filtration.

a. All sediment removed from erosion and sedimentation pollution control facilities shall be spread over spoil areas with controls already in place. Stabilize the spoil material with the temporary

#### seeding mixture.

a. If the vegetative cover is not established uniformly by the third mowing, the contractor shall reapply topsoil if necessary and seed and mulch as needed to provide adequate cover.

#### Silt Socks:

a. The Contractor shall maintain the socks in a functional condition at all times and it shall be routinely inspected. b. Where the sock requires repair, it will be routinely repaired.

c. The contractor shall remove sediment collected at the base of the sock when they reach 1/2 of the exposed height of the sock, or as directed by the Engineer. Alternatively, rather than create a soil disturbing activity, the engineer may call for additional sock to be added at areas of high sedimentation, placed immediately on top of the existing sediment laden sock. The sock will be dispersed on site when no longer required, as determined by the Engineer.

a. The sediment basin shall be stabilized with the temporary seeding mixture and maintained to ensure that it is structurally sound at all times. Sediment accumulation within the sediment trap shall be removed when it reaches the clean-out storage elevation as indicated on the E&SCP.

#### Recycling and Disposal of Materials

The operator shall remove from the site, recycle, or dispose of all building materials and wastes in accordance with the Department's Solid Waste Management Regulations at 25 PA. Code 260.1et seg., 271.1 et seg., and 287.1 et seg. The contractor shall not illegally bury, dump, or discharge any building material or wastes.

Wastes generated during the construction of this project shall be recycled if at all possible. Any materials that cannot be recycled or reused shall be disposed of at a Pennsylvania Department of Environmental Protection approved landfill. If soil and/or rock disposal areas are required, erosion and sedimentation controls shall be implemented at these areas. Any excess soil waste may only be disposed of at an approved E&S/NPDES permitted site.

#### Responsibillies for Fill Materials

The contractor is responsible to use environmental due diligence to ensure any fill material required to be imported to or exported from the site qualifies as Clean Fill.

Clean Fill is defined as: Uncontaminated, non-water soluble, non-decomposable, inert, solid material. The term includes soil, rock, stone, dredged material, used asphalt, and brick, block or concrete from construction and demolition activities that is separate from other waste and is recognizable as such. The term does not include materials placed in or on the waters of the Commonwealth unless otherwise authorized. (The term "used asphalt" does not include milled asphalt or asphalt that has been processed for re—use.)

Environmental due diligence: Investigative techniques, including, but not limited to, visual property inspections, electronic data base searches, review of property ownership, review of property use history, Sanborn maps, environmental questionnaires, transaction screens, analytical testing, environmental assessments or audits. Analytical testing is not a required part of due diligence unless visual inspection and/or review of the past land use of the property indicates that the fill may have been subjected to a spill or release of regulated substance. If the fill may have been affected by a spill or release of a regulated substance, it must be tested to determine if it qualifies as clean fill. Testing should be performed in accordance with Appendix A of the Department's policy "Management of Fill".

Fill material that does not qualify as clean fill is regulated fill. Regulated fill is waste and must be managed in accordance with the Department's municipal or residual waste regulations based on 25 Pa. Code Chapters 287 Residual Waste Management or 271 Municipal Waste Management, whichever is applicable.



#### CENTRAL PENNSYLVANIA **REGION OFFICE:**

3075 ENTERPRISE DRIVE SUITE 100 STATE COLLEGE, PA 1680 PH: 814-231-8285 Fax: 814-237-2308


#### LANCASTER REGION OFFICE: 3904 B ABEL DRIVE COLUMBIA, PA 17512 PH: 717-522-5031

#### Fax: 717-522-5046 WWW.PENNTERRA.COM

COPYRIGHT 2020 BY THE ENGINEE! THE INFORMATION CONTAINED HEREON MAY NO BE USED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF THE ENGINEER except as otherwise provided by appropriat

© PENNTERRA ENGINEERING 2020 ALL RIGHTS RESERVED

LAWS OR STATUTES.



Draftsman Proj.Manager Perimeter Ck. 17125-RESIDENTIAL-SUB-ES-NAR

03/25/20 REVISED PER FERGUSON TOWNSHIP COMMENTS 01/31/20 REVISED PER FERGUSON TOWNSHIP 10/03/19 REVISED PER FERGUSON TOWNSHIP 08/07/19 REVISED PER FERGUSON TOWNSHIP COMMENTS Description REVISIONS

ERGUSON TOWNSHIP

CENTRE COUNTY


PENNSYLVANIA

ORCHARD VIEW

**PRELIMINARY** SUBDIVISION PLAN

**EROSION & SEDIMENTATION** NARRATIVE &

MAY 14, 2019



				<u> </u>	<u> </u>
	/	~/////		GEOTEX	TILE
	_	ECTION	<u>A-A</u>	ADDON	
	RIP	RAP		APRON	
PIPE				INITIAL	TERMINAL
DIA Pd (IN)	SIZE (R)	THICK. Rt (IN)	LENGTH AI (FT)	WIDTH Aiw (FT)	WIDTH Atw (FT)
36	R-5	27	20	9.00	29.00

	•										
	aprons the ap				<u>and</u>	after	each	runoff	event.	Displaced	riprap

1. All aprons shall be constructed to the dimensions shown. Terminal widths shall be adjusted as


OUT-A2-A3


necessary to match receiving channels.

3. Extend riprap on back side of apron to at least ½ depth of pipe on both sides to prevent scour around the pipe.

#### RIPRAP APRON NOT TO SCALE


----PVC CLEANOUT DOOR TOP OF CLEANOUT OPTION 1 BOTTOM OF CLEANOUT OPTION 1 BOTTOM OF CLEANOUT OPTION 2 — ALUMINUM J STRAP — ORIFICE PLATE (5" DIA.)







SKIMMER-CONSTRUCTED WITH HARNER FARM FINAL SUBDIVISION PLAN


SEDIMENT BASIN CROSS SECTION - CONSTRUCTED WITH HARNER FARM FINAL SUBDIVISION PLAN NOT TO SCALE



CONSTRUCTION ENTRANCE NOT TO SCALE







NOTES:

1. INSTALL ON FLAT GRADE FOR OPTIMUM PERFORMANCE 2. CONCRETE WASHOUT MAY BE STACKED IN A PYRAMIDAL CONFIGURATION FOR ADDED HEIGHT AND STABILITY 3. CONCRETE WASHOUT MAY BE DIRECT SEEDED AT THE TIME OF INSTALLATION


4. A SUITABLE IMPERVIOUS GEOMEMBRANE SHALL BE PLACED AT THE LOCATION OF THE WASHOUT PRIOR TO INSTALLING THE FILTER SOCKS.

CONCRETE WASHOUT AREA

NOT TO SCALE

DROP INLET FILTER W/ EARTHEN BERM (TYPE C) NOT TO SCALE

FILTERED WATER




Fax: 814-237-2308

LANCASTER **REGION OFFICE:** 3904 B ABEL DRIVE COLUMBIA, PA 17512 PH: 717-522-5031

Fax: 717-522-5046 **WWW.PENNTERRA.COM** 

COPYRIGHT 2020 BY THE ENGINEE! THE INFORMATION CONTAINED HEREON MAY NO BE USED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF THE ENGINEER EXCEPT AS OTHERWISE PROVIDED BY APPROPRIAT LAWS OR STATUTES.

© PENNTERRA ENGINEERING 2020 ALL RIGHTS RESERVED



Draftsman Proj.Manager Perimeter Ck. Adod125-RESIDENTIAL-SUB-ES-DT

==

1/4" OPENING (MAX.)

\*COMPOST SHALL BE NETTED OR OTHERWISE SECURED

PIPE SECTION

---WIRE MESH

1/4" OPENING (MAX.)

SECTION

6" MIN HEIGHT

FILTERED WATER

—AASHTO No. 57 OUTLET PROTECTION

PIPE SECTION

RUNOFF WATER -

AASHTO #57— (6" MIN. DEPTH)

6" MIN HEIGHT

03/25/20 REVISED PER FERGUSON TOWNSHIP COMMENTS

FERGUSON TOWNSHIP CENTRE COUNTY PENNSYLVANIA

PRELIMINARY SUBDIVISION PLAN

EROSION & SEDIMENTATION CONTROL

> PROJECT NO. 17125

01/31/20 REVISED PER FERGUSON TOWNSHIP COMMENTS 10/03/19 REVISED PER FERGUSON TOWNSHIP COMMENTS 08/07/19 REVISED PER FERGUSON TOWNSHIP COMMENTS REVISIONS ORCHARD VIEW

DETAILS

MAY 14, 2019 N.T.S.

